

Educational Suitability Summary Report

Murchison Middle School

Date: 02/02/2021 Score 60% Average

Murchison Middle School, serving a student enrollment of approximately 1,250 students in northwest Austin, is known for its International Baccalaureate Middle Years program as well as being a pathway for multiple CTE programs and Project Lead the Way that can feed into Anderson High School.

Through the 2017 bond program, the original campus is getting multiple upgrades and modernizations that include the media center, administrative suite and new teacher Professional Learning Centers (PLCs). A new three-story studio building was also added. The media center is spacious with technology and flexible furniture. The new studio addition includes science labs, maker spaces, studios and collaboration areas. The new addition has ample transparency and flexible furniture to support individual and group learning.

The following departments were not included in the modernization project: athletics, performing arts and CTE. The gymnasiums are small, lack sufficient storage and the wood floors are damaged from a water leak. The band and orchestra rooms are too small with too few practice rooms shared between them. Choir is currently on the other side of the campus away from the other performing arts programs. The CTE program is extensive, offering courses in engineering, business management, computer science, web design and graphic design for high school credit. After the 2017 bond construction work ends, the entire CTE department will be in portable buildings.

A greenhouse and garden are well maintained but there are no true outdoor learning studios. There are some areas that could work as outdoor studios if furniture and shade structures are provided, and a secured perimeter is added. The property includes a park, kickball fields, and City of Austin community pool directly adjacent, which are all used by the surrounding community.

Interview Overview

The assessment team interviewed Principal Beth Newton and Librarian Christy Cochran to discuss Murchison Middle School. The administrators emphasized the identity of the school in the front arches and other exterior elements that include dedication areas for past staff and faculty, oak trees and dedicated bricks in the courtyard. The exterior has a few outdoor areas that could be used for learning, have proper furniture or access to Wi-Fi.

The administration is very happy with the new building and the media center modernizations. The

Educational Suitability Summary Report

Murchison Middle School

building features open collaboration areas they are using as learning studios. Professional development may be needed to fully utilize these new spaces. They stated that there are still not enough PLCs, and they are far apart, forcing teachers to travel across campus for planning. The existing building studios are too small to function for bigger groups or provide flexibility.

The campus is most concerned with the following areas: athletics, performing arts, CTE programs, existing science labs and special education. There is not a separate entrance for gym events or performing arts events. Both spaces lack enough space to fully function for their enrollment. The main issues of the gymnasiums are size, storage, damaged wood flooring and no separate, secured entry. The band and orchestra areas are too small and there is not a place for all the programs to perform together with roughly 300 students. The choir is separate from the band and orchestra and located on the other side of the campus. All performing arts areas are outdated and need updated acoustical treatments. Once the CTE program moves to all portable buildings it will not have access to large group areas, flexibility or integration with the rest of the campus. The special education room has not been updated and is located next to performing arts away and from other learning studios and the administration suite. The existing science labs are outdated. The furniture is in very bad shape and some of the sinks are not working.

Assessment Findings

The Educational Suitability Assessment of Murchison Middle School earned a 60% overall score and places the campus in a category of Average. The assessment consists of seven General Building categories and eight Academic categories to determine areas that need more attention.

Unsatisfactory Categories (36-50%):

Outdoor Learning and Activity

Score is unsatisfactory.

There are little to no outdoor learning studios. The areas that could be an are not shaded. There is a greenhouse and gardens, but they are not close to the studios.

General Building

Score is unsatisfactory.

After the modernization and new addition, the campus will still lack a community room. The gym, library and cafeteria cannot be secured from the rest of the building for after-hours activities.

Visual and Performing Arts

Score is unsatisfactory.

The band hall is sized per Ed Specs, but Aux Band Hall is undersized. Orchestra, choir, dance rooms are undersized and lack sufficient storage per the education specifications. Spaces are not interconnected with large group spaces and cannot be used by the entire community. No transparency to share or display fine arts program work and no access to outside.

Food Services

Score is unsatisfactory.

Cafeteria seating includes outdated finishes and furniture (tables with attached stools). The cafeteria is undersize but has an adjacent courtyard for outdoor dining. The cafeteria houses the performance

Educational Suitability Summary Report

Murchison Middle School

stage, which is 600 square feet undersized per the education specification and is not suitable for performing arts events.

Technology

Score is unsatisfactory.

Technology meets the educational specifications in the new building and the newly renovated media center. All other areas in the existing building lack sufficient plugs and charging stations. The campus has digital media signage in the reception area and a large projection screen and ceiling-mounted projector in the cafeteria.

Average Categories (51-65%):

Controllability of Systems

Score is average.

Thermostats do not allow individual control in the existing campus. Lighting and lighting controls meet the educational specifications in the new building, but the existing building has single-switch lighting, and some blinds need to be replaced to control daylighting.

Furniture, Fixtures, Equipment

Score is average.

Furniture has been updated in the media center, administrative suite and the new studio building. All other areas have attached desks and seats in the studios and tables with attached stools in the dining commons. They cannot be easily moved or reconfigured.

CTE and Career Connected Learning

Score is average.

Murchison is aligned with a CTE cluster pathway and this score measures the current courses being offered. The entire CTE program is being relocated to portables and will not have access to large group gathering space or flexibility and proximity to the learning spaces.

Athletics and Wellness

Score is average.

Gyms and support spaces are too small. Wood flooring is damaged. Space is not multifunctional and does not ensure sufficient circulation for large numbers of learners to access efficiently.

Satisfactory Categories (66-80%):

Academics & Learning

Score is satisfactory.

Classroom sizes and transparency in the new building meet the educational specifications. Classrooms in the existing building are undersized with limited transparency through a narrow window in the door. Storage is insufficient in the existing building and there are no group rooms.

Exterior

Score is satisfactory.

The exterior of the building has signage on the building and at the main intersection. The main entry has been moved in the new construction and the school appears to have two entries, which can be

Educational Suitability Summary Report

Murchison Middle School

confusing to visitors. There is separation of vehicular traffic, but site is small and crowded.

Security

Score is satisfactory.



Environmental Quality

Score is satisfactory.

All studios in both the new construction and the existing building have at least one exterior window. The media center and the cafetorium need acoustical enhancements to function better. Blinds need to be replaced in the existing building. Principal noted some rodent problems.

Very Satisfactory Categories (81-100%):

Media Resources


Score is very satisfactory.

Newly renovated media resource center has ample space, group rooms, flexible furniture and access to technology.

Administration Spaces

Score is very satisfactory.

Newly renovated administrative space has open, large reception area with new furnishings. Acoustics are good and there is a conference room off the main reception. Counselors' offices are in the previous administrative suite and need acoustical improvements, which is a big need for the school.



Original entry with arches. Can confuse visitors since this is no longer the main entry.



New Media Center with collaborative furniture, nice lighting, large space.



Cafeteria has only one type of furniture and needs acoustical enhancements.



Outdoor dining area is large and has shade.



Water cistern on-site and working.



Furniture in existing building is outdated and offers only one type, which is not flexible.



Existing Science Labs: Furniture cabinetry is broken, and sinks are not functioning.



Outdoor gardening area is well maintained.



Existing building modernized to have open collaboration in corridors.



Performing arts areas are small and lack enhanced acoustical solutions.



Austin ISD Educational Suitability Assessment Criteria

General Building

School Name	Walk Attendees:	Date:
Murchison Middle School	Angela Whitaker-Williams, Jennifer Hoskins	2/26/2021

- Exterior		1	2	3	4	5	N/A		8.75	69%
1.1 Does the s	site permit desirable separation of vehicular, bus and n traffic?			3				Comments	1.00	3.00
1 2 3 4	Very unsatisfactory - Bus, car and pedestrian all happen at the same location Unsatisfactory - Cars and buses mix, pedestrians are separated Average - Buses, cars, and pedestrians are separate but stack space is small Satisfactory - Buses, cars, and pedestrians are separate but drop off does not have a canopy or a holding place like a commons or cafeteria Very satisfactory - Buses, cars, and pedestrians are separate separate and drop off area has a canopy and							Canopy is missing from bus loop. Will be added in Phoschool).	ase 2 (accordir	ng to
N/A	Does not apply		1			1				
12	ding easily identified with appropriate signage and ty wayfinding?				4			Comments	0.25	1.00
1 2 3 4 5	Very unsatisfactory - Campus has no signage / wayfinding Unsatisfactory - Signage/wayfinding is faded/hidden Average - Signage / wayfinding visible but not apparent Satisfactory - Signage / wayfinding is visible but not good condition Very satisfactory - Signage and wayfinding is visible and easy to use							Signage is in good condition but there are two main e one that is no longer used and the newly constructed to identify which one to use.		•
N/A	Does not apply									

O2/11/2022 ²

1 - E	xterior (cor	nt.)	1	2	3	4	5	N/A	A		
1.3	ls the dump	oster accessible for trash / compost disposal?				4			Comments	0.50	2.00
	1 2 3 4 5	Very unsatisfactory - No compost present, route has obstacles (stairs, curbs, barriers) to dumpster Unsatisfactory - Compost is present. Route has obstacles to dumpster Average - Compost is present (<100' to cafeteria), Route to dumpster is free and clear but the two are not directly adjacent. Satisfactory - Compost and dumpster are directly adjacent and route is barrier free Very Satisfactory - Compost and dumpster are directly adjacent and route is barrier free. Dumpster are shaped / positioned so people of all heights can access it.							One set of dumpsters outside of cafeteria is accessib	e. Other set is	not.
	N/A	Does not apply	_	_	_		_				
2 - 0		arning and Activity	1	2	3	4	5	N/A	4	10.00	40%
2.1	Are outdoo the ed spec	r studios and support spaces appropriately configured per ?			3				Comments	1.00	3.00
	1	Very unsatisfactory - No dedicated outdoor studios							Areas are nice and located under trees but no shade	structure. New	/
	2	Unsatisfactory - Too small, poor condition, disconnected							building has outside areas on each floor that are cov	ered but no fu	rniture.
		from learning spaces, no flexibility, no shade provided							Wi-Fi access is a problem and need writable surfaces	s. There is a	
	3	Average - Adequate size, adequate condition, needs some renovations or updates to function well, 50% or less							greenhouse and gardens that are well kept.		
	4	shade coverage over studio area Satisfactory - Good size, good condition, connected to learning spaces, good flexibility, more than 50% shade coverage over studio area							Outdoor spaces are not secure.		
	5	Very satisfactory - Generous size, excellent condition, connected to learning spaces, excellent flexibility, full shade coverage over studio area									
	N/A	Does not apply									
2.2		olaygrounds (elementary only) and support spaces per the ed spec?						N/A	Comments	0.00	0.00
	1	Very unsatisfactory - No dedicated active playground									
	2	Unsatisfactory - Too small, poor condition, no shade									
	0	provided									
	3	Average - Adequate size, adequate condition, needs some renovations or updates to function well, 50% or less									
	4	shade coverage over play structure Satisfactory - Good size, good condition, more than 50% shade coverage over play structure									
	5	Very satisfactory - Generous size, excellent condition, full shade coverage over play structure									
	N/A	Does not apply									

2 - C	Outdoor Le	arning and Activity (cont)	1	2	3	4	5	N/A	4		
2.3		s and support spaces appropriately configured per the ed uation on infrastructure not condition of plants)			3				Comments	0.00	0.00
	1 2	Very unsatisfactory - No dedicated gardens Unsatisfactory - Too small, poor condition, disconnected from learning spaces, no flexibility, no accessible water source							Monitoring answer, does not affect score for Outdoor Activity. Greenhouse and gardens are great but not a spaces. They will be moved during Phase 2.	•	
	3	Average - Adequate size, adequate condition, needs some renovations or updates to function well, water source is difficult to access									
	4	Satisfactory - Good size, good condition, connected to learning spaces, good flexibility, water source is accessible with 100 ft hose									
	5	Very Satisfactory - Generous size, excellent condition, connected to learning spaces, excellent flexibility, water source is less than 50ft from the garden or has irrigation									
	N/A	Does not apply									
2.4	Are the rained spec?	gardens and/or cisterns appropriately configured per the				4			Comments	0.00	0.00
	1 2 3	Very unsatisfactory - No rain gardens or cisterns Unsatisfactory - Too small, poor condition, not functioning, disconnected Average - Adequate size, adequate condition, is connected, needs some renovations or updates to function well Satisfactory - Good size, good condition, functions							Monitoring answer, does not affect score for Outdoor Activity. One by garden will need to be moved in pha	_	
	5 N/A	properly Very Satisfactory - Generous size, excellent condition, exceptional functionality, connected to learning spaces, educational signage provided Does not apply									
2.5		hool have animal husbandry? (optional)	1						Comments	0.00	0.00
	1 5	No Yes		ı			ı				
2.6	Does the so	hool have nature loop trails? (optional)	1						Comments	0.00	0.00
	1 5	No Yes		-							
2.7	Does the so	hool have a learning pond? (optional)					5		Comments	0.00	0.00
	1 5	No Yes									
2.8	Does the so	hool have a grass play field and walking trail?	1						Comments	1.00	1.00
	1	No									
	5	Yes									

3	- General Building			2	3	4	5	N/A	Ą	11.25	42%
	3.1 Are interio	circulation routes wide enough to safely and effectively				4			Comments		
	accommod	late student movement?				7			Comments	0.50	2.00
	1	Very unsatisfactory - Primary circulation is 5'-0" to 6'-0"							Hallways range in size from 7'-4" to over 10'.		
		wide									
	2	Unsatisfactory - Primary circulation is 6'-0" to 7'-0" wide							Principal notes - Interior hallways near original class	rooms are rathe	er
	3	Average - Primary circulation is 7'-0" to 8'-0" wide							narrow. Would be renovated in Phase 2.		
	4	Satisfactory - Primary circulation is 8'-0"-10'-0" wide									
	5	Very satisfactory - Primary circulation is 10'-0"+ wide									
	N/A	Does not apply									
	Are commu	unity use areas arranged so that the school can allow night	,						Community		
	3.2 functions v	vithout full school access?	ı						Comments	0.75	0.75
	1	Very unsatisfactory - Cafeteria, gym, and library cannot							The cafeteria, gyms and library can't be secured from	n the rest of the	;
		be accessed after hours							building for after-hours activities.		
	2	Unsatisfactory - Only one of the public spaces (Cafeteria,									
		Gym and Library) can be accessed from parking and									
	•	secured after hours									
	3	Average - Only two of the public spaces can be accessed from parking and secured after hours									
	4	Satisfactory - All of the public spaces can be accessed									
	7	from parking and secured from the rest of the building									
		but not individually									
	5	Very satisfactory - Cafeteria, gym, and library can be									
		accessed from parking and locked off from rest of									
		campus for night/evening use with their own entrance									
	N/A	Does not apply									
	ls there a c	ommunity room that is a dedicated meeting space outside	,						Community		
	3.3 of school for	unction?	ı						Comments	0.75	0.75
	1	Very unsatisfactory - No dedicated community room							Phase 2 master plan has community room and new o	athletic space w	/ith
	2	Unsatisfactory - Community room but within school							evening access.		
		function, no access after school hours									
	3	Average - Community room, moderate size, but need									
	4	some renovations or updates to function well									
	4	Satisfactory - Community room, good size /layout, meets needs /functions well									
	5	Very Satisfactory - Community room, generous size, nice									
	· ·	condition, functions appropriately outside of school									
		function									
	N/A	Does not apply									
	3.4 Does the g	eneral appearance of the school convey pride for the					5		Comments		
	students a	nd community?								0.25	1.25
	1	Very unsatisfactory - General appearance is poor							New addition of campus looks great and has lots of	learning on disp	olay.
	2	Unsatisfactory - General appearance is aged but ok							Existing areas have display for student work.		
	3	Average - General appearance is good									
	4	Satisfactory - General appearance shows pride in									
	5	campus and student works									
	J	Very Satisfactory - General appearance shows pride in campus and student works and is welcoming to the									
		community									
	N/A	Does not apply									

4 - Security		1 2	2	3 4	1	5 N//	A	16.25	
4.1 Does the fa	cility have key card access at all major entries?						Comments		
1	Very unsatisfactory - No entries								
2	Unsatisfactory - 1/4 of major entries								
3	Average - 1/2 of major entries								
4	Satisfactory - 3/4 of major entries								
5	Very satisfactory - All of major entries								
N/A	Does not apply								
4.2 How adequ	rate is site lighting and security for the campus overall?						Comments		
1	Very unsatisfactory - No exterior lighting, no secure perimeter								
2	Unsatisfactory - Lighting is limited to front entry only, parking lot lighting poor, security is minimal								
3	Average - Lighting at all night-use entries and parking lot, but poor condition. Security is moderate								
4	Satisfactory - Lighting at all night-use entries and								
	parking lots, good condition, signage less visible,								
	perimeter is well secured but needs updates								
5	Very satisfactory - Signage, parking lots, and entries are well lit, visible and easy to use, perimeter is very secure								
N/A	Does not apply								
ls the main	office located at the school entry and configured with a						Community		
4.3 secure vesti	bule to the main corridor?						Comments		
1	Very unsatisfactory - No secure vestibule, office located								
	far from main entry, allows visitors access to school								
•	unsupervised								
2	Unsatisfactory - No secure vestibule, office located								
	somewhat far from main entry, minimal supervision of								
3	visitors Average - Office close to entry, views of front door, but								
3	no secure vestibule								
4	Satisfactory - Office is well-located with a secure								
·	vestibule, but needs updates								
5	Very satisfactory - Office well-located with secure								
	vestibule and all appropriate security features								
N/A	Does not apply								
	ough interior transparency for faculty to passively supervise d their activities who are not in studios?			3			Comments	1.00	3.00
1	Very unsatisfactory - No transparency of walls						New construction has lots of transparency. Exist	ting building does not.	
2	Unsatisfactory - Limited transparency in certain locations								
3	Average - Good transparency in certain locations but								
	inadequate or missing in other locations of school								
4	Satisfactory - Adequate transparency throughout the								
	school								
5	Very satisfactory - Excellent transparency throughout the school								
N/A	Does not apply								

Perkins&Will 02/11/2022 ⁶

5 - Environmental Quality	1	2	3	4	5	N/A		25.00	72%
5.1 How are acoustics in studios in general?			3				Comments	1.00	3.00
1 Very unsatisfactory - Recognized word/sound from adjacent studio/corridor 2 Unsatisfactory - Audible sound from adjacent studio/corridor 3 Average - Slight sound from outside room 4 Satisfactory - Walls to deck insulated only white noise from mechanical system 5 Very satisfactory - Able to hear quiet speaking from across the room N/A Does not apply							Original classrooms have poor acoustics.		
5.2 Is the studio artificial lighting adequate quality?			3				Comments	1.00	3.00
1 Very unsatisfactory - Sporadic lights work, glare, less than 20 FC 2 Unsatisfactory - 10-19 FC or serious glare 3 Average- 20-29 FC minor glare 4 Satisfactory - 30-39 FC and no glare 5 Very satisfactory - 40+ FC and no glare N/A Does not apply									
5.3 Is there access to natural light in studios?					5		Comments	1.00	5.00
1 Very unsatisfactory - No learning spaces have natural light 2 Unsatisfactory - 1-25% of learning spaces have natural light or windows are too small to let in light 3 Average - 26-50% of learning spaces have natural light 4 Satisfactory - 51-75% of learning spaces have natural light 5 Very satisfactory - 76-100% of learning spaces have natural light N/A Does not apply							Some existing rooms do not have natural light.		
2000 постары,					_		Comments		
5.4 Is there access to outside views from learning spaces? 1 Very unsatisfactory - No learning spaces have views					5		Comments	1.00	5.00
Very unsatisfactory - No learning spaces have views Unsatisfactory - 1-25% of learning spaces have views or windows are too small to see out Average - 26-50% of learning spaces have views Satisfactory - 51-75% of learning spaces have views Very satisfactory - 76-100% of learning spaces have views									

Perkins&Will 02/11/2022 ⁷

5 - Env	vironmer	ntal Quality (cont.)	1	2	3	4	5	N/A	4		
5.5	Does the bu	uilding have odor or pest problems?		2					Comments	1.00	2.00
	1	Very unsatisfactory - Evidence of both pests and odors							Principal noted rodent problem(in couseling office) a	nd bad odors f	rom
	2	Unsatisfactory - Evidence of pests or odors							kitchen. Lack of good ventilation in the kitchen.		
	3	Average - Limited evidence of pests, no odors									
	4	Satisfactory - No evidence of pests / odors, school									
		cleanliness in good condition									
	5	Very Satisfactory - No evidence, school cleanliness in									
		excellent condition									
	N/A	Does not apply									
6 - Coi	ntrollabi	lity of Systems	1	2	3	4	5	N/A	4	12.50	52%
6.1	Does the st	udio thermostat allow for individual control?	1						Comments	0.50	0.50
	1	No									
	5	Yes									
6.2 A	Are shades	provided to control natural light in learning spaces?			3				Comments	1.00	3.00
	1	Very unsatisfactory - No, windows are covered with							Existing blinds are in poor shape.		
		boards/paper									
	2	Unsatisfactory - No, windows have no light control									
	3	Average - Yes, but poor condition blinds									
	4	Satisfactory - Yes, blinds									
	5	Very satisfactory - Blackout shades									
	N/A	Does not apply									
6.3 V	What is the	quality of lighting controls in the studios?			3				Comments	1.00	3.00
	1	Very unsatisfactory - Single switch only per room							New addition meets Ed Spec. Existing building has sir	ngle switch per	room.
	2	Unsatisfactory - Alternating rows switch off								·	
	3	Average - Alternating lamps in single fixtures switch off									
	4	Satisfactory - Tri level switching									
	5	Very satisfactory - Dimmable									
	N/A	Does not apply									

7 - Furniture, F	ixtures & Equipment	1	2	3	4	5	N/A		18.75	60%
7.1 What is the	e current condition of the furniture?			3				Comments	0.75	2.25
1	Very unsatisfactory - Damaged or broken, non-							New addition meets Ed Spec. Existing building still ho	as older attache	ed
	functioning							desks and chairs.		
2	Unsatisfactory - Torn/ bent/ wrong size									
3	Average - Scratched/dented/marked									
4	Satisfactory - Not new, but sturdy and clean									
5 N/A	Very satisfactory - New									
N/A	Does not apply		ı			ı	I	Г		
Are a varie	ty of furniture types being accommodated throughout the									
	arning commons, dining commons, other multi-use spaces?			3				Comments		
,								N	1.00	3.00
	Very Unsatisfactory - Same furniture used in all spaces							New additional meets Ed Spec. Existing building has	turniture of one	e type.
2	Unsatisfactory - Furniture variety in one multi-use space									
3	Average - Furniture variety in more than one multi-use									
,	space									
4	Satisfactory - All multi-use spaces have greater than one type of furniture									
5	Very satisfactory - All multi-use spaces have greater than									
	two types of furniture									
N/A	Does not apply									
7.3 How well d	loes furniture accommodate rapid reconfiguration of a			3				Comments	1.00	3.00
1	Very Unsatisfactory - Furniture is fixed or very heavy							Combined average of both the new addition that me	eets Ed Spec an	d the
2	Unsatisfactory - Furniture does not allow desks to be							existing spaces that still have the older furniture that	is large and	
	configured as individuals, small groups, or large groups							cumbersome. Majority of Building A and B has attack	ned chair / desl	k
3	Average - Mix of furniture that can reconfigure but is							combinations.		
4	cumbersome to move Satisfactory - Furniture is flexible for multiple									
-	configurations of space									
5	Very satisfactory - Furniture is flexible for multiple									
	configurations of space, easy to move and stack									
N/A	Does not apply									
7.4 Is the furni	ture ergonomic and size appropriate for grade level?			3				Comments	1.00	3.00
1	Very unsatisfactory - Desk with attached chair					•		Combined average of both the new addition that me	ets Ed Spec an	d the
	combinations too small for grade level							existing spaces that still have the older furniture that	is large and	
2	Unsatisfactory - Desk with attached chair combinations							cumbersome.		
3	Average - Mix of studios with tables/loose chairs and desks with fixed seats									
4	Very satisfactory - Tables with loose chairs									
5	Very satisfactory - Tables with loose chairs Very satisfactory - Tables with loose chairs that allow									
Ĵ	students to be active									
N/A	Does not apply									U

Perkins&Will 02/11/2022 ⁹

ero Waste	1	2	3	4	5	N/A	5.00	90%
Do studios and corridors have blue recycle bins with bilingual instructions and/or image sorting instructions?				4			Comments 0.50	2.00
1 Very unsatisfactory - There are no recycling and landfill bins and signage are sparse or infrequent, OR there are only landfill bins with no recycling bins. 2 Unsatisfactory - Bins and signage are sparse or infrequent and/or lack clear signage. 3 Average - 50% of corridors and studios have both a landfill bin and a recycle bin in an accessible location. The containers have clear signage. 4 Satisfactory - 75% of studios and corridors have a visible landfill and recycle collection containers in an accessible location. The containers have clear signage. 5 Very satisfactory - All studios / corridors (100%) have visible landfill and recycle collection containers in accessible locations. The containers have clear signage, and the style and format is consistent and uniform across campus.							A score for this category is being recorded, but this category is not calculated in the overall ESA average New studios have bins with instructions. Old studios do not.	
N/A Does not apply		•						
Does the cafeteria (or wherever meals are served) have at least one of each: green compost bin, blue recycle bin, and landfill bin? Are the bins labelled clearly with bilingual and/or image sorting?					5		Comments 0.50	2.50
1 Very unsatisfactory- There may be landfill bins, but there are no compost and/or recycle bins. There is not clear sorting signage. 2 Unsatisfactory- Recycle, landfill, and compost bins are present, but the bins are scattered and no co-located next to one another. Signage is absent or inconsistent. 3 Average- There is at least one waste station with all three bins (recycle, compost, landfill) located with close proximity to one another. The signage is visible and consistent. 4 Satisfactory- There are several waste stations as described above 5 Very Satisfactory - There are several waste stations as described above, and additional signage in the cafeteria that encourages recycling/composting. N/A Does not apply								



Austin ISD Educational Suitability Assessment Criteria

Academics - Middle School / High School

	School Na	me							Walk Attendees:	Date:	
	Murchisor	Middle School					_		Angela Whitaker-Williams, Jennifer Hoskins		
		• • •	_				_			(=	
8 - 8	Academics	& Learning	1	2	3	4	5	N/A		65.00	69%
8.1	Are studios	appropriately configured per the ed spec?			3				Comments	1.00	3.00
	1	Very unsatisfactory - Too small, no flexibility,							Existing building undersized at 750 sq, ft. New const	ruction meets Ed	
	2	Unsatisfactory - Too small, only one area for all teaching methods, limited flexibility, disconnected							Specs.		
	3	Neutral - Adequate size, multiple areas for different teaching methods, adequate flexibility, limited transparency and connection to other studios and shared learning spaces, needs updates or renovations to function well.									
	4	Satisfactory - Good size, multiple areas for different teaching methods, good flexibility, good transparency and connection to other studios and shared learning									
	5	Very Satisfactory - Generous size, multiple areas for different teaching methods, excellent flexibility, generous display area and visual teaching tools, excellent transparency and connection with other studios and shared learning spaces									
	N/A	Does not apply									
8.2	Do studios ed spec?	have appropriate support spaces such as storage per the			3				Comments	1.00	3.00
	1	Very unsatisfactory - None provided							Score is averaged between new construction and ex	isting building.	
	2	Unsatisfactory - Too small, disconnected, poor condition									
	3	Neutral - Adequate size, average condition, needs									
	4	updates or renovations to function well Satisfactory - Good size, connected, good condition									
	5	Very Satisfactory - Generous size, connected, excellent condition									
	N/A	Does not apply									

8 - <i>A</i>	cademics	& Learning (cont.)	1	2	3	4	5	N/A	4		
8.3	Do typical	learning neighborhoods have small and medium (high			3				Comments		
0.3	school only	y) group rooms and open collaboration space?			3				Comments	1.00	3.00
	1	Very unsatisfactory - No breakout rooms or open							Score is averaged between new construction and exi	sting building.	Existing
		collaboration spaces are provided							building has no group rooms and open collaborative	spaces.	
	2	Unsatisfactory - Too small or too few, poor condition, no									
		flexibility, lacks visual connection to learning									
		neighborhood, poor acoustic privacy									
	3	Average - Adequate size, adequate condition, needs									
		some renovations or updates to function well									
	4	Satisfactory - Good size, good condition and flexibility,									
		transparency and connection to learning neighborhood,									
		acoustic privacy									
	5	Very Satisfactory - Generous size, excellent condition and									
		flexibility, transparency and connection to learning									
		neighborhood, acoustic privacy									
	N/A	Does not apply		1			1				
8.4		e Labs and support spaces appropriately configured per			3				Comments		
	the ed spe					<u> </u>				1.00	3.00
	1	Very unsatisfactory - No dedicated science room							Existing building: science labs are under square footo	-	
	2	Unsatisfactory - Too small, poor condition, no connected							The furniture is old and sinks do not work. Connected		
		support space							some but not all labs. Fixed lab tables exist in several	rooms - flexib	le
	3	Average - Adequate size, adequate condition, needs							would be preferred. New building: science labs meet	the education	al
		some renovations or updates to function well							specifications.		
	4	Satisfactory - Good size, good condition, connected									
	5	support spaces Very Satisfactory - Generous size, excellent condition,									
	5	connected support spaces									
	N/A	Does not apply									
		Spaces and support spaces appropriately configured per				1					
8.5		c? (cross reference with CTE below)			3				Comments	1.00	3.00
	1	Very unsatisfactory - No dedicated maker spaces		<u> </u>		<u> </u>		<u> </u>	New construction has 3 maker spaces. Existing building		0.00
	2	Unsatisfactory - Too small, poor condition, disconnected							They construction has a maker spaces. Existing ballan	ng mac mone.	
	_	from learning spaces, no flexibility									
	3	Average - Adequate size, adequate condition, needs									
		some renovations or updates to function well									
	4	Satisfactory - Good size, good condition, connected to									
		learning spaces									
	5	Very Satisfactory - Generous size, excellent condition,									
		connected to learning spaces									
	N/A	Does not apply							,		

Perkins&Will 02/11/2022 ³

8 - Academ	ics & Learning (cont.)	1	2	3	4	5	N/A	4		
8.6 Is there	a Professional Learning Center in the learning neighborhood?				4			Comments	1.00	4.00
1 2 3 4 5	Very unsatisfactory - No dedicated space for Professional Learning Center Unsatisfactory - Too small, poor condition, disconnected Average - Adequate size, adequate condition, needs some renovations or updates to function well Satisfactory - Good size, good condition, connected Very Satisfactory - Generous size, excellent condition, connected							New PLCs were added to existing building in 2017 boi includes (1) PLC per neighborhood. Existing building ronew PLC. Assessment team did not see a PLC in existing the existing building ronew PLC. Assessment team did not see a PLC in existing the existi	enovation incl	
Q /	re adequate places to display the evidence and artifacts of g (both 2D and 3D)?				4			Comments	1.00	4.00
1 2 3	Average - Adequate size, adequate condition, needs updates or renovations to function well Satisfactory - Good size, good condition							Observed tackable surfaces in corridors and display of Principal's note - missing in new admin space and oth building.		sting
5 N/A										
	ne building / learning neighborhood provide adequate unities for students/teachers to collaborate in varying group				4			Comments	1.00	4.00
1	Very unsatisfactory - No space to support collaboration in various sizes. Unsatisfactory - Too small, inflexible, only one option, does not support a variety of group sizes					•		New construction has lots of furniture and space in cobuilding has lots of space and some furniture. Space classrooms and makes supervision challenging.		•
3 4 5	Average - Adequate space for collaboration, needs updates or renovations to function well. Satisfactory - Good size, good condition, multiple options to support a variety of group sizes Very Satisfactory - Generous size, excellent condition, multiple options to support a variety of group sizes									
N/A										
8.9 Does th	ne building provide opportunities for informal interaction?					5		Comments	1.00	5.00
1 2	Very unsatisfactory - No space Unsatisfactory - Too small, poor condition, layout and furnishings do not support informal interaction well							New construction meets Ed Specs. Existing has lots of engagement and impromptu meeting spaces including		
3	Average - Adequate size and condition, needs updates or renovations to function well. Satisfactory - Good size, good condition, layout and									
5	furnishings support informal interactions Very Satisfactory - Generous size, excellent condition, layout and furnishings support informal interactions									
N/A	A Does not apply									

8 - A	cademics 8	& Learning (cont.)	1	2	3	4	5	N/A	· · · · · · · · · · · · · · · · · · ·		
8.10		ilding provide adequate opportunities for students to			3				Comments		
0.10	work indepe	endently?			3					1.00	3.00
	1	Very unsatisfactory - No breakout rooms/small study							Score is averaged between new construction and exi	sting building.	Existing
		spaces							building does not have small breakout rooms. New c	onstruction me	eets Ed
	2	Unsatisfactory - Too small, poor condition, no acoustic							Specs.		
		privacy, only one space for independent work,									
		disconnected from learning neighborhood									
	3	Average - Adequate size and condition, needs updates									
		or renovations to function well.									
	4	Satisfactory - Good size and condition, acoustic privacy,									
		variety of independent work space options, connected to									
	5	learning neighborhood Very Satisfactory - Generous size, excellent condition,									
	5	acoustic privacy, variety of independent work space									
		options, connected to learning neighborhood									
	N/A	Does not apply									
	Special Edu	,									
	•	Education spaces appropriately configured per the ed			1	l I					
8.11	spec?	Education spaces appropriately configured per the ed			3				Comments	1.00	3.00
	1	Very unsatisfactory - Too small, no flexibility,			<u> </u>	<u> </u>			The Special Education area is currently in one room in		
		•							Classroom size is adequate but disconnected from ot	-	_
	2	Unsatisfactory - Too small, only one area for all teaching							Needs renovations and furniture.	ner learning a	ieus.
	•	methods, limited flexibility, disconnected							Needs renovations and furniture.		
	3	Neutral - Adequate size, multiple areas for different									
		teaching methods, adequate flexibility, limited							School requests an area of de-escalaction.		
		transparency and connection to other studios and									
		shared learning spaces, needs updates or renovations to function well.									
	4										
	4	Satisfactory - Good size, multiple areas for different									
		teaching methods, good flexibility, good transparency									
	E	and connection to other studios and shared learning									
	5	Very Satisfactory - Generous size, multiple areas for									
		different teaching methods, excellent flexibility, generous display area and visual teaching tools, excellent									
		transparency and connection with other studios and									
		shared learning spaces									
	N/A	Does not apply									
0.10		Education support spaces, such as storage, space for									
8.12		er, appropriately configured per the ed spec?		2					Comments	1.00	2.00
	1	Very unsatisfactory - None provided		•	•				Limited storage for non-life skills SPED rooms.		
	2	Unsatisfactory - Too small, disconnected, poor condition									
	3	Neutral - Adequate size, average condition, needs									
		updates or renovations to function well									
	4	Satisfactory - Good size, connected, good condition									
	5	Very Satisfactory - Generous size, connected, excellent									
		condition									
	N/A	Does not apply									

8 - Academics & Learning (cont.)	1	2	3	4	5	N/A			
8.13 Are Accessible restrooms and changing rooms readily available to the Special Education spaces?					5		Comments	1.00	5.00
1 No									
5 Yes STEAM Center									
			Τ	l					
8.14 Does the campus have space to support a "STEAM" center?	1						Comments	0.00	0.00
1 Very unsatisfactory - No available space for STEAM center and inadequate studio / collaborative space 2 Unsatisfactory - Collaborative areas / studios for CTE/CCL are completely separate but adequate size 3 Neutral - Collaborative areas / studios for CTE/CCL are adjacent but function separately 4 Satisfactory - Collaborative areas / studios for CTE/CCL function and have space availability to create STEAM center 5 Very Satisfactory - Functioning STEAM center offers studios, labs, common collaborative areas to support multimedia distance and hands-on project based							All STEAM/CTE will be located in the portables. Sched in phase 2.	duled for constr	uction
N/A Does not apply									
9 - CTE and Career Connected Learning	1		ı	1				11.25	56%
How close is your campus to a CTE cluster pathway that is aligned with your CTE programs (Middle School only)?					5		Comments	1.00	5.00
 Very unsatisfactory - No correlation to CTE cluster pathway, no CTE programs. Unsatisfactory - School supports less than half of the CTE programs that are listed in the cluster pathway. Average - School support half of CTE programs listed in the cluster pathway, but missing some. Satisfactory - School support a majority of CTE programs listed in the CTE cluster pathway. Very Satisfactory - School is aligned with CTE cluster pathway. N/A Does not apply 							Program is aligned with Anderson HS. All CTE courses portables, and this assessment does not cover portal programs listed below are available, the spaces that place are mostly likely to be found deficient per Ed S ₁ .	oles. While the the courses tak	ke
117									
9.2 Do campus facilities align with the CTE Ed Spec Requirements for the current pathways offered?: Architecture and Construction	1							0.25	0.25
1 No 5 Yes								0.20	
N/A Does not apply									
9.3 Arts, Audio and Video Technology and Communications	1							0.25	0.25
9.4 Business, Management and Administration	1							0.25	0.25
9.5 Education and Training						N/A		0.00	0.00
9.6 Health Science						N/A		0.00	0.00

9 - CTE and Career Connected Learning (cont.)	1	2	3	4	5	N/A			
9.7 Hospitality and Tourism						N/A		0.00	0.00
9.8 Human Services (high school only)						N/A		0.00	0.00
9.9 Information Technology	1							0.25	0.25
9.10 Agriculture, Food and Natural Resources						N/A		0.00	0.00
9.]] Science, Technology, Engineering, and Mathematics	1							0.25	0.25
9.12 Transportation, Distribution and Logistics						N/A		0.00	0.00
9.13 Finance (high school only)						N/A		0.00	0.00
9.14 Government and Public Administration / JROTC Military programs (high school only)						N/A		0.00	0.00
9.15 Law, Public Safety, Corrections and Security (high school only)						N/A		0.00	0.00
9.16 Manufacturing (high school only)						N/A		0.00	0.00
9.17 Marketing, Sales and Services (high school only)						N/A		0.00	0.00
10 - Visual and Performing Arts								35.00	37%
•	_							00.00	0770
10.1 Is there flexibility of space to also be used by CTE and Athletics?							Comments	0.00	0.00
1 No 5 Yes							Monitoring answer, but doesn't affect overall score.		
10.2 Are band and support spaces (rehearsal and storage) appropriately configured per the ed spec?			3				Comments	1.00	3.00
1 Very unsatisfactory - Too small, missing program spaces 2 Unsatisfactory - Too small, poor condition 3 Neutral - Adequate size, adequate condition, needs updates or renovations to function well. 4 Satisfactory - Good size, good condition 5 Very Satisfactory - Generous size, excellent condition							Band Hall is sized per the educational specifications, ft. undersized. Not large enough space for all 300 statogether. Need additional practice rooms.		
N/A Does not apply			_						
Are orchestra and support spaces appropriately configured per the ed spec?		2					Comments	1.00	2.00
1 Very unsatisfactory - Too small, missing program spaces							Missing dedicated practice rooms/ensemble rooms.		
2 Unsatisfactory - Too small, poor condition									
 Neutral - Adequate size, adequate condition, needs updates or renovations to function well. 									
4 Satisfactory - Good size, good condition									
5 Very Satisfactory - Generous size, excellent condition									
N/A Does not apply									

10 - Visual and	Performing Arts (cont.)	1	2	3	4	5	N/A	4		
10.4 Are choir a	nd support spaces appropriately configured per the ed		2					Comments		
spec?								Comments	1.00	2.00
1	Very unsatisfactory - Too small, missing program spaces							Choir located in opposite side of building. School note	ed space is not	t large
2	Unsatisfactory - Too small, poor condition							enough for full choir.		
3	Neutral - Adequate size, adequate condition, needs									
	updates or renovations to function well.									
4	Satisfactory - Good size, good condition									
5	Very Satisfactory - Generous size, excellent condition									
N/A	Does not apply									
10.5	and support spaces appropriately configured per the ed	1						Comments		
spec?									1.00	1.00
1	Very unsatisfactory - Too small, missing program spaces							Dance too small. Currently in walled-off stage space.		
2	Unsatisfactory - Too small, poor condition									
3	Neutral - Adequate size, adequate condition, needs									
	updates or renovations to function well.									
4	Satisfactory - Good size, good condition									
5	Very Satisfactory - Generous size, excellent condition									
N/A	Does not apply	1	1		1	1	1			1
106	r and support spaces appropriately configured per the ed		2					Comments	1.00	
spec?							<u> </u>	Calculate Academy and the academy of the death	1.00	2.00
1	Very unsatisfactory - Too small, missing program spaces							School notes too small for number of students.		
2	Unsatisfactory - Too small, poor condition									
3	Neutral - Adequate size, adequate condition, needs									
4	updates or renovations to function well.									
5	Satisfactory - Good size, good condition									
N/A	Very Satisfactory - Generous size, excellent condition Does not apply									
Are visual c	arts and support spaces appropriately configured per the	I	I		I		1			
10.7 ed spec?	and and support spaces uppropriately cominguing per and		2					Comments	1.00	2.00
1	Very unsatisfactory - Too small, missing program spaces	1				1	1			
2	Unsatisfactory - Too small, poor condition									
3	Neutral - Adequate size, adequate condition, needs									
Ĭ	updates or renovations to function well.									
4	Satisfactory - Good size, good condition									
5	Very Satisfactory - Generous size, excellent condition									
N/A	Does not apply									·
Danathaaa	Continue de la contin									
	ampus have adequate space for the specialty arts Ensemble, Guitar, Music studies, Music theory and Piano)?	1						Comments		
programs (Ensemble, Outton, ividate actuales, ividate theory and Fidilo)!								1.00	1.00
1	No							Campus interview indicated that performing arts area	a is too small t	0
5	Yes							support programs.		

11 - Athletics and Wellness							18.75	52%
11.1 Does the campus meet ed spec standard for physical education program spaces?		2				Comments	1.00	2.00
1 Very unsatisfactory - Too small, missing program spaces 2 Unsatisfactory - Too small, poor condition 3 Average - Adequate size, adequate condition, needs some renovations or updates to function well 4 Satisfactory - Good size, good condition 5 Very Satisfactory - Generous size, excellent condition N/A Does not apply						Gyms too small for number of students. Phase 2 of mas new gym with outside access for UIL events.	ter plan is to	build
11.2 Does the campus have a dedicated wellness center?	1					Comments	0.50	0.50
1 No 5 Yes						Campus has a small weight room off the gym area. It c t is open to the campus. Has minimal old equipment.	loes not app	ear that
11.3 Does the community have access to exterior playfields/courts?				5		Comments	0.50	2.50
1 No 5 Yes								
11.4 Are facilities available to facilitate eSports (High School only)?				١	N/A	Comments	0.00	0.00
1 No 5 Yes					N	Monitoring answer, but doesn't affect overall score.		
17.5 Are facilities set up to support UIL sanctioned athletics for basketball?	1				t	Assessment team met with coach's and they said that they could not support UIL events because the condition of the gym flooring is bad	0.25	0.25
1 No 5 Yes								
11.6 Are facilities set up to support UIL sanctioned athletics for track?				5	Т	Frack appeared to be in good condition.	0.25	1.25
1 No 5 Yes								
17.7 Are facilities set up to support UIL sanctioned athletics for football?				5	F	Football field appeared to be in good condition	0.25	1.25
1 No 5 Yes						•		
17.8 Are facilities set up to support UIL sanctioned athletics for volleyball?	1					Coaches said gym flooring and leaking in gym will not support UIL activities.	0.25	0.25
1 No 5 Yes			•					
11.9 Are facilities set up to support UIL sanctioned athletics for tennis?	1				С	Tennis courts appeared to have low areas that were collecting puddles. Some nets were down. School reports they are very old.	0.25	0.25
1 No 5 Yes								
11.10 Are facilities set up to support UIL sanctioned athletics for soccer?				5	p	Assessment team assumes that soccer would be colayed at football field. Field appeared in good condition.	0.25	1.25
1 No 5 Yes								

Perkins&Will 02/11/2022 9

11 - Athletics and Wellness (cont.)	1	2	3 4	4 5	1 3	N/A			
Are facilities (dedicated storage) set up to support UIL sanctioned athletics for cross-country (high school only)?					1	N/A	Comments	0.00	0.00
1 No 5 Yes									
11.12 Are facilities (dedicated storage) set up to support UIL sanctioned athletics for golf (high school only)?					1	N/A	Comments	0.00	0.00
1 No 5 Yes					•		·		
11.13 Are facilities (dedicated storage) set up to support UIL sanctioned athletics for swimming (high school only)?					1	N/A	Comments	0.00	0.00
1 No 5 Yes					•		·		
Are facilities set up to support UIL sanctioned athletics for wrestling (high school only)?					1	N/A	Comments	0.00	0.00
1 No 5 Yes					•		·		
Are facilities set up to support UIL sanctioned athletics for baseball (high school only)?					1	N/A	Comments	0.00	0.00
1 No 5 Yes					•		·		
11.16 Are facilities set up to support UIL sanctioned athletics for softball (high school only)?					1	N/A	Comments	0.00	0.00
1 No 5 Yes							·		
11.17 Are facilities (dedicated space outside of the gymnasium) available to support competitive spirit activities for cheerleading and drill team?	1						Comments	0.25	0.25
1 No 5 Yes	ı						No practice space on campus is large enough.		
11 - Athletics and Wellness (cont.)	1	2	3 4	4 5	1 7	N/A			
How do the athletics fields align with FMP Campus Improvements? 11.18 Turf Field, Parking lot lighting, ADA accessible amenities (high School only)					1	N/A	Comments	0.00	0.00
1 Very unsatisfactory - No turf, inaccessible, no site lighting 2 Unsatisfactory - No turf/field in poor condition, some accessibility concerns, poor site lighting							Monitoring answer, but doesn't affect overall score.	0.00	0.00
 Average - Field in adequate condition, needs some updates or renovations to function well Satisfactory - Turf field in good condition, good ADA 									
access and site lighting									
5 Very Satisfactory - Turf field with excellent maintenance, excellent ADA access for spectators and athletes, excellent site lighting									
N/A Does not apply.						L			

02/11/2022 ¹⁰

12 -	Food Servi	ices								10.00	50%
12.1	Is the Dinin	ng Commons appropriately configured per the ed spec?		2					Comments	1.00	2.00
	1 2 3 4	Very unsatisfactory - Too small, missing program spaces Unsatisfactory - Too small, poor condition, only one option for eating space provided, inadequate circulation Average - Adequate size and condition, needs updates or renovations to function well Satisfactory - Good size and condition, good circulation, multiple options for eating space (ex: connection to outdoor eating space) Very Satisfactory - Generous size, excellent condition and circulation, multiple options for eating space (ex:						•	Furniture is outdated. Still has tables with attached s with seating and tables with umbrellas. Poor acousti School capacity at 1,300 cafeteria should be 7,400 S	cs	
	N/A	connection to outdoor eating space) Does not apply									
12.2	Are the Foo	od Services support spaces appropriately configured per c?			3	3			Comments	1.00	3.00
	1 2 3 4 5	Very unsatisfactory - None provided Unsatisfactory - Too small, disconnected, poor condition Neutral - Adequate size, average condition, needs updates or renovations to function well Satisfactory - Good size, connected, good condition Very Satisfactory - Generous size, connected, excellent condition									
	N/A	Does not apply									
13 -	Media Res		1	2	- 3	3 4	5	N/A	A	30.00	93%
13.1	visitors to t				3	3			Comments	1.00	3.00
	1 2 3 4 5	Very unsatisfactory - Not accessible Unsatisfactory - Limited access, difficult to find, no transparency Average - Adequate accessibility, needs updates or renovations to function well Satisfactory - Accessible, easy to find, good transparency, good condition Very Satisfactory - Accessible, easy to find, excellent transparency, excellent condition							The Media Center is new but is not easy to access for	visitors.	
	N/A	Does not apply							L		

13 - Media Res	ources - Continued	1	2	3	4	5	N/A	A		
13.2 How well de	oes the Library/Media Center support quiet study?					5		Comments	1.00	5.00
1 2 3 4 5	Very unsatisfactory - No quiet study spaces Unsatisfactory - One area in poor condition, poor acoustic privacy Average - One or more areas provided, needing updates or renovations to function well Satisfactory - Clusters or small rooms adjacent to media center, good condition, good acoustic privacy Very Satisfactory - Multiple clusters or small rooms adjacent to media center, excellent condition, excellent acoustic privacy									
N/A	Does not apply				1	l	I			
13.3 How well do	oes the Library/Media Center support social interaction?					5		Comments	1.00	5.00
1 2 3 4 5	Very unsatisfactory - No space Unsatisfactory - Too small, poor condition, layout and furnishings do not support informal interaction well Average - Adequate size and condition, needs updates or renovations to function well. Satisfactory - Good size, good condition, layout and furnishings support informal interactions Very Satisfactory - Generous size, excellent condition, layout and furnishings support informal interactions				,					
N/A	Does not apply oes the Library/Media Center support collaborative work				ı			1		
137	oups (4-8 students)?					5		Comments	1.00	5.00
1 2 3 4 5	Very unsatisfactory - No breakout rooms, no flexible furniture, no support Unsatisfactory - Too small, one area, poor condition Average - Adequate size, multiple areas provided, needing updates or renovations to function well Satisfactory - Clusters or small rooms adjacent to media center, flexible furniture, good condition Very Satisfactory - Multiple clusters or small rooms adjacent to media center, flexible furniture, excellent condition Does not apply									
135	oes the Library/Media Center support collaborative work oups (10-25)?					5		Comments	1.00	5.00
1 2 3 4 5 N/A	Very unsatisfactory - No gathering areas Unsatisfactory - Too small, one common space, limited seating, poor condition Average - Adequate size, one common space, needs updates or renovations to function well Satisfactory - Good size, multiple common spaces with seating, good condition Very Satisfactory - Generous size, multiple commons spaces with seating, excellent condition								1.00	3.00
IN/A	Does not apply									

	13 - Media Res	ources - Continued	1	2	3	4	5	N/A	4		
	13.6 How well d	loes the Library/Media Center support technology?					5		Comments	1.00	5.00
	1 2 3	Very unsatisfactory - No vis comm tools Unsatisfactory - Outdated, poorly functioning, or insufficient Average - Mix of old and new									
	4	Satisfactory - projectors, marker boards, smart boards in most spaces - good condition									
	5	Very Satisfactory - projectors, marker boards, smart boards in most spaces - new condition									
	N/A	Does not apply									
	14 - Technolog	у	1	2	3	4	5	N/A	4	20.00	50%
	14.1 How well e	equipped are the facilities with instructional technology?			3				Comments	1.00	3.00
,	1	Very unsatisfactory - Limited to no technology present in instructional spaces							Technology meets Ed Specs in the new building but is existing, Score is averaged.	lacking in the	
	2	Unsatisfactory - One type of technology present									
	3	Average - Multiple types of technology, smart boards.									
	4	Poor condition. Limited to only certain areas of school. Satisfactory - Multiple types of technology, smart boards. Good condition.									
	5	Very Satisfactory - Multiple types of technology, smart boards. Excellent condition									
	N/A	Does not apply		1			1	_	,		
	14.2 spaces?	adequate number of power and data outlets in learning			3				Comments	1.00	3.00
	1	Very unsatisfactory - Outlet configuration does not							Power and data meet Ed Specs in the new building b	-	
	2	support digital devices throughout school (1 per wall) Unsatisfactory - Outlet configuration support digital devices only in certain areas of school (2 per wall)							existing building. Score is averaged. School notes existing dequate for power / charging / supporting technology.		s very
	3	Average - Outlet configuration support digital devices but limited capacity throughout school (3 per wall)									
	4	Satisfactory - Outlet configuration support digital devices with adequate coverage and capacity in limited locations (>3 per wall)									
	5	Very Satisfactory - Excellent outlet configuration to support digital devices throughout school (>3 per wall)									
	N/A	Does not apply									

Perkins&Will 02/11/2022 13

14 - Technolog	gy (cont.)	1	2	3	4	5	1	N/A			
14.3 Are there c	adequate charging locations for devices?			3					Comments	1.00	3.00
1 2 3 4	Very unsatisfactory - Not enough charging locations throughout school for 1:1 Unsatisfactory - Charging locations, haphazard locations, and inadequate in size for number of devices Average - Charging locations well organized but not enough capacity for 1:1 Satisfactory - Charging locations, haphazard locations, but supports 1:1.				•				Charging stations meet Ed Specs in the new building existing, Score is averaged.	but lacking in	the
5	Very Satisfactory - Charging locations throughout school to support 1:1.										
N/A	Does not apply										
14.4 ls there add	equate AV for presentations spaces – cafeteria, gym, aux	1							Comments	1.00	1.00
1	Very unsatisfactory - AV not present in one or more					•			Gym / aux gym lacking AV.		
2	Unsatisfactory - AV undersized for room. Poor condition										
3 4	Average - AV adequately sized / poor condition OR AV undersized / average condition Satisfactory - AV adequately sized for room. Average										
5 N/A	Condition. Very Satisfactory - AV adequately sized for room. Excellent condition. Does not apply										
	gital media signage at the reception area?					5			Comments	0.00	0.00
1	Very unsatisfactory - No digital media present in reception area									0.00	0.00
2	Unsatisfactory - Undersized, poor condition										
3	Average - Adequately sized / poor condition OR undersized / adequate condition										
4	Satisfactory - Media signage present, good sized, good condition										
5	Very Satisfactory - Generously sized, excellent condition										
N/A	Does not apply							L			

15 - Administration Spaces	1	2	3	4	5	N/A	\	20.00	90%
15.1 Is there a reception area that functions as a security checkpoint for all visitors?							Comments		
 Very unsatisfactory - No security checkpoint Unsatisfactory - Checkpoint is too small, poor condition 		•			•	•			
3 Average - Needs updates or renovations to function well									
4 Satisfactory - Good size, good condition									
5 Very Satisfactory - Generous size, excellent condition N/A Does not apply									
15.2 Does the administration area feel welcoming?					5		Comments	1.00	5.00
1 Very unsatisfactory - No welcome space		•	•	•	•	•			
2 Unsatisfactory - Too small, poor lighting and									
transparency, limited informal seating, poor condition 3 Average - Adequate size and layout, needs updates or									
renovations to feel welcoming									
4 Satisfactory - Good size and layout, good lighting and									
transparency, informal seating provided									
5 Very Satisfactory - Generous size and layout, plenty of									
light and transparency, informal seating provided, excellent condition									
N/A Does not apply									
For those spaces that require it does the administration area have									
15.3 adequate acoustic privacy?	1		3				Comments	1.00	3.00
 Very unsatisfactory - No acoustic separations 							Counseling areas in existing building have very poor	acoustics and	voices
Unsatisfactory - Acoustic separations do not perform							travel between spaces. Counseling area very small a		xisting
3 Average - Some acoustic separations function okay, but							building. Phase 2 expands counseling to new Admin	PLC.	
portions need updates or renovations									
4 Satisfactory - Good acoustic separations 5 Very Satisfactory - Excellent acoustic separations									
N/A Does not apply									
15.4 Are conference rooms easily accessed for public / parent use?					5		Comments	1.00	5.00
1 Very unsatisfactory - Not accessible for public/parent					I		School notes admin conference room only, not public		
 Unsatisfactory - Limited access, no transparency, poor 									
condition, difficult to find									
3 Average - Adequate accessibility, needs updates or									
renovations to function well									
4 Satisfactory - Good accessibility, good transparency, good size and condition									
5 Very Satisfactory - Excellent accessibility, excellent									
transparency, generous size, excellent condition									
N/A Does not apply									