

Bear Creek Elementary School

Date: 12/22/2020 Score 95% Very Satisfactory

Bear Creek Elementary School, serving an enrollment of approximately 490 students in southwest Austin, is one of the first schools to be designed and built in the 2017 Bond Program. Its design follows the vision for creating 21st-century learning environment for students and educators. It was inaugurated in 2020 and the campus grounds cover approximately 19 acres. There is a lookout point off the second-level studio wing that overlooks the Hill Country and could be used as an outdoor studio. There are many open green areas. One of the playgrounds is not adjacent to the learning spaces, but it is shaded. The other playground is adjacent to a covered outdoor basketball court. There is a large cistern in the front of the campus however, no garden areas were observed.

Given its recent construction, the school meets a high percentage of the Education Specifications. The learning neighborhoods are located in a three-level structure and are connected to the administration, library, gym and cafeteria via an elongated corridor, creating an interior courtyard space. Studios are adequately sized and have built-in storage. In the learning spaces, flexible furniture allows for different size groups. There is opportunity to have breakout sessions in designated small group rooms that are adjacent to the studios. Visual connections between these rooms allows for passive supervision into these spaces. There is also ample space in the hallways allowing groups to meet outside of the studios.

The main entrance vestibule is secure and adjacent to a community room and the administration office. Visitors are unable to pass without checking in with administrators. Within the administration suite, there is a conference room at the end of the corridor for parent conferences. The acoustical quality between offices is sufficient but acoustics between the offices and hallway was of concern.

The cafeteria and gymnasium spaces are able to be accessed from the public parking and corridors leading to the gymnasium and cafeteria can be secured for after-hours activities. The cafeteria is adjacent to the gymnasium and can open into one big space for large events. The stage has a backlit projector, lighting and speakers. The furniture in the cafeteria is flexible and there is booth-type seating available. The library is just past the secure vestibule at the main entrance. There are different types of furniture allowing for small and large group study, as well as a reading area for smaller kids. Multiple windows create good transparency into the hallway.

Interview Overview

The interview was conducted with Principal David Crissey and Gene Glenn from AECOM. The principal is concerned about the capacity due to district boundary reconfigurations. If the capacity increases, Principal Crissey indicated maker spaces would have to be converted to regular studios and portables would have to be considered. The only place the campus has space for portables is in the parking lot. The campus was designed to add studios and Principal Crissey indicated that the new studio additions need to be considered.

Bear Creek Elementary School

Some other concerns centered around outdoor facilities and security. There is a lack of an open area for the students. The school backs up to a preserve, and the site is limited. There are two playground areas that are at either side of the campus. The courtyard space could be better utilized with more outdoor furniture.

The hope is the facility is used to its full potential. The building is set up for collaboration for small and large groups. The idea is to foster more project-based learning. Looking ahead 20 years, Principal Crissey thinks this will become the norm. He said that technology should not follow but lead the design of the building. Another important component is furniture. Having the ability to rapidly reconfigure the spaces is essential.

Assessment Findings

The Educational Suitability Assessment of Bear Creek Elementary earned a 95% overall score and places the campus in a category of Very Satisfactory. The assessment consists of seven General Building categories and seven Academic categories to determine areas that need more attention.

Satisfactory Categories (66-80%):

Outdoor Learning and Activity

Score is satisfactory.

The outdoor playing areas are at a distance away from the studio wings. There is no direct access to play areas and no visible learning pond or garden were observed.

Technology

Score is satisfactory.

Studios do not appear have adequate number of outlets to charge devices or projectors for teaching. The cafeteria has a backlit projector and there is digital media signage in the reception office.

Very Satisfactory Categories (81-100%):

Academics & Learning

Score is very satisfactory.

Studios are sized well and have dedicated small-group breakout areas adjacent. There is excellent transparency. The school is equipped with maker spaces and locations for informal interactions.

Administrative Spaces

Score is very satisfactory.

The administrative space feels welcoming to visitors. The acoustics between offices is adequate however, sound can be heard from the hallway in the admin suite. A large conference room is available that seats 12 people.

Security

Score is very satisfactory.

Bear Creek Elementary School

Furniture, Fixtures, Equipment

Score is very satisfactory.

All studios and spaces have new furniture. Teachers can move furniture to offer more options of size of groups and methods of teaching. There is a variety of furniture offered in different spaces throughout the building.

Media Resources

Score is very satisfactory.

Library is easily accessible to visitors and has sufficient transparency. The library has a breakout room to support collaborative work for small groups.

General Building

Score is very satisfactory.

Main circulation routes are wide enough allowing for safe and effective movement. The layout of building provides access to gym and cafeteria for after hour functions without gaining access to the rest of school.

PE and Wellness

Score is very satisfactory.

The gym is configured well and in good condition with connected outdoor spaces. The gym has sufficient storage and connection to cafeteria for larger groups.

Exterior

Score is very satisfactory.

The circulation separates bus, vehicular and pedestrian traffic well. Trash/compost bins are accessible and directly adjacent to the kitchen area. The building is easily identifiable for visitors.

Food Services

Score is very satisfactory.

Connection to outdoor eating and plenty of seating options are available. Clean and generous kitchen space, operable partition to gym.

Visual and Performing Arts

Score is very satisfactory.

There are separate rooms for music and art. Both were well equipped with storage and amenities. Cafeteria stage is ample size for productions.

Controllability of Systems

Score is very satisfactory.

Studios have multiple dimming options for artificial lighting. Studios have their own thermostat. Exterior windows have shades to control natural lighting.

Environmental Quality

Score is very satisfactory.

Perkins&Will

Bear Creek Elementary School

The acoustics in the studios are good however, sound/voices could be heard from the hallway, likely due to the volume necessary to talk with masks on. All studios have access to natural daylight and views to the outside.

Bear Creek Elementary School



Entry to Bear Creek is welcoming, and a covered entry is provided. The school was inaugurated in 2020.




The community room, including a prep area and restroom, is adjacent to the secured entrance lobby for easy access to the public.

Bear Creek Elementary School



The Media Center just past the secured entrance lobby. Flexible furniture allows for different size groups.



PLC room for staff is spacious and allows for group or individual planning.

Bear Creek Elementary School



Informal meeting spaces are located throughout the learning neighborhoods of the campus.




Small group rooms are located adjacent to studios and have good transparency for passive supervision.



The maker space has movable partitions allowing the space to open to the corridor.



Studios have flexibility to create multiple areas for different teaching methods and have good control over artificial and natural lighting.



An outlook point connected to the studio wing allows a view of the Hill Country.



The outdoor covered basketball area is adjacent to the gym. Pre-K and kindergarten playground is beyond.



Perkins&Will

Austin ISD Educational Suitability Assessment Criteria

General Building

School Name	Walk Attendees:	Date:
Bear Creek ES	Carlos Cruz and Anacleto Rojas	12.22.2020

- Ex	terior		1	2	3	4	5	N/A		8.75	1009
1.1	Does the site traffic?	e permit desirable separation of vehicular, bus and pedestrian					5		Comments	1.00	5.0
	1	Very unsatisfactory - Bus, car and pedestrian all happen at the same location							Building located far off of road and has ample room for cars.	stacking of bus	ses and
	2	Unsatisfactory - Cars and buses mix, pedestrians are separated									
	3	Average - Buses, cars, and pedestrians are separate but stack space is small									
	4	Satisfactory - Buses, cars, and pedestrians are separate but drop off does not have a canopy or a holding place like a commons or cafeteria									
	5	Very satisfactory - Buses, cars, and pedestrians are separate and drop off area has a canopy and destination									
	N/A	Does not apply									
1.2	Is the buildir wayfinding?	ng easily identified with appropriate signage and community					5		Comments	0.25	1.3
	1	Very unsatisfactory - Campus has no signage / wayfinding							One main vehicular entrance with good signage, easy to	navigate.	
	2	Unsatisfactory - Signage/wayfinding is faded/hidden									
	3	Average - Signage / wayfinding visible but not apparent									
	4	Satisfactory - Signage / wayfinding is visible but not good condition									
	5	Very satisfactory - Signage and wayfinding is visible and easy to use									
	N/A	Does not apply									

1 -	Exterior (con	it.)	1	2	3	3 4	5	N/A			
1.3	3 Is the dump	ster accessible for trash / compost disposal?					5		Comments	0.50	2.50
	1	Very unsatisfactory - No compost present, route has obstacles (stairs, curbs, barriers) to dumpster		•		•					
	2	Unsatisfactory - Compost is present. Route has obstacles to dumpster									
	3	Average - Compost is present (<100' to cafeteria), Route to dumpster is free and clear but the two are not directly adjacent.									
	4	Satisfactory - Compost and dumpster are directly adjacent and route is barrier free									
	5	Very Satisfactory - Compost and dumpster are directly adjacent and route is barrier free. Dumpster are shaped / positioned so people of all heights can access it.									
	N/A	Does not apply									
2 -	Outdoor Led	arning and Activity	1	2	3	3 4	5	N/A		15.00	80%
2.	1 Are outdoor ed spec?	r studios and support spaces appropriately configured per the			3	3			Comments	1.00	3.00
	1	Very unsatisfactory - No dedicated outdoor studios							Outdoor studios located at distance away from the stud	ios. There is an	inner
	2	Unsatisfactory - Too small, poor condition, disconnected from learning spaces, no flexibility, no shade provided							courtyard but only has landscaping and some sitting are	eas.	
	3	Average - Adequate size, adequate condition, needs some renovations or updates to function well, 50% or less shade coverage over studio area									
	4	Satisfactory - Good size, good condition, connected to learning spaces, good flexibility, more than 50% shade coverage over studio area									
	5	Very satisfactory - Generous size, excellent condition, connected to learning spaces, excellent flexibility, full shade coverage over studio area									
	N/A	Does not apply		_							
2.	2 Are active p per the ed s	playgrounds (elementary only) and support spaces configured spec?				4			Comments	1.00	4.00
	1	Very unsatisfactory - No dedicated active playground								,	
	2	Unsatisfactory - Too small, poor condition, no shade provided									
	3	Average - Adequate size, adequate condition, needs some renovations or updates to function well, 50% or less shade coverage over play structure									
	4	Satisfactory - Good size, good condition, more than 50% shade coverage over play structure									
	5	Very satisfactory - Generous size, excellent condition, full shade coverage over play structure									
	N/A	Does not apply									

2 - C	otdoor Lea	rning and Activity (cont)	1	2	3	4	5	N/A	X		
2.3		and support spaces appropriately configured per the ed lation on infrastructure not condition of plants)	1						Comments	0.00	0.00
	1 2	Very unsatisfactory - No dedicated gardens Unsatisfactory - Too small, poor condition, disconnected from learning spaces, no flexibility, no accessible water source							Monitoring answer, does not affect score for Outdoor Le No gardens	arning and Act	ivity.
	3	Average - Adequate size, adequate condition, needs some renovations or updates to function well, water source is difficult to access									
	4	Satisfactory - Good size, good condition, connected to learning spaces, good flexibility, water source is accessible with 100 ft hose									
	5	Very Satisfactory - Generous size, excellent condition, connected to learning spaces, excellent flexibility, water source is less than 50ft from the garden or has irrigation									
	N/A	Does not apply									
2.4	Are the rain spec?	gardens and/or cisterns appropriately configured per the ed				4			Comments	0.00	0.00
	1 2	Very unsatisfactory - No rain gardens or cisterns Unsatisfactory - Too small, poor condition, not functioning, disconnected							Monitoring answer, does not affect score for Outdoor Le Signficant size cistern in front of the school adjacent to t		
	3	Average - Adequate size, adequate condition, is connected, needs some renovations or updates to function well									
	4	Satisfactory - Good size, good condition, functions properly									
	5	Very Satisfactory - Generous size, excellent condition, exceptional functionality, connected to learning spaces, educational signage provided									
	N/A	Does not apply									
2.5		nool have animal husbandry? (optional)	1						Comments	0.00	0.00
	1 5	No Yes									
26		nool have nature loop trails? (optional)	1					Γ	Comments	0.00	0.00
2.0	1	No							Comments	0.00	0.00
	5	Yes									
2.7	Does the sch	nool have a learning pond? (optional)	1						Comments	0.00	0.00
	1	No									
2.0	5	Yes					-		Commonto	1.00	E 00
2.8	Does the sch	nool have a grass play field and walking trail? No					5		Comments	1.00	5.00
	5	Yes									

3 -	General Buil	ding	1	2	3	4	5	N/A		11.25	100%
3.		circulation routes wide enough to safely and effectively ate student movement?					5		Comments	0.50	2.50
	1	Very unsatisfactory - Primary circulation is 5'-0" to 6'-0" wide							12 feet in main corridors.		
	•	11 11 (1 D : 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1									
	2	Unsatisfactory - Primary circulation is 6'-0" to 7'-0" wide									
	3	Average - Primary circulation is 7'-0" to 8'-0" wide									
	4	Satisfactory - Primary circulation is 8'-0"-10'-0" wide									
	5	Very satisfactory - Primary circulation is 10'-0"+ wide									
_	N/A	Does not apply									
3.:		nity use areas arranged so that the school can allow night thout full school access?					5		Comments	0.75	3.75
	1	Very unsatisfactory - Cafeteria, gym, and library cannot be accessed after hours							Yes. Entrance from parking lot to gym area can be closed	d off to rest of o	campus.
	2	Unsatisfactory - Only one of the public spaces (Cafeteria, Gym and Library) can be accessed from parking and secured after hours									
	3	Average - Only two of the public spaces can be accessed from parking and secured after hours									
	4	Satisfactory - All of the public spaces can be accessed from parking and secured from the rest of the building but not individually									
	5	Very satisfactory - Cafeteria, gym, and library can be accessed from parking and locked off from rest of campus for night/evening use with their own entrance									
	N/A	Does not apply									
	ls there a co	mmunity room that is a dedicated meeting space outside of		Π	Π		5		Comments		
3.	school funct	ion?					5		Comments	0.75	3.75
	1	Very unsatisfactory - No dedicated community room							Off of secured vestubule. Ample size for a good size grou	ıp.	
	2	Unsatisfactory - Community room but within school function, no access after school hours									
	3	Average - Community room, moderate size, but need some renovations or updates to function well									
	4	Satisfactory - Community room, good size /layout, meets needs /functions well									
	5	Very Satisfactory - Community room, generous size, nice condition, functions appropriately outside of school function									
	N/A	Does not apply									
3.4		neral appearance of the school convey pride for the students					5		Comments		
J.,	and commu	nity?					J		Comments	0.25	1.25
	1	Very unsatisfactory - General appearance is poor							New school dedicated this year.		
	2	Unsatisfactory - General appearance is aged but ok									
	3	Average - General appearance is good									
	4	Satisfactory - General appearance shows pride in campus and student works									
	5	Very Satisfactory - General appearance shows pride in campus and student works and is welcoming to the community									
	N/A	Does not apply									

	4 - Seci	urity		1	2	3	4	5	N/A		16.25	L
	4.1 D	oes the fac	cility have key card access at all major entries?							Comments	0.25	
ľ		1	Very unsatisfactory - No entries									
		2	Unsatisfactory - 1/4 of major entries									
		3	Average - 1/2 of major entries									
		4	Satisfactory - 3/4 of major entries									
		5	Very satisfactory - All of major entries									
		N/A	Does not apply									
	4.2 H	ow adequ	ate is site lighting and security for the campus overall?							Comments	1.00	_
		1	Very unsatisfactory - No exterior lighting, no secure perimeter									
		2	Unsatisfactory - Lighting is limited to front entry only, parking lot lighting poor, security is minimal									
		3	Average - Lighting at all night-use entries and parking lot, but poor condition. Security is moderate									
		4	Satisfactory - Lighting at all night-use entries and parking lots, good condition, signage less visible, perimeter is well secured but needs updates									
		5	Very satisfactory - Signage, parking lots, and entries are well lit, visible and easy to use, perimeter is very secure									
		N/A	Does not apply									
			office located at the school entry and configured with a secure the main corridor?							Comments	1.00	
		1	Very unsatisfactory - No secure vestibule, office located far from main entry, allows visitors access to school unsupervised									
		2	Unsatisfactory - No secure vestibule, office located somewhat far from main entry, minimal supervision of visitors									
		3	Average - Office close to entry, views of front door, but no secure vestibule									
		4	Satisfactory - Office is well-located with a secure vestibule, but needs updates									
		5	Very satisfactory - Office well-located with secure vestibule and all appropriate security features									
		N/A	Does not apply									
			ugh interior transparency for faculty to passively supervise I their activities who are not in studios?					5		Comments	1.00 5.0	00
Ì		1	Very unsatisfactory - No transparency of walls							There is good transparency for the breakout smaller roo	ms adjacent to the	
		2	Unsatisfactory - Limited transparency in certain locations							studios allowing the instructor to see in those rooms from	n the studios.	
		3	Average - Good transparency in certain locations but inadequate or missing in other locations of school									
		4	Satisfactory - Adequate transparency throughout the school									
		5	Very satisfactory - Excellent transparency throughout the school									
		N/A	Does not apply									П

5	- Environment	tal Quality	1	2	3	4	5	N/A		25.00	100%
	5.1 How are acc	oustics in studios in general?					5		Comments	1.00	5.00
	1 2 3 4 5 N/A	Very unsatisfactory - Recognized word/sound from adjacent studio/corridor Unsatisfactory - Audible sound from adjacent studio/corridor Average - Slight sound from outside room Satisfactory - Walls to deck insulated only white noise from mechanical system Very satisfactory - Able to hear quiet speaking from across the room Does not apply							Conversation can be heard from corridor, likely due to vo	olume needed v	vith
	5.2 Is the studio	o artificial lighting adequate quality?					5		Comments	1.00	5.00
	1 2 3 4 5 N/A	Very unsatisfactory - Sporadic lights work, glare, less than 20 FC Unsatisfactory - 10-19 FC or serious glare Average- 20-29 FC minor glare Satisfactory - 30-39 FC and no glare Very satisfactory - 40+ FC and no glare Does not apply									
	5.3 Is there acce	ess to natural light in studios?					5		Comments	1.00	5.00
	1 2 3 4 5 N/A	Very unsatisfactory - No learning spaces have natural light Unsatisfactory - 1-25% of learning spaces have natural light or windows are too small to let in light Average - 26-50% of learning spaces have natural light Satisfactory - 51-75% of learning spaces have natural light Very satisfactory - 76-100% of learning spaces have natural light Does not apply				•			All studios have access to natural light		
	5.4 Is there acce	ess to outside views from learning spaces?					5		Comments	1.00	5.00
	1 2 3 4 5	Very unsatisfactory - No learning spaces have views Unsatisfactory - 1-25% of learning spaces have views or windows are too small to see out Average - 26-50% of learning spaces have views Satisfactory - 51-75% of learning spaces have views Very satisfactory - 76-100% of learning spaces have views							All studios have access to outside views		5.50

Perkins&Will 02/11/2022 ⁷

5 - Eı	nvironmen	tal Quality (cont.)	1	2	3	4	5	N/A			
5.5	Does the bu	uilding have odor or pest problems?					5		Comments	1.00	5.00
	1	Very unsatisfactory - Evidence of both pests and odors								•	
	2	Unsatisfactory - Evidence of pests or odors									
	3	Average - Limited evidence of pests, no odors									
	4	Satisfactory - No evidence of pests / odors, school cleanliness in good condition									
	5	Very Satisfactory - No evidence, school cleanliness in excellent condition									
	N/A	Does not apply									
6 - C	ontrollabil	ity of Systems	1	2	3	4	5	N/A		12.50	100%
6.1	Does the st	udio thermostat allow for individual control?					5		Comments	0.50	2.50
	1	No									
	5	Yes									
6.2	Are shades	provided to control natural light in learning spaces?					5		Comments	1.00	5.00
	1	Very unsatisfactory - No, windows are covered with boards/paper									
	2	Unsatisfactory - No, windows have no light control									
	3	Average - Yes, but poor condition blinds									
	4	Satisfactory - Yes, blinds									
	5	Very satisfactory - Blackout shades									
	N/A	Does not apply									
6.3	What is the	quality of lighting controls in the studios?					5		Comments	1.00	5.00
	1	Very unsatisfactory - Single switch only per room							Multiple dimming capabilities.		
	2	Unsatisfactory - Alternating rows switch off									
	3	Average - Alternating lamps in single fixtures switch off									
	4	Satisfactory - Tri level switching									
	5	Very satisfactory - Dimmable									
	N/A	Does not apply									

7 - Furnit	ture, Fixtures & Equipment	1	2	3	4	5	N/A		18.75	100%
7.1 Wh	at is the current condition of the furniture?					5		Comments	0.75	3.75
	1 Very unsatisfactory - Damaged or broken, non-functioning 2 Unsatisfactory - Torn/ bent/ wrong size 3 Average - Scratched/dented/marked 4 Satisfactory - Not new, but sturdy and clean 5 Very satisfactory - New N/A Does not apply									
	a variety of furniture types being accommodated throughout the ool - learning commons, dining commons, other multi-use spaces?					5		Comments	1.00	5.00
	1 Very Unsatisfactory - Same furniture used in all spaces 2 Unsatisfactory - Furniture variety in one multi-use space 3 Average - Furniture variety in more than one multi-use space 4 Satisfactory - All multi-use spaces have greater than one type of furniture 5 Very satisfactory - All multi-use spaces have greater than two types of furniture									
7.3 Hov	N/A Does not apply w well does furniture accommodate rapid reconfiguration of a space?					5		Comments	1.00	5.00
	Very Unsatisfactory - Furniture is fixed or very heavy Unsatisfactory - Furniture does not allow desks to be configured as individuals, small groups, or large groups							Larger group tables are harder to move, depends on gra		5.00
	Average - Mix of furniture that can reconfigure but is cumbersome to move Satisfactory - Furniture is flexible for multiple configurations of space Very satisfactory - Furniture is flexible for multiple configurations of space, easy to move and stack N/A Does not apply									
7.4 Is th	ne furniture ergonomic and size appropriate for grade level?					5		Comments	1.00	5.00
	Very unsatisfactory - Desk with attached chair combinations too small for grade level Unsatisfactory - Desk with attached chair combinations Average - Mix of studios with tables/loose chairs and desks with fixed seats Very satisfactory - Tables with loose chairs Very satisfactory - Tables with loose chairs that allow students to be active N/A Does not apply					<u>, </u>		Combo of desk or tables, depending on grade level.		

02/11/2022 9

Zer	o Waste		1	2	3	4	5	N/A	4	5.00	100%
		and corridors have blue recycle bins with bilingual instructions ge sorting instructions?					5		Comments	0.50	2.50
	1	Very unsatisfactory - There are no recycling and landfill bins and signage are sparse or infrequent, OR there are only landfill bins with no recycling bins.						•	A score for this category is being recorded, but this category in the overall ESA average.	gory is not calcu	ulated
	2	Unsatisfactory - Bins and signage are sparse or infrequent and/or lack clear signage.							No clear signage.		
	3	Average - 50% of corridors and studios have both a landfill bin and a recycle bin in an accessible location. The containers have clear signage.									
	4	Satisfactory - 75% of studios and corridors have a visible landfill and recycle collection containers in an accessible location. The containers have clear signage.									
	5	Very satisfactory - All studios / corridors (100%) have visible landfill and recycle collection containers in accessible locations. The containers have clear signage, and the style and format is consistent and uniform across campus.									
	N/A	Does not apply									
	each: green	Ifeteria (or wherever meals are served) have at least one of a compost bin, blue recycle bin, and landfill bin? Are the bins arly with bilingual and/or image sorting?					5		Comments	0.50	2.50
	1	Very unsatisfactory- There may be landfill bins, but there are no compost and/or recycle bins. There is not clear sorting signage.	,						No labeled bins.		
	2	Unsatisfactory- Recycle, landfill, and compost bins are present, but the bins are scattered and no co-located next to one another. Signage is absent or inconsistent.									
	3	Average-There is at least one waste station with all three bins (recycle, compost, landfill) located with close proximity to one another. The signage is visible and consistent.									
	4	Satisfactory- There are several waste stations as described above									
	5	Very Satisfactory - There are several waste stations as described above, and additional signage in the cafeteria that encourages recycling/composting.									
	N/A	Does not apply									



Perkins&Will

Austin ISD Educational Suitability Assessment Criteria

Academics - Elementary School

School Name	Walk Attendees:	Date:
Bear Creek ES	Carlos Cruz and Anacleto Rojas	12.22.20

3 - Ac	ademics 8	k Learning	1	2	3	4	5	N/A		70.00	99%
8.1	Are studios	appropriately configured per the ed spec?					5		Comments	1.00	5.00
	1	Very unsatisfactory - Too small, no flexibility, disconnected							Studios meet the configuration of the ed spec in terms o studio spaces average below the 800 NSF. The studios t		
	2	Unsatisfactory - Too small, only one area for all teaching methods, limited flexibility, disconnected							NSF. The small group (5) tend to be around 115 NSF. Ed s 125.		
	3	Neutral - Adequate size, multiple areas for different teaching methods, adequate flexibility, limited transparency and connection to other studios and shared learning spaces, needs updates or renovations to function well.									
	4	Satisfactory - Good size, multiple areas for different teaching methods, good flexibility, good transparency and connection to other studios and shared learning spaces									
	5	Very Satisfactory - Generous size, multiple areas for different teaching methods, excellent flexibility, generous display area and visual teaching tools, excellent transparency and connection with other studios and shared learning spaces									
	N/A	Does not apply									
8.2		nd Kinder have appropriate support spaces such as restrooms e per the ed spec?					5		Comments	1.00	5.0
	1	Very unsatisfactory - None provided									
	2	Unsatisfactory - Too small, disconnected, poor condition									
	3	Neutral - Adequate size, average condition, needs updates or renovations to function well									
	4	Satisfactory - Good size, connected, good condition									
	5	Very Satisfactory - Generous size, connected, excellent condition									
	N/A	Does not apply									

8 - A	cademics 8	k Learning (cont.)	1	2	3	4	5	N/A	4		
8.3	Do studios h spec?	nave appropriate support spaces such as storage per the ed				4			Comments	1.00	4.00
	1 2	Very unsatisfactory - None provided Unsatisfactory - Too small, disconnected, poor condition		•				•	Storage provided in casework.		
	3	Neutral - Adequate size, average condition, needs updates or renovations to function well									
	4	Satisfactory - Good size, connected, good condition									
	5	Very Satisfactory - Generous size, connected, excellent condition									
	N/A	Does not apply									
8.4	Do typical le collaboratio	earning neighborhoods have small group rooms and open on space?					5		Comments	1.00	5.00
	1	Very unsatisfactory - No breakout rooms or open collaboration spaces are provided							Small flex space in corridors of learning neighborhood, aroup rooms in most areas. Visibility to breakout spaces		small-
	2	Unsatisfactory - Too small or too few, poor condition, no flexibility, lacks visual connection to learning neighborhood, poor acoustic privacy							g. cap : coc		
	3	Average - Adequate size, adequate condition, needs some renovations or updates to function well									
	4	Satisfactory - Good size, good condition and flexibility, transparency and connection to learning neighborhood, acoustic privacy									
	5	Very Satisfactory - Generous size, excellent condition and flexibility, transparency and connection to learning neighborhood, acoustic privacy									
	N/A	Does not apply								,	
8.5		studios large enough to support project-based learning and ching modalities?					5		Comments	1.00	5.00
	1	Very unsatisfactory - Too small, no flexibility, does not support project-based learning							Flexible furniture allows for better flexibility.		
	2	Unsatisfactory - Undersized, decentralized resources, limited flexibility									
	3	Average - Adequate size, needs some renovations or updates to function well									
	4	Satisfactory - Good size, centralized resources, good flexibility									
	5	Very Satisfactory - Generous size, centralized project resources, excellent flexibility									
	N/A	Does not apply									

8 - A		k Learning (cont.)	1	2	3	4	5	N/A		
8.6	Are Maker S ed spec?	Spaces and support spaces appropriately configured per the					5		Comments 1.00	5.00
	1	Very unsatisfactory - No dedicated maker spaces							Maker space currently not set up due to COVID but dedicated space is	
	2	Unsatisfactory - Too small, poor condition, disconnected from learning spaces, no flexibility							provided.	
	3	Average - Adequate size, adequate condition, needs some renovations or updates to function well								
	4	Satisfactory - Good size, good condition, connected to learning spaces								
	5	Very Satisfactory - Generous size, excellent condition, connected to learning spaces								
	N/A	Does not apply								
8.7	Is there a Pr	ofessional Learning Center in the learning neighborhood?					5		Comments 1.00	5.00
	1	Very unsatisfactory - No dedicated space for Professional Learning Center		•	•	•	•	•		
	2	Unsatisfactory - Too small, poor condition, disconnected								
	3	Average - Adequate size, adequate condition, needs some								
		renovations or updates to function well								
	4	Satisfactory - Good size, good condition, connected								
	5	Very Satisfactory - Generous size, excellent condition, connected								
	N/A	Does not apply								
8.8	Is there a de	edicated science room and support space?	1						Comments 0.00	0.00
	1	No							Monitoring answer, but doesn't affect overall score.	
	5	Yes								
8.9		dequate places to display the evidence and artifacts of oth 2D and 3D)?					5		Comments 1.00	5.00
	1	Very unsatisfactory - No dedicated space							Large display at secure vestibule and tack strips for 2D display through	out
	2	Unsatisfactory - Too small, non-dedicated, poor condition							corridors.	
	3	Average - Adequate size, adequate condition, needs updates or renovations to function well								
	4	Satisfactory - Good size, good condition								
	5	Very Satisfactory - Generous size, excellent condition								
	N/A	Does not apply								

Perkins&Will 02/11/2022 ⁴

8 - A	cademics &	Learning (cont.)	1	2	3	4	5	N/A			
8.10		ilding provide adequate opportunities for students/teachers te in varying group sizes?					5		Comments	1.00	5.00
	1	Very unsatisfactory - No space to support collaboration in various sizes.		•					Dedicated small-group rooms, plenty of larger gathering	g spaces.	
	2	Unsatisfactory - Too small, inflexible, only one option, does not support a variety of group sizes									
	3	Average - Adequate space for collaboration, needs updates or renovations to function well.									
	4	Satisfactory - Good size, good condition, multiple options to support a variety of group sizes									
	5	Very Satisfactory - Generous size, excellent condition, multiple options to support a variety of group sizes									
	N/A	Does not apply									
8.11	Does the bui	ilding provide opportunities for informal interaction?					5		Comments	1.00	5.00
	1	Very unsatisfactory - No space							Informal furnishings provide more opportunities and are	in ample space	e for
	2	Unsatisfactory - Too small, poor condition, layout and furnishings do not support informal interaction well							this to occur.		
	3	Average - Adequate size and condition, needs updates or renovations to function well.									
	4	Satisfactory - Good size, good condition, layout and furnishings support informal interactions									
	5	Very Satisfactory - Generous size, excellent condition, layout and furnishings support informal interactions									
	N/A	Does not apply									
8.12		rning neighborhood / building provide adequate es for students to work independently?					5		Comments	1.00	5.00
	1	Very unsatisfactory - No breakout rooms/small study spaces					•		There are opportunities in the hallways and small-group	rooms.	
	2	Unsatisfactory - Too small, poor condition, no acoustic privacy, only one space for independent work, disconnected from learning neighborhood									
	3	Average - Adequate size and condition, needs updates or renovations to function well.									
	4	Satisfactory - Good size and condition, acoustic privacy, variety of independent work space options, connected to learning neighborhood									
	5	Very Satisfactory - Generous size, excellent condition, acoustic privacy, variety of independent work space options, connected to learning neighborhood									
	N/A	Does not apply									

O2/11/2022 ⁵

8 - A	cademics 8	Learning (cont.)		 				
8.13	Are Special	Education spaces appropriately configured per the ed spec?			5	Comments	1.00	5.00
	1	Very unsatisfactory - Too small, no flexibility, disconnected						
	2	Unsatisfactory - Too small, only one area for all teaching methods, limited flexibility, disconnected						
	3	Neutral - Adequate size, multiple areas for different teaching methods, adequate flexibility, limited transparency and connection to other studios and shared learning spaces, needs updates or renovations to function well.						
	4	Satisfactory - Good size, multiple areas for different teaching methods, good flexibility, good transparency and connection to other studios and shared learning spaces						
	5	Very Satisfactory - Generous size, multiple areas for different teaching methods, excellent flexibility, generous display area and visual teaching tools, excellent transparency and connection with other studios and shared learning spaces						
	N/A	Does not apply						
8.14		Education support spaces, such as storage, space for er, appropriately configured per the ed spec?			5	Comments	1.00	5.00
	1 2	Very unsatisfactory - None provided Unsatisfactory - Too small, disconnected, poor condition				Life skills room large and open. Have separate PT/OT/s	peech rooms.	
	3	Neutral - Adequate size, average condition, needs updates or renovations to function well						
	4	Satisfactory - Good size, connected, good condition						
	5	Very Satisfactory - Generous size, connected, excellent condition						
	N/A	Does not apply						
8.15		ole restrooms and changing rooms readily available to the cation spaces?			5	Comments	1.00	5.00
	1	No						
	5	Yes						

02/11/2022 ⁶

9	- V i	isual and Pe	erforming Arts	1	2	3	4	5	N/A		15.00	100%
	9.1	Are music spetthe ed spec?	aces and the cafeteria stage appropriately configured per					5		Comments	1.00	5.00
		1 2	Very unsatisfactory - Too small, missing program spaces Unsatisfactory - Too small, poor condition									
		3	Neutral - Adequate size, adequate condition, needs updates or renovations to function well.									
		4	Satisfactory - Good size, good condition									
		5	Very Satisfactory - Generous size, excellent condition									
		N/A	Does not apply									
	9.2	Are music an the ed spec?	d performance storage spaces appropriately configured per					5		Comments	1.00	5.00
		1	Very unsatisfactory - None provided									
		2	Unsatisfactory - Too small, disconnected, poor condition									
		3	Neutral - Adequate size, average condition, needs updates or renovations to function well									
		4	Satisfactory - Good size, connected, good condition									
		5	Very Satisfactory - Generous size, connected, excellent condition									
		N/A	Does not apply									
	9.3	Are Visual Ar spec?	ts spaces and storage appropriately configured per the ed					5		Comments	1.00	5.00
		1	Very unsatisfactory - Too small, missing program spaces							Kiln, abundant storage and movable desks.		
		2	Unsatisfactory - Too small, poor condition									
		3	Average - Adequate size, adequate condition, needs some renovations or updates to function well									
		4	Satisfactory - Good size, good condition									
		5	Very Satisfactory - Generous size, excellent condition									
		N/A	Does not apply									

10 - PE and Wellness	1	2	3	4	5	N/A		10.00	100%
10.1 Does the campus meet the ed spec standard for physical education program spaces?					5		Comments	1.00	5.00
1 Very unsatisfactory - Too small, missing program spaces 2 Unsatisfactory - Too small, poor condition 3 Average - Adequate size, adequate condition, needs some renovations or updates to function well 4 Satisfactory - Good size, good condition 5 Very Satisfactory - Generous size, excellent condition N/A Does not apply 10.2 Are the physical education storage spaces appropriately configured per the ed spec? 1 Very unsatisfactory - None provided 2 Unsatisfactory - Too small, disconnected, poor condition 3 Neutral - Adequate size, average condition, needs updates or renovations to function well 4 Satisfactory - Good size, connected, good condition 5 Very Satisfactory - Generous size, connected, excellent					5		Comments Double doors to exterior connected to outdoor play and court.	1.00	5.00
condition N/A Does not apply									
11 - Food Services	1	2	3	4	5	N/A		10.00	100%
11.1 Is the Dining Commons appropriately configured per the ed spec?				Ė	5	1,7,	Comments	1.00	5.00
1 Very unsatisfactory - Too small, missing program spaces 2 Unsatisfactory - Too small, poor condition, only one option for eating space provided, inadequate circulation 3 Average - Adequate size and condition, needs updates or renovations to function well 4 Satisfactory - Good size and condition, good circulation, multiple options for eating space (ex: connection to outdoor eating space) 5 Very Satisfactory - Generous size, excellent condition and circulation, multiple options for eating space (ex: connection to outdoor eating space)							Connection to outdoor eating and plenty of seating opt Clean and generous kitchen space, operable partition to		ole.
N/A Does not apply		1	r -		ı	_	T		
11.2 Are the Food Services support spaces appropriately configured per the ed spec?					5		Comments	1.00	5.00
1 Very unsatisfactory - None provided 2 Unsatisfactory - Too small, disconnected, poor condition 3 Neutral - Adequate size, average condition, needs updates or renovations to function well 4 Satisfactory - Good size, connected, good condition 5 Very Satisfactory - Generous size, connected, excellent condition N/A Does not apply									

12 - Media Resources N/A 30.00 87% Is the Library/Media Center easily accessible for the occupants and visitors Comments to the school? 1.00 4.00 Very unsatisfactory - Not accessible Easy to find and located near entry just off of secured vestibule. 2 Unsatisfactory - Limited access, difficult to find, no transparency Average - Adequate accessibility, needs updates or 3 renovations to function well Satisfactory - Accessible, easy to find, good transparency, good condition 5 Very Satisfactory - Accessible, easy to find, excellent transparency, excellent condition N/A Does not apply 12.2 How well does the Library/Media Center support quiet study? Comments 1.00 2.00 Very unsatisfactory - No quiet study spaces 1 space. No small group room or quiet study space. 2 Unsatisfactory - One area in poor condition, poor acoustic 3 Average - One or more areas provided, needing updates or renovations to function well 4 Satisfactory - Clusters or small rooms adjacent to media center, good condition, good acoustic privacy Very Satisfactory - Multiple clusters or small rooms adjacent 5 to media center, excellent condition, excellent acoustic privacy N/A Does not apply 12.3 How well does the Library/Media Center support social interaction? Comments 1.00 5.00 Very unsatisfactory - No space Unsatisfactory - Too small, poor condition, layout and 2 furnishings do not support informal interaction well 3 Average - Adequate size and condition, needs updates or renovations to function well. 4 Satisfactory - Good size, good condition, layout and furnishings support informal interactions Very Satisfactory - Generous size, excellent condition, layout 5 and furnishings support informal interactions N/A Does not apply How well does the Library/Media Center support collaborative work in 5 Comments small groups (4-8 students)? 1.00 5.00 Very unsatisfactory - No breakout rooms, no flexible Small area can be set up with different furniture grouping but no separate furniture, no support room. Unsatisfactory - Too small, one area, poor condition 2 3 Average - Adequate size, multiple areas provided, needing updates or renovations to function well 4 Satisfactory - Clusters or small rooms adjacent to media center, flexible furniture, good condition Very Satisfactory - Multiple clusters or small rooms adjacent to media center, flexible furniture, excellent condition N/A Does not apply

12 - I	Media Reso	urces - Continued	1	2	3	4	5	N/A			
12.5	How well do larger group	es the Library/Media Center support collaborative work in os (10-25)?					5		Comments	1.00	5.00
	1 2	Very unsatisfactory - No gathering areas Unsatisfactory - Too small, one common space, limited seating, poor condition		•							
	3	Average - Adequate size, one common space, needs updates or renovations to function well									
	4	Satisfactory - Good size, multiple common spaces with seating, good condition									
	5	Very Satisfactory - Generous size, multiple commons spaces with seating, excellent condition									
	N/A	Does not apply		,		1	1			1	
12.6		es the Library/Media Center support technology?					5		Comments	1.00	5.00
	1	Very unsatisfactory - No vis comm tools							Projection		
	2	Unsatisfactory - Outdated, poorly functioning, or insufficient									
	3	Good - Mix of old and new whiteboards/projectors/etc.									
	4	Satisfactory - Projectors, marker boards, smart boards in most spaces - good condition									
	5	Very Satisfactory - Projectors, marker boards, smart boards in most spaces - new condition									
	N/A	Does not apply									
13 - 1	Technology		1	2	3	4	5	N/A		20.00	75%
13.1	How well eq	uipped are the facilities with instructional technology?			3				Comments	1.00	3.00
	1	Very unsatisfactory - Limited to no technology present in instructional spaces							No projectors		
	2	Unsatisfactory - One type of technology present									
	3	Average - Multiple types of technology, smart boards, poor condition, limited to only certain areas of school									
	4	Satisfactory - Multiple types of technology, smart boards, good condition.									
	5	Very Satisfactory - Multiple types of technology, smart boards, excellent condition									
	N/A	Does not apply									
13.2	Is there an a spaces?	dequate number of power and data outlets in learning				4			Comments	1.00	4.00
	1	Very unsatisfactory - Outlet configuration does not support digital devices throughout school (1 per wall)									
	2	Unsatisfactory - Outlet configuration support digital devices only in certain areas of school (2 per wall)									
	3	Average - Outlet configuration support digital devices but not enough capacity throughout school (3 per wall)									
	4	Satisfactory - Outlet configuration support digital devices with adequate coverage and capacity throughout school (>3 per wall)									
	5	Very Satisfactory - Excellent outlet configuration to support digital devices throughout school (>3 per wall)									
	NI/A	Door not apply									

02/11/2022 ¹⁰

13 - Technology	y (cont.)	1	2	3	4	5	N/A	4		
13.3 Are there a	dequate charging locations for devices?			3				Comments	1.00	3.0
1	Very unsatisfactory - No centralized charging location							Studios do not have adequate number of outlets to cha	rge devices.	
2	Unsatisfactory - Centralized charging location, but inadequate in size for number of devices									
3	Average - Charging cart or tower but not adequately sized for number of devices									
4	Satisfactory - Charging cart or tower not centralized									
5	Very Satisfactory - Charging cart or tower located									
	centralized location. Excellent condition									
N/A	Does not apply			_					1	
3.4 Is there ade	equate AV for presentations spaces – cafeteria and gym?					5		Comments	1.00	5.0
1	Very unsatisfactory - AV not present in one or more space							Backlit projector screen.		
2	Unsatisfactory - AV undersized for room, poor condition									
3	Average - Adequately sized / poor condition OR AV undersized / adequate condition									
4	Satisfactory - Good size, good condition									
5	Very Satisfactory - Generous sized, excellent condition									
N/A	Does not apply									
3.5 Is there dig	ital media signage at the reception area?					5		Comments	0.00	0.0
1	Very unsatisfactory - No digital media present in reception area				•	•	•			
2	Unsatisfactory - Undersized, poor condition									
3	Average - Adequately sized / poor condition OR undersized / adequate condition									
4	Satisfactory - Media signage present, good sized, good condition									
5	Very Satisfactory - Generously sized, excellent condition									
N/A	Does not apply									

14 - A	dministra	tion Spaces	1	2	3	4	5	N/A	4	20.00	909
14.1	Is there a re visitors?	eception area that functions as a security checkpoint for all							Comments	1.00	
	1 2 3 4 5 N/A	Very unsatisfactory - No security checkpoint Unsatisfactory - Checkpoint is too small, poor condition Average - Needs updates or renovations to function well Satisfactory - Good size, good condition Very Satisfactory - Generous size, excellent condition Does not apply	•	•		•	•				
14.2		dministration area feel welcoming?					5		Comments	1.00	5.
	1 2	Very unsatisfactory - No welcome space Unsatisfactory - Too small, poor lighting and transparency, limited informal seating, poor condition						1			
	3	Average - Adequate size and layout, needs updates or renovations to feel welcoming Satisfactory - Good size and layout, good lighting and									
	5	transparency, informal seating provided Very Satisfactory - Generous size and layout, plenty of light and transparency, informal seating provided, excellent condition									
	N/A	Does not apply									
14.3		paces that require it, does the administration area have acoustic privacy?			3				Comments	1.00	3.
	1 2 3 4 5	Very unsatisfactory - No acoustic separations Unsatisfactory - Acoustic separations do not perform well Average - Some acoustic separations function okay, but portions need updates or renovations Satisfactory - Good acoustic separations Very Satisfactory - Excellent acoustic separations							Between offices ok. Hallway sound can be heard from office	es.	
	N/A	Does not apply	ı	1		_		_			
14.4	Are confere	ence rooms easily accessed for public / parent use?					5		Comments	1.00	5.
	1	Very unsatisfactory - Not accessible for public/parent use							Conference room at end of hallway in admin area. Fits 12.		
	2	Unsatisfactory - Limited access, no transparency, poor condition, difficult to find									
	3	Average - Adequate accessibility, needs updates or renovations to function well									
	4	Satisfactory - Good accessibility, good transparency, good size and condition									
	5	Very Satisfactory - Excellent accessibility, excellent transparency, generous size, excellent condition									
	N/A	Does not apply									