



Educational Suitability Summary Report

Blanton Elementary School

Date: 12/11/2020

Score 56% Average

Blanton Elementary School, serving an enrollment of approximately 600 students, is in northeast Austin off Westminster Drive. This school is part of a diverse community of bilingual students and has aligned its educational programming with the district's Creative Learning and Early College High School initiatives.

The original design of the building (which was built in 1964), poses a few challenges for the students and teachers. Main communal spaces – gym, cafeteria and library – are all undersized per the Ed Spec, leaving no location for assemblies or community meetings. Studios in the main building are also undersized, but all have access to exterior views and sunlight. The annex studio space is newer, but the layout creates acoustic separation issues.


The layout of the main building creates interior courtyard space that the school has utilized for learning through animal husbandry (chickens, koi fish) and a greenhouse. Though dated, the outdoor garden space was a well-liked feature by students and teachers. With renovations, the exterior space of the campus could become excellent outdoor learning areas.

Interview Overview

The principal invited many key players in the school to join us in the interview, including teachers from across grade levels and a parent. Much of the conversation focused on the lack of space and how that affected school programming. This poses a problem for the school due to the expectation that enrollment will increase in the near future. Multiple programs were not located in suitable spaces, which makes instruction and community involvement difficult – such as Special Education, the computer lab and art/music space. The HVAC was reported to not work properly in the cafeteria, which was said to be the best space to host community and district meetings. It was noted by a District Project Manager that the roof top unit for the cafeteria HVAC is being replaced in Summer 2021.

Another key point that was touched on throughout the conversation was that the school serves a diverse population and creating the equity for both Spanish and English learners and parents is important. More space for classes in each language was requested as well as multipurpose space for after-school programs.

The school lacks STEM and maker space, as well as a dedicated science lab, which were priorities for many of the interview attendees. Another wish list item was better theater/stage space. The current stage is undersized and is typically full of storage. The cafeteria is constantly busy, and the poor acoustics make it difficult to schedule rehearsals. Though studios share direct connection with the other adjacent, there is no collaboration space throughout the learning areas.



The campus has a major grade change across the main building and playground, which has made it difficult for students in wheelchairs. The District Project Manager noted that the ADA path of travel around the campus is being upgraded. Construction is to be completed in the future. One portion of the building is two stories, but there is no elevator and only a ramp outside near the playgrounds. Accessibility inside the school, as well as for outdoor learning areas, needs to be included in any renovations. The District Project Manager noted that ADA upgrades to gym restrooms, classroom restrooms, and 200/300 wing are needed.

Teachers really enjoy the outdoor learning areas that they have present and the unique spaces of the koi pond, greenhouse and gardens, and chicken coops. Though the interior courtyard spaces provide great locations for outdoor learning, access to interior learning areas needs improvement. These spaces do not have dedicated learning areas, which could be more successful with dedicated furniture and shading.

Overall, the campus is very well-liked in the community and school pride is on display around every corner. It was also mentioned that the general aesthetic of the school was something that should remain in the event of a renovation or addition.

Assessment Findings

The Educational Suitability Assessment of Blanton Elementary earned a 56% overall score and places the campus in a category of Average. The assessment consists of seven General Building categories and seven Academic categories to determine areas that need more attention.

Unsatisfactory Categories (36-50%):

Exterior

Score is unsatisfactory.

The current bus drop-off area is located in the teacher parking lot, which doesn't allow much stack space. The entrance of the building is not clearly identified from the street, creating confusion.

General Building

Score is average.

In general, corridors are spacious. There are no dedicated community rooms. The campus is arranged so that the gym can be accessed after-hours without allowing access to the learning areas. The cafeteria and library cannot be opened without allowing access to the 200 and 100 wing respectively.

Security Score is unsatisfactory.

Educational Suitability Summary Report

Blanton Elementary School

Academics and Learning

Score is unsatisfactory. Studios are undersized while also lacking collaboration and breakout space.

PE and Wellness

Score is unsatisfactory.

The gym is outdated and undersized, per the Ed Spec. Storage space is lacking, which creates further issues for the areas available for play and instruction.

Food Services

Score is unsatisfactory. Dining commons is undersized per the Ed Spec and provides only one option for eating space. Kitchen and service area are also undersized.

Average Categories (51-65%):

Controllability of Systems

Score is average.

Studios have individual thermostat controls. Each studio has two light switches, controlling alternating rows of lights.

Furniture, Fixtures, Equipment

Score is average.

Furniture is old and lacks variety. The library has a variety of furniture, but most other spaces do not. Furniture looks grade appropriate.

Visual and Performing Arts

Score is average.

Stage is small and lacks storage. Music and art rooms are spacious, though disconnected from performing spaces.

Media Resources

Score is average.

Library is divided into three areas but has no acoustic separation. Lacks proper furniture for informal interaction.

Technology

Score is average. Studios seen have projector screens and portable TVs, however, lack adequate number of outlets.

Satisfactory Categories (66-80%):

Outdoor Learning and Activity

Score is satisfactory.

Educational Suitability Summary Report

Blanton Elementary School

Outdoor learning spaces are dated and need renovation to allow better use. Walking path is provided, and koi pond is source of pride for the school.

Environmental Quality

Score is satisfactory. Every studio has access to daylight, and most have access to outdoor views.

Very Satisfactory Categories (81-100%):

Administration Spaces

Score is very satisfactory. Reception area was recently renovated. It is welcoming and provides a good checkpoint close to the main entrance.

Educational Suitability Summary Report

Blanton Elementary School

Supporting Photographs



Blanton ES main entrance: Canopy also connects to door just out of view with inadequate signage to distinguish the main entrance.




Educational Suitability Summary Report

Blanton Elementary School

Supporting Photographs



School pride is on display all over the campus.



Koi pond is a highlight of the campus.

Educational Suitability Summary Report

Blanton Elementary School

Supporting Photographs



Outdoor gardens are regularly used, but in poor condition. It was noted by the District Project Manager that the school has requested chicken coop to be relocated here and developed as a teaching space.



Playscape equipment and shading structures are dated.

Educational Suitability Summary Report

Blanton Elementary School

Supporting Photographs



Recently renovated admin office.



Gym is dated and small, per the Ed Spec.

Educational Suitability Summary Report

Blanton Elementary School

Supporting Photographs



Stage is small and lacks storage.



Computer lab is acoustically connected to the PTA storage space and lacks daylighting and views.

02/11/2022



Perkins&Will

Austin ISD Educational Suitability Assessment Criteria

General Building

School Name	Walk Attendees:	Date:
Blanton Elementary School	Patrick Reinhard, Kelly McEachern	12/10/2020

1 - E	xterior		1	2	3	4	5	N/A	X .	8.75	46%
1.1	Does the sit pedestrian	te permit desirable separation of vehicular, bus and traffic?		2					Comments	1.00	2.00
	1	Very unsatisfactory - Bus, car and pedestrian all happen at the same location		•					Bus drop-off occurs at teacher parking, so stack space student pickup/drop-off at main entrance.	is small. Covere	ed
	2	Unsatisfactory - Cars and buses mix, pedestrians are separated									
	3	Average - Buses, cars, and pedestrians are separate but stack space is small									
	4	Satisfactory - Buses, cars, and pedestrians are separate but drop off does not have a canopy or a holding place like a commons or cafeteria									
	5	Very satisfactory - Buses, cars, and pedestrians are separate and drop off area has a canopy and destination									
	N/A	Does not apply									
1.2	ls the build wayfinding	ing easily identified with appropriate signage and community ?		2					Comments	0.25	0.50
	1	Very unsatisfactory - Campus has no signage / wayfinding		•					Analog school sign at corner near main entrance. Bus c pickup/drop-off are separated and unclear. Building m		
	2	Unsatisfactory - Signage/wayfinding is faded/hidden							clearly identified from the street.		
	3	Average - Signage / wayfinding visible but not apparent									
	4	Satisfactory - Signage / wayfinding is visible but not good condition									
	5	Very satisfactory - Signage and wayfinding is visible and easy to use									
	N/A	Does not apply									

02/11/2022 ²

- Exterior (co	ont.)	1	2	3	4	5	N/A			
1.3 Is the dun	npster accessible for trash / compost disposal?			3				Comments	0.50	1.5
1	Very unsatisfactory - No compost present, route has obstacles (stairs, curbs, barriers) to dumpster							Dumpsters are at the back of the visitor parking with n along the route.	o accessible ra	np
2	Unsatisfactory - Compost is present. Route has obstacles to dumpster									
3	Average - Compost is present (<100' to cafeteria), Route to dumpster is free and clear but the two are not directly adjacent.									
4	Satisfactory - Compost and dumpster are directly adjacent and route is barrier free									
5	Very Satisfactory - Compost and dumpster are directly adjacent and route is barrier free. Dumpster are shaped / positioned so people of all heights can access it.									
N/A	Does not apply									
- Outdoor L	earning and Activity	1	2	3	4	5	N/A		15.00	67
2.1 Are outdo the ed spe	por studios and support spaces appropriately configured per ec?		2					Comments	1.00	2.0
1	Very unsatisfactory - No dedicated outdoor studios							Outdoor spaces are disconnected from learning areas	and lack prope	r
2	Unsatisfactory - Too small, poor condition, disconnected from learning spaces, no flexibility, no shade provided							seating. Teachers say the area floods from runoff. Exte second courtyard from cafeteria for ease of access. Erc	rior doors need	ed to
3	Average - Adequate size, adequate condition, needs some renovations or updates to function well, 50% or less shade coverage over studio area							venting are issues in this area.		
4	Satisfactory - Good size, good condition, connected to learning spaces, good flexibility, more than 50% shade coverage over studio area									
5	Very satisfactory - Generous size, excellent condition, connected to learning spaces, excellent flexibility, full shade coverage over studio area									
N/A	Does not apply									
	e playgrounds (elementary only) and support spaces			3				Comments	1.00	
	d per the ed spec?	1							1.00	3.
								Playscapes look dated. Only one is covered and swings		3. ed.
2.2 configure	d per the ed spec?							Playscapes look dated. Only one is covered and swings		
2.2 configure	d per the ed spec? Very unsatisfactory - No dedicated active playground Unsatisfactory - Too small, poor condition, no shade						I	Playscapes look dated. Only one is covered and swings		
2.2 configure 1 2	d per the ed spec? Very unsatisfactory - No dedicated active playground Unsatisfactory - Too small, poor condition, no shade provided Average - Adequate size, adequate condition, needs some renovations or updates to function well, 50% or less shade						1	Playscapes look dated. Only one is covered and swings		
2.2 configure 1 2 3	d per the ed spec? Very unsatisfactory - No dedicated active playground Unsatisfactory - Too small, poor condition, no shade provided Average - Adequate size, adequate condition, needs some renovations or updates to function well, 50% or less shade coverage over play structure Satisfactory - Good size, good condition, more than 50%						1	Playscapes look dated. Only one is covered and swings		

02/11/2022 ³

2 - Outdoor Leo	arning and Activity (cont)	1	2	3	4	5	N/	/A		
	s and support spaces appropriately configured per the ed uation on infrastructure not condition of plants)				4			Comments	0.00	0.00
1	Very unsatisfactory - No dedicated gardens							Recording answer, does not affect score for Outdoor Le	arning and Ac	tivity.
2	Unsatisfactory - Too small, poor condition, disconnected from learning spaces, no flexibility, no accessible water source							Gardens aren't directly connected to learning spaces. P but used. Multiple hose bibs nearby.	C C	
3	Average - Adequate size, adequate condition, needs some renovations or updates to function well, water source is difficult to access									
4	Satisfactory - Good size, good condition, connected to learning spaces, good flexibility, water source is accessible with 100 ft hose									
5	Very Satisfactory - Generous size, excellent condition, connected to learning spaces, excellent flexibility, water source is less than 50ft from the garden or has irrigation									
N/A	Does not apply									
2.4 Are the rain ed spec?	gardens and/or cisterns appropriately configured per the	1						Comments	0.00	0.00
1	Very unsatisfactory - No rain gardens or cisterns							Recording answer, does not affect score for Outdoor Le	arnina and Ac	tivity.
2	Unsatisfactory - Too small, poor condition, not functioning, disconnected								j	.
3	Average - Adequate size, adequate condition, is connected, needs some renovations or updates to function well									
4	Satisfactory - Good size, good condition, functions properly									
5	Very Satisfactory - Generous size, excellent condition, exceptional functionality, connected to learning spaces, educational signage provided									
N/A	Does not apply									
2.5 Does the sch	hool have animal husbandry? (optional)					5		Comments	0.00	0.00
1	No							Chickens, Koi Fish		
5	Yes									
2.6 Does the sch	hool have nature loop trails? (optional)	1						Comments	0.00	0.00
1	No									
5	Yes hool have a learning pond? (optional)					5	1	Commonto	0.00	0.00
2.7 Does the sch	No				_	5	<u> </u>	Comments Koi pond	0.00	0.00
5	Yes							Korpona		
	hool have a grass play field and walking trail?					5	T	Comments	1.00	5.00
				_			1			
1	No							Path is not ADA compliant to the walking trail.		

- Gener	al Build	ding	1	2	3	4	5	N/A		11.25	47%
		irculation routes wide enough to safely and effectively te student movement?				4			Comments	0.50	2.00
	1	Very unsatisfactory - Primary circulation is 5'-0" to 6'-0" wide							Some hallways are 8', but most are 10'.		
	2	Unsatisfactory - Primary circulation is 6'-0" to 7'-0" wide									
	3	Average - Primary circulation is 7'-0" to 8'-0" wide									
	4	Satisfactory - Primary circulation is 8'-0"-10'-0" wide									
	4 5										
		Very satisfactory - Primary circulation is 10'-0"+ wide									
	N/A	Does not apply			r			-			
		ity use areas arranged so that the school can allow night hout full school access?		2					Comments	0.75	1.50
	1	Very unsatisfactory - Cafeteria, gym, and library cannot be accessed after hours							Only Gym can be secured from learning areas after how cafeteria (from the 200 wing) cannot be secured. None		
	2	Unsatisfactory - Only one of the public spaces (Cafeteria, Gym and Library) can be accessed from parking and secured after hours							from parking.		,
	3	Average - Only two of the public spaces can be accessed from parking and secured after hours									
	4	Satisfactory - All of the public spaces can be accessed from parking and secured from the rest of the building but not individually									
	5	Very satisfactory - Cafeteria, gym, and library can be accessed from parking and locked off from rest of campus for night/evening use with their own entrance									
	N/A	Does not apply									
	ere a cor ol functi	mmunity room that is a dedicated meeting space outside of on?	1						Comments	0.75	0.7
	1	Very unsatisfactory - No dedicated community room				-			No dedicated community room.		
	2	Unsatisfactory - Community room but within school function, no access after school hours									
	3	Average - Community room, moderate size, but need some renovations or updates to function well									
	4	Satisfactory - Community room, good size /layout, meets needs /functions well									
	5	Very Satisfactory - Community room, generous size, nice condition, functions appropriately outside of school function									
1	N/A	Does not apply									
		neral appearance of the school convey pride for the d community?				4			Comments	0.25	1.00
	1	Very unsatisfactory - General appearance is poor							Murals throughout campus show pride in students and	community.	
	2	Unsatisfactory - General appearance is aged but ok								· · · · · ·	
	3	Average - General appearance is good									
	4	Satisfactory - General appearance shows pride in campus and student works									
	5	Very Satisfactory - General appearance shows pride in campus and student works and is welcoming to the community									
	N/A	Does not apply									

- Security		1	2 3	4	5 1	N/A		16.25	
	icility have key card access at all major entries?						Comments	0.25	
1 2 3 4 5 N/A	Very unsatisfactory - No entries Unsatisfactory - 1/4 of major entries Average - 1/2 of major entries Satisfactory - 3/4 of major entries Very satisfactory - All of major entries Does not apply								
I.2 How adequ	uate is site lighting and security for the campus overall?						Comments	1.00	1
1	Very unsatisfactory - No exterior lighting, no secure perimeter		•						
2	Unsatisfactory - Lighting is limited to front entry only, parking lot lighting poor, security is minimal								
3	Average - Lighting at all night-use entries and parking lot, but poor condition. Security is moderate								
4	Satisfactory - Lighting at all night-use entries and parking lots, good condition, signage less visible, perimeter is well secured but needs updates								
5	Very satisfactory - Signage, parking lots, and entries are well lit, visible and easy to use, perimeter is very secure								
N/A	Does not apply					L			_
	office located at the school entry and configured with a ibule to the main corridor?						Comments	1.00	
1	Very unsatisfactory - No secure vestibule, office located far from main entry, allows visitors access to school unsupervised			1	<u> </u>				
2	Unsatisfactory - No secure vestibule, office located somewhat far from main entry, minimal supervision of visitors								
3	Average - Office close to entry, views of front door, but no secure vestibule								
4	Satisfactory - Office is well-located with a secure vestibule, but needs updates								
5	Very satisfactory - Office well-located with secure vestibule and all appropriate security features								
N/A	Does not apply								
	bugh interior transparency for faculty to passively supervise d their activities who are not in studios?		2				Comments	1.00	2
1	Very unsatisfactory - No transparency of walls						Only half-lite in classroom door, but typically covered.		
2	Unsatisfactory - Limited transparency in certain locations						Project Manager, classroom doors and exterior doors o	do not have ADA	
3	Average - Good transparency in certain locations but inadequate or missing in other locations of school					C	compliant lites.		
4	Satisfactory - Adequate transparency throughout the school								
5	Very satisfactory - Excellent transparency throughout the school								
N/A	Does not apply								

02/11/2022 °

	5 - Environmei	ntal Quality	1	2	3	4	5	N/A		25.00	76%
ſ	5.1 How are a	coustics in studios in general?				4			Comments	1.00	4.00
	1	Very unsatisfactory - Recognized word/sound from adjacent studio/corridor Unsatisfactory - Audible sound from adjacent									
	2	studio/corridor									
	3	Average - Slight sound from outside room									
	4	Satisfactory - Walls to deck insulated only white noise from mechanical system									
	5	Very satisfactory - Able to hear quiet speaking from across the room									
_	N/A	Does not apply				1		r —			
	5.2 Is the studi	o artificial lighting adequate quality?			3				Comments	1.00	3.00
	1	Very unsatisfactory - Sporadic lights work, glare, less than 20 FC							For some teachers, fluorescent lighting is too harsh in to turn on. They use lamps and natural daylight in lieu of	•	
	2	Unsatisfactory - 10-19 FC or serious glare							turn on. They use lamps and natural adylight in lieu of	overneda lighti	ng.
	3	Average- 20-29 FC minor glare									
	4	Satisfactory - 30-39 FC and no glare									
	5	Very satisfactory - 40+ FC and no glare									
	N/A	Does not apply									
	5.3 Is there ac	cess to natural light in studios?					5		Comments	1.00	5.00
	1	Very unsatisfactory - No learning spaces have natural light							Rooms on first floor do not have adequate windows. Al adequate daylight.	ll other studios	have
	2	Unsatisfactory - 1-25% of learning spaces have natural light or windows are too small to let in light									
	3	Average - 26-50% of learning spaces have natural light									
	4	Satisfactory - 51-75% of learning spaces have natural light									
	5	Very satisfactory - 76-100% of learning spaces have natural light									
	N/A	Does not apply									
ſ	5.4 Is there ac	cess to outside views from learning spaces?				4			Comments	1.00	4.00
Ĩ	1	Very unsatisfactory - No learning spaces have views							Some basement studios only have transom windows w	ith no views.	
	2	Unsatisfactory - 1-25% of learning spaces have views or windows are too small to see out									
	3	Average - 26-50% of learning spaces have views									
	4	Satisfactory - 51-75% of learning spaces have views									
	5	Very satisfactory - 76-100% of learning spaces have views									
	N/A	Does not apply									

5 - E	nvironmen	tal Quality (cont.)	1	2	3	4	5	N/A			
5.5	Does the bu	uilding have odor or pest problems?			3				Comments	1.00	3.00
	1 2 3 4 5	Very unsatisfactory - Evidence of both pests and odors Unsatisfactory - Evidence of pests or odors Average - Limited evidence of pests, no odors Satisfactory - No evidence of pests / odors, school cleanliness in good condition Very Satisfactory - No evidence, school cleanliness in excellent condition						1	Strong odors at times in second (chicken) courtyard. Might b sewer vents.	be grease t	rap or
	N/A	Does not apply		•	•		-			10 50	
0-0	.ontrollabil	ity of Systems	1	2	3	4	5	N/A		12.50	60%
6.1	Does the st	udio thermostat allow for individual control?					5		Comments	0.50	2.50
	1	No							Rooms on lower level do not have individual controls (6-8 ro	oms)	
_	5	Yes	1	1	1	1	1	1	1		
6.2	Are shades	provided to control natural light in learning spaces?			3				Comments	1.00	3.00
	1	Very unsatisfactory - No, windows are covered with boards/paper			•				Blinds look old. Some teachers have taken down blinds.		
	2 3	Unsatisfactory - No, windows have no light control Average - Yes, but poor condition blinds									
	4	Satisfactory - Yes, blinds									
	5	Very satisfactory - Blackout shades									
	N/A	Does not apply									
6.3	What is the	quality of lighting controls in the studios?		2					Comments	1.00	2.00
	1 2 3 4 5 N/A	Very unsatisfactory - Single switch only per room Unsatisfactory - Alternating rows switch off Average - Alternating lamps in single fixtures switch off Satisfactory - Tri level switching Very satisfactory - Dimmable Does not apply							2 switches per studio, controlling alternating rows.		

02/11/2022 *

7 - Furnitur	e, Fixtures & Equipment	1	2	3	4	5	N/A	A Contraction of the second seco	18.75	59%
7.1 What i	the current condition of the furniture?				4			Comments	0.75	3.00
1	Very unsatisfactory - Damaged or broken, non-functioning							Furniture is old.		
2	Unsatisfactory - Torn/ bent/ wrong size									
3										
2	Satisfactory - Not new, but sturdy and clean									
5	Very satisfactory - New									
N/	A Does not apply									
	ariety of furniture types being accommodated throughout the - learning commons, dining commons, other multi-use spaces?		2					Comments	1.00	2.00
1	Very Unsatisfactory - Same furniture used in all spaces							Library has variety, but cafeteria does not.		
2	Unsatisfactory - Furniture variety in one multi-use space									
3	Average - Furniture variety in more than one multi-use space									
2	Satisfactory - All multi-use spaces have greater than one type of furniture									
5	Very satisfactory - All multi-use spaces have greater than two types of furniture									
N/										
7.3 How w space	ell does furniture accommodate rapid reconfiguration of a			3				Comments	1.00	3.00
1	Very Unsatisfactory - Furniture is fixed or very heavy							Some group tables, but most studios only have individu	al desks.	
2	Unsatisfactory - Furniture does not allow desks to be configured as individuals, small groups, or large groups									
3	Average - Mix of furniture that can reconfigure but is cumbersome to move									
2	Satisfactory - Furniture is flexible for multiple configurations of space									
5	Very satisfactory - Furniture is flexible for multiple configurations of space, easy to move and stack									
N/	A Does not apply									
7.4 Is the f	urniture ergonomic and size appropriate for grade level?			3				Comments	1.00	3.00
1	Very unsatisfactory - Desk with attached chair combinations too small for grade level									
2	Unsatisfactory - Desk with attached chair combinations									
3	Average - Mix of studios with tables/loose chairs and desks with fixed seats									
4	Very satisfactory - Tables with loose chairs									
ŧ	Very satisfactory - Tables with loose chairs that allow students to be active									
N/	A Does not apply									

02/11/2022 °

Waste		1	2	3	4	5	N/A		5.00	703
	and corridors have blue recycle bins with bilingual s and/or image sorting instructions?			3				Comments	0.50	1.5
1 2 3 4 5	 Very unsatisfactory - There are no recycling and landfill bins and signage are sparse or infrequent, OR there are only landfill bins with no recycling bins. Unsatisfactory - Bins and signage are sparse or infrequent and/or lack clear signage. Average - 50% of corridors and studios have both a landfill bin and a recycle bin in an accessible location. The containers have clear signage. Satisfactory - 75% of studios and corridors have a visible landfill and recycle collection containers in an accessible location. The containers have clear signage. Very satisfactory - All studios / corridors (100%) have visible landfill and recycle collection containers in accessible locations. The containers have clear signage, and the style and format is consistent and uniform across campus. 							A score for this category is being recorded, but this cat in the overall ESA average. Only in studios; not seen in corridors.	egory is not cal	culate
N/A	Does not apply		r	r	r		r		1	
each: greer	afeteria (or wherever meals are served) have at least one of n compost bin, blue recycle bin, and landfill bin? Are the bins early with bilingual and/or image sorting?				4			Comments	0.50	2.0
1 2 3	Very unsatisfactory- There may be landfill bins, but there are no compost and/or recycle bins. There is not clear sorting signage. Unsatisfactory- Recycle, landfill, and compost bins are present, but the bins are scattered and no co-located next to one another. Signage is absent or inconsistent. Average- There is at least one waste station with all three bins (recycle, compost, landfill) located with close proximity to one another. The signage is visible and consistent. Satisfactory- There are several waste stations as described		<u> </u>	•		·	·	A score for this category is being recorded, but this cat in the overall ESA average. School was recognized for recycling in 2019.	egory is not cal	culate
4 5	above Very Satisfactory - There are several waste stations as described above, and additional signage in the cafeteria that encourages recycling/composting. Does not apply									

02/11/2022



Perkins&Will

Austin ISD Educational Suitability Assessment Criteria


Academics - Elementary School

School Name	Walk Attendees:	Date:
Blanton Elementary School	Patrick Reinhard, Kelly McEachern	12/10/2020

8 - Academics	s & Learning	1	2	3	4	5	N/A	A	70.00	49%
8.1 Are studio	s appropriately configured per the ed spec?			3				Comments	1.00	3.0
1	Very unsatisfactory - Too small, no flexibility,							Studios are a good size but have little transparency b	etween spaces	and
	disconnected							corridor. Some rooms share doors between them or r	estrooms with a	a
2	Unsatisfactory - Too small, only one area for all teaching							hallway. No shared learning areas.		
	methods, limited flexibility, disconnected									
3	Neutral - Adequate size, multiple areas for different							500 wing studios are slightly undersized at 830 SF.		
	teaching methods, adequate flexibility, limited									
	transparency and connection to other studios and									
	shared learning spaces, needs updates or renovations to									
	function well.									
4	Satisfactory - Good size, multiple areas for different									
	teaching methods, good flexibility, good transparency									
	and connection to other studios and shared learning									
5	spaces Very Satisfactory - Generous size, multiple areas for									
5	different teaching methods, excellent flexibility, generous									
	display area and visual teaching tools, excellent									
	transparency and connection with other studios and									
	shared learning spaces									
N/A	Does not apply									
Do Pre-K	and Kinder have appropriate support spaces such as				1	[_		
8.2 restrooms	and storage per the ed spec?			3				Comments	1.00	3.0
1	Very unsatisfactory - None provided							There are non-ADA compliant classroom restrooms.	ull accessibility	repor
2	Unsatisfactory - Too small, disconnected, poor condition							to be addressed in FCA.		•
3	Neutral - Adequate size, average condition, needs									
	updates or renovations to function well									
4	Satisfactory - Good size, connected, good condition									
5	Very Satisfactory - Generous size, connected, excellent									
	condition									
N/A	Does not apply									

02/11/2022 ²

8 - 8	Academics a	& Learning (cont.)	1	2	3	4	5	N/A	A		
8.3		nave appropriate support spaces such as storage per the				4			Comments		
0.0	ed spec?					-			Commenta	1.00	4.00
	1	Very unsatisfactory - None provided							Built in storage cabinets.		
	2	Unsatisfactory - Too small, disconnected, poor condition									
	3	Neutral - Adequate size, average condition, needs									
		updates or renovations to function well									
	4	Satisfactory - Good size, connected, good condition									
	5	Very Satisfactory - Generous size, connected, excellent									
		condition									
	N/A	Does not apply									
8.4		earning neighborhoods have small group rooms and open	1						Comments		
0.4	collaboratio		I						Comments	1.00	1.00
	1	Very unsatisfactory - No breakout rooms or open									
		collaboration spaces are provided									
	2	Unsatisfactory - Too small or too few, poor condition, no									
		flexibility, lacks visual connection to learning									
	0	neighborhood, poor acoustic privacy									
	3	Average - Adequate size, adequate condition, needs some renovations or updates to function well									
	4	Satisfactory - Good size, good condition and flexibility,									
	-	transparency and connection to learning neighborhood,									
		acoustic privacy									
	5	Very Satisfactory - Generous size, excellent condition and									
		flexibility, transparency and connection to learning									
		neighborhood, acoustic privacy									
	N/A	Does not apply									
8.5		studios large enough to support project-based learning			3				Comments		
0.5	and multipl	e teaching modalities?			5				Comments	1.00	3.00
	1	Very unsatisfactory - Too small, no flexibility, does not							Studios are large enough, but the technology infrastr	ucture needs	
		support project-based learning							updates. Resources aren't centralized.		
	2	Unsatisfactory - Undersized, decentralized resources,									
		limited flexibility									
	3	Average - Adequate size, needs some renovations or									
	4	updates to function well Satisfactory - Good size, centralized resources, good									
	4	Satistactory - Good size, centralized resources, good flexibility									
	5	Very Satisfactory - Generous size, centralized project									
	U	resources, excellent flexibility									
	N/A	Does not apply							L		
	.,										



8 - Aca	demics &	& Learning (cont.)	1	2	3	4	5	N/A	4		
8.6 AI	re Maker S	Spaces and support spaces appropriately configured per	1						Comments		
o.o th	e ed spec	?	I						Comments	1.00	1.00
	1	Very unsatisfactory - No dedicated maker spaces									
	2	Unsatisfactory - Too small, poor condition, disconnected									
		from learning spaces, no flexibility									
	3	Average - Adequate size, adequate condition, needs									
		some renovations or updates to function well									
	4	Satisfactory - Good size, good condition, connected to									
	_	learning spaces									
	5	Very Satisfactory - Generous size, excellent condition,									
	N1/A	connected to learning spaces									
	N/A	Does not apply					1	1			
8.7 ls	there a Pr	ofessional Learning Center in the learning neighborhood?	1						Comments	1.00	1.00
	1	Very unsatisfactory - No dedicated space for									
		Professional Learning Center									
	2	Unsatisfactory - Too small, poor condition, disconnected									
	3	Average - Adequate size, adequate condition, needs									
		some renovations or updates to function well									
	4	Satisfactory - Good size, good condition, connected									
	5	Very Satisfactory - Generous size, excellent condition,									
		connected									
	N/A	Does not apply					-		1		
8.8 ls	there a de	edicated science room and support space?	1						Comments	0.00	0.00
	1	No							Monitoring answer, but doesn't affect overall score.		
	5	Yes									
A A	re there ac	dequate places to display the evidence and artifacts of				1	[
8.9 le	arning (bo	oth 2D and 3D)?			3				Comments	1.00	3.00
	1	Very unsatisfactory - No dedicated space		t			E		Tackable surfaces on corridor walls. No display cases.		
	2	Unsatisfactory - Too small, non-dedicated, poor									
		condition									
	3	Average - Adequate size, adequate condition, needs									
		updates or renovations to function well									
	4	Satisfactory - Good size, good condition									
	4										
	5	Very Satisfactory - Generous size, excellent condition									

	& Learning (cont.)	1	2	3	4	5	N/A		-	
	uilding provide adequate opportunities for	1						Comments		
students/te	eachers to collaborate in varying group sizes?	-						Comments	1.00	1.0
1	Very unsatisfactory - No space to support collaboration							Only space available is cafeteria, gym or library.		
	in various sizes.									
2	Unsatisfactory - Too small, inflexible, only one option,									
	does not support a variety of group sizes									
3	Average - Adequate space for collaboration, needs									
	updates or renovations to function well.									
4	Satisfactory - Good size, good condition, multiple options									
	to support a variety of group sizes									
5	Very Satisfactory - Generous size, excellent condition,									
	multiple options to support a variety of group sizes									
N/A	Does not apply					1				
8.11 Does the b	uilding provide opportunities for informal interaction?	1						Comments		
									1.00	1.0
1	Very unsatisfactory - No space									
2	Unsatisfactory - Too small, poor condition, layout and									
	furnishings do not support informal interaction well									
3	Average - Adequate size and condition, needs updates									
	or renovations to function well.									
4	Satisfactory - Good size, good condition, layout and									
-	furnishings support informal interactions									
5	Very Satisfactory - Generous size, excellent condition,									
NI/A	layout and furnishings support informal interactions									
N/A	Does not apply				-	1	-		1	
810	earning neighborhood / building provide adequate	1						Comments	1.00	-
	ies for students to work independently?								1.00	1.0
1	Very unsatisfactory - No breakout rooms/small study									
	spaces									
2	Unsatisfactory - Too small, poor condition, no acoustic									
	privacy, only one space for independent work,									
	disconnected from learning neighborhood									
3	Average - Adequate size and condition, needs updates									
	or renovations to function well.									
4	Satisfactory - Good size and condition, acoustic privacy,									
	variety of independent work space options, connected to									
F	learning neighborhood									
5	Very Satisfactory - Generous size, excellent condition,									
	acoustic privacy, variety of independent work space									
N1/4	options, connected to learning neighborhood									_
N/A	Does not apply									


8 - A	cademics	& Learning (cont.)							
8.13	Are Special spec?	l Education spaces appropriately configured per the ed		3			Comments	1.00	3.00
	1	Very unsatisfactory - Too small, no flexibility,					Meet Ed Spec at approx. 850 SF; however, some reso	urce teachers	are
		disconnected					currently in an office setting and a portable classroom	n.	
	2	Unsatisfactory - Too small, only one area for all teaching							
		methods, limited flexibility, disconnected							
	3	Neutral - Adequate size, multiple areas for different							
		teaching methods, adequate flexibility, limited							
		transparency and connection to other studios and							
		shared learning spaces, needs updates or renovations to							
		function well.							
	4	Satisfactory - Good size, multiple areas for different							
		teaching methods, good flexibility, good transparency							
		and connection to other studios and shared learning							
	5	spaces Very Satisfactory - Generous size, multiple areas for							
	0	different teaching methods, excellent flexibility, generous							
		display area and visual teaching tools, excellent							
		transparency and connection with other studios and							
		shared learning spaces							
	N/A	Does not apply							
	Are Specia	Education support spaces, such as storage, space for							
8.14	washer/dry	ver, appropriately configured per the ed spec?			4		Comments	1.00	4.00
	1	Very unsatisfactory - None provided							
	2	Unsatisfactory - Too small, disconnected, poor condition							
	3	Neutral - Adequate size, average condition, needs							
		updates or renovations to function well							
	4	Satisfactory - Good size, connected, good condition							
	5	Very Satisfactory - Generous size, connected, excellent							
		condition							
	N/A	Does not apply							
8,15	Are Accessi	ible restrooms and changing rooms readily available to the				_	Community		
8.15	Special Edu	ucation spaces?				5	Comments	1.00	5.00
	1	No							
	5	Yes							
_									

02/11/2022 *

9 - Visual and	Performing Arts	1	2	3	4	5	N	/A	15.00	60%
9.1 Are music s	spaces and the cafeteria stage appropriately configured spec?			3				Comments	1.00	3.00
1	Very unsatisfactory - Too small, missing program spaces							Not enough storage space on the cafeteria stage. M	usic room is	
2	Unsatisfactory - Too small, poor condition							disconnected from learning spaces in an annex build	ling.	
3	Neutral - Adequate size, adequate condition, needs updates or renovations to function well.							Principal Comment: Traveling art and music teacher	share a portab	le
4	Satisfactory - Good size, good condition							classroom, which leads to an inequitable experience	depending on	what
5	Very Satisfactory - Generous size, excellent condition							team a student is assigned to.		
N/A	Does not apply									
9.2 Are music of per the ed	and performance storage spaces appropriately configured spec?			3				Comments	1.00	3.00
1	Very unsatisfactory - None provided								•	
2	Unsatisfactory - Too small, disconnected, poor condition									
3	Neutral - Adequate size, average condition, needs									
	updates or renovations to function well									
4	Satisfactory - Good size, connected, good condition									
5	Very Satisfactory - Generous size, connected, excellent									
	condition									
N/A	Does not apply	r	1		-	-				
9.3 Are Visual ed spec?	Arts spaces and storage appropriately configured per the			3				Comments	1.00	3.00
1	Very unsatisfactory - Too small, missing program spaces									
2	Unsatisfactory - Too small, poor condition									
3	Average - Adequate size, adequate condition, needs									
	some renovations or updates to function well									
4	Satisfactory - Good size, good condition									
5	Very Satisfactory - Generous size, excellent condition									
N/A	Does not apply									

0 - PE and Wellness		1	2	3	4	5	N/A	N	10.00	409
10.1 Does the campus me program spaces?	et the ed spec standard for physical education		2					Comments	1.00	2.0
2 Unsatisf	atisfactory - Too small, missing program spaces actory - Too small, poor condition - Adequate size, adequate condition, needs							Small space, lacking in storage spaces. Old ventilation work.	on system does	n't
some re 4 Satisfac	- Adequate size, adequate condition, needs novations or updates to function well cory - Good size, good condition isfactory - Generous size, excellent condition							Principal Comment: When the traveling PE teacher is size classes share the gym.	at Blanton, tw	o full
N/A Does no										
IO.2 Are the physical educ per the ed spec?	ation storage spaces appropriately configured		2					Comments	1.00	2.0
2 Unsatisf 3 Neutral updates 4 Satisfac								Very limited. Gym restrooms are in very poor condition	on.	
1 - Food Services	- 466.)	1	2	3	4	5	N/A		10.00	40
	ns appropriately configured per the ed spec?		2					Comments	1.00	2.0
2 Unsatisf option fr 3 Average or renov 4 Satisfac multiple outdoor 5 Very Sat circulation	atisfactory - Too small, missing program spaces actory - Too small, poor condition, only one or eating space provided, inadequate circulation - Adequate size and condition, needs updates ations to function well cory - Good size and condition, good circulation, options for eating space (ex: connection to eating space) isfactory - Generous size, excellent condition and on, multiple options for eating space (ex: on to outdoor eating space) t apply				• •					
Are the Food Services 11.2 the ed spec?	support spaces appropriately configured per		2					Comments	1.00	2.
1 Very uns 2 Unsatisf 3 Neutral updates 4 Satisfact						1			,	

12 - Media Resources	1	2	3	4	5	N/A	A	30.00	57%
12.1 Is the Library/Media Center easily accessible for the occupants and visitors to the school?		2					Comments	1.00	2.0
 Very unsatisfactory - Not accessible Unsatisfactory - Limited access, difficult to find, no transparency Average - Adequate accessibility, needs updates or renovations to function well Satisfactory - Accessible, easy to find, good transparency, good condition Very Satisfactory - Accessible, easy to find, excellent transparency, excellent condition N/A Does not apply 							Close to main entrance, but difficult to find on your o	wn.	
12.2 How well does the Library/Media Center support quiet study?			3	1			Comments	1.00	3.00
 Very unsatisfactory - No quiet study spaces Unsatisfactory - One area in poor condition, poor acoustic privacy Average - One or more areas provided, needing updates or renovations to function well Satisfactory - Clusters or small rooms adjacent to media center, good condition, good acoustic privacy Very Satisfactory - Multiple clusters or small rooms adjacent to media center, excellent condition, excellent acoustic privacy N/A Does not apply 		L	L				A few different areas, but not acoustically separated		
12.3 How well does the Library/Media Center support social interaction?		2					Comments	1.00	2.0
 Very unsatisfactory - No space Unsatisfactory - Too small, poor condition, layout and furnishings do not support informal interaction well Average - Adequate size and condition, needs updates or renovations to function well. Satisfactory - Good size, good condition, layout and furnishings support informal interactions Very Satisfactory - Generous size, excellent condition, layout and furnishings support informal interactions N/A Does not apply 							Lacks proper furniture	1.00	2.0
12.4 How well does the Library/Media Center support collaborative work in small groups (4-8 students)?			3	1			Comments	1.00	3.0
 Very unsatisfactory - No breakout rooms, no flexible furniture, no support Unsatisfactory - Too small, one area, poor condition Average - Adequate size, multiple areas provided, needing updates or renovations to function well Satisfactory - Clusters or small rooms adjacent to media center, flexible furniture, good condition Very Satisfactory - Multiple clusters or small rooms adjacent to media center, flexible furniture, excellent condition N/A Does not apply 									



12 - Media Res	sources - Continued	1	2	3	4	5	N/A	N N N N N N N N N N N N N N N N N N N		
125	does the Library/Media Center support collaborative work roups (10-25)?			3				Comments	1.00	3.00
1	Very unsatisfactory - No gathering areas Unsatisfactory - Too small, one common space, limited									
2	seating, poor condition									
3	Average - Adequate size, one common space, needs									
	updates or renovations to function well									
4	Satisfactory - Good size, multiple common spaces with seating, good condition									
5	Very Satisfactory - Generous size, multiple commons									
	spaces with seating, excellent condition									
N/A	Does not apply						1			
12.6 How well d	does the Library/Media Center support technology?				4			Comments	1.00	4.00
1	Very unsatisfactory - No vis comm tools							Portable TV and projector screens		
2	Unsatisfactory - Outdated, poorly functioning, or insufficient									
3	Good - Mix of old and new whiteboards/projectors/etc.									
4	Satisfactory - Projectors, marker boards, smart boards in									
	most spaces - good condition									
5	Very Satisfactory - Projectors, marker boards, smart									
N/A	boards in most spaces - new condition Does not apply									
13 - Technolog		1	2	3	4	5	N/A		20.00	60%
		•	2		-				20.00	0078
13.1 How well e	equipped are the facilities with instructional technology?			3				Comments	1.00	3.00
1	Very unsatisfactory - Limited to no technology present in instructional spaces							Most studios had projector screens and portable TV		
2	Unsatisfactory - One type of technology present									
3	Average - Multiple types of technology, smart boards,									
4	poor condition, limited to only certain areas of school Satisfactory - Multiple types of technology, smart									
7	boards, good condition.									
5	Very Satisfactory - Multiple types of technology, smart									
	boards, excellent condition									
N/A	Does not apply adequate number of power and data outlets in learning					-	1	1		
13.2 spaces?	adequate number of power and data outlets in learning		2					Comments	1.00	2.00
1	Very unsatisfactory - Outlet configuration does not							Teachers said they're lacking. Not enough seen.		
	support digital devices throughout school (1 per wall)									
2	Unsatisfactory - Outlet configuration support digital									
	Unsatisfactory - Outlet configuration support digital devices only in certain areas of school (2 per wall)									
2 3	Unsatisfactory - Outlet configuration support digital devices only in certain areas of school (2 per wall) Average - Outlet configuration support digital devices									
	Unsatisfactory - Outlet configuration support digital devices only in certain areas of school (2 per wall)									
3	Unsatisfactory - Outlet configuration support digital devices only in certain areas of school (2 per wall) Average - Outlet configuration support digital devices but not enough capacity throughout school (3 per wall) Satisfactory - Outlet configuration support digital devices with adequate coverage and capacity									
3 4	Unsatisfactory - Outlet configuration support digital devices only in certain areas of school (2 per wall) Average - Outlet configuration support digital devices but not enough capacity throughout school (3 per wall) Satisfactory - Outlet configuration support digital devices with adequate coverage and capacity throughout school (>3 per wall)									
3	Unsatisfactory - Outlet configuration support digital devices only in certain areas of school (2 per wall) Average - Outlet configuration support digital devices but not enough capacity throughout school (3 per wall) Satisfactory - Outlet configuration support digital devices with adequate coverage and capacity									

13 -	Technolog	y (cont.)	1	2	3	4	5	N/A	4		
13.3	3 Are there a	dequate charging locations for devices?		2					Comments	1.00	2.00
	1	Very unsatisfactory - No centralized charging location							Only saw 1 charging cart in computer lab.		
	2	Unsatisfactory - Centralized charging location, but									
		inadequate in size for number of devices									
	3	Average - Charging cart or tower but not adequately									
		sized for number of devices									
	4	Satisfactory - Charging cart or tower not centralized									
	5	Very Satisfactory - Charging cart or tower located									
	N1/A	centralized location. Excellent condition									
_	N/A	Does not apply			1	1	1	r		1	
13.4	1 Is there ade	equate AV for presentations spaces – cafeteria and gym?					5		Comments	1.00	5.00
	1	Very unsatisfactory - AV not present in one or more							Gym has projector and screens. Cafeteria has a new	projector.	
		space									
	2	Unsatisfactory - AV undersized for room, poor condition									
	3	Average - Adequately sized / poor condition OR AV									
		undersized / adequate condition									
	4	Satisfactory - Good size, good condition									
	5	Very Satisfactory - Generous sized, excellent condition									
_	N/A	Does not apply									
13.5	5 Is there dig	tal media signage at the reception area?				4			Comments	0.00	0.00
	1	Very unsatisfactory - No digital media present in							Small wall-hung TV		
		reception area									
	2	Unsatisfactory - Undersized, poor condition									
	3	Average - Adequately sized / poor condition OR									
		undersized / adequate condition									
	4	Satisfactory - Media signage present, good sized, good condition									
	5	Very Satisfactory - Generously sized, excellent condition									
	N/A	Does not apply									

02/11/2022 "

	tration Spaces	1	2	3	4	5	N/A		20.00	80
14.1 Is there of visitors?	a reception area that functions as a security checkpoint for all							Comments	1.00	ĺ
1	Very unsatisfactory - No security checkpoint	•							•)
2	Unsatisfactory - Checkpoint is too small, poor condition									
3	Average - Needs updates or renovations to function well									
4	Satisfactory - Good size, good condition									
5	Very Satisfactory - Generous size, excellent condition									
N/A	Does not apply				_					
4.2 Does the	e administration area feel welcoming?				4			Comments	1.00	4.0
1	Very unsatisfactory - No welcome space	•	• •		•	•				
2	Unsatisfactory - Too small, poor lighting and									
	transparency, limited informal seating, poor condition									
3	Average - Adequate size and layout, needs updates or									
	renovations to feel welcoming									
4	Satisfactory - Good size and layout, good lighting and									
5	transparency, informal seating provided Very Satisfactory - Generous size and layout, plenty of									
5	light and transparency, informal seating provided,									
	excellent condition									
N/A										
For thos	e spaces that require it, does the administration area have	1			1	_				
4.3 adequat	te acoustic privacy?					5		Comments	1.00	5.
1	Very unsatisfactory - No acoustic separations					•		Principal comment: If additional administrators and	counselors are	adde
2	Unsatisfactory - Acoustic separations do not perform							there is not enough dedicated office space with acou	ustic privacy.	
	well									
3	Average - Some acoustic separations function okay, but									
	portions need updates or renovations									
4	Satisfactory - Good acoustic separations									
5 N/A	Very Satisfactory - Excellent acoustic separations									
-	Does not apply ference rooms easily accessed for public / parent use?				4			Comments		
									1.00	4.0
1	Very unsatisfactory - Not accessible for public/parent									
2	use Unsatisfactory - Limited access, no transparency, poor									
2	condition, difficult to find									
	Average - Adequate accessibility, needs updates or									
3	renovations to function well									
3										
3 4	Satisfactory - Good accessibility, good transparency,									
	Satisfactory - Good accessibility, good transparency,									
4	Satisfactory - Good accessibility, good transparency, good size and condition									