02/11/2022 Perkins&Will



Educational Suitability Summary Report

Davis Elementary School

Date: 01/04/2021 **63% Average**

Davis Elementary School serves an enrollment of approximately 630 students in northwest Austin. It was built in 1992, with an additional studio building constructed in 1999. The campus consists of approximately 72,000 square feet on 13 acres. The school's curriculum includes on foreign language experience and world culture, exposing students to Spanish, German, French, Latin and Chinese at different grade levels. With a very active PTA made up of over 300 families, the engagement between community and school is an important focus.

Overall, the building adequately supports the enrollment and community needs when compared with the district's Education Specifications. The main areas that would benefit from improvement and updates include exterior and interior studio spaces for academics and learning, as well as informal and collaborative spaces throughout the campus. The location of the gym, cafeteria and library do not allow for the rest of the campus to be secured for after-school events. Having dedicated entries or lockable separation from the rest of the school would help with security and wayfinding. These spaces are adequately sized and equipped with furniture and technology. The lack of storage in studios and the limited options for alternative spaces for groups to collaborate are the largest points of concern. Studios' access to natural light and views of the outdoors are strong elements in the space.

Interview Overview

The interview participants consisted of Principal Jennifer Daniels, Assistant Principal Lauren Kajdas, head custodian Delano Howard and bookkeeper Teresa Clement. When asked about features of the campus that are important to keep, staff specified a memory garden that was created in honor of students who have passed away and a paved outdoor space with engraved bricks. They feel that many of the spaces do not fit their needs or work in the ways they should. Over the years, they have made modifications to improve these spaces to the best of their abilities.

Large spaces for group breakout and activities are high on their list of priorities, in addition to larger studios to better support the programs and activities they would like to implement. More spaces for music, art and PE are needed for traveling teachers who have to share spaces or be moved into a portable to accommodate class sizes. Flexible spaces that could be used for after school or mentoring programs are needed due to limited ability for reconfiguration in the library and cafeteria.

The University of Texas at Austin performed a sound study in the cafeteria and found noise levels in the space that are potentially unsafe.

The staff believes that 20 years from now, a studio will not be tied to a space that has four walls. The

Perkins&Will

Educational Suitability Summary Report

Davis Elementary School

addition of common spaces for collaboration and smaller areas for breaking out into groups will become crucial to the educational experience. Having appropriate furniture to support these types of learning modalities will be important throughout these spaces. They already have a big focus on the Six C's that the district outlines, but their spaces limit their abilities to implement them to the level they would like. A lack of space also applies when thinking of hosting district meetings on campus, as they can only have them if they are under 50 people.

Outdoor learning spaces around the campus have been improved over the years but further development is desired. The principal and staff worked briefly with a landscape architect to envision updates and renovations that could occur in the exterior spaces. The addition of rain gardens, food gardens, seating in outdoor studio spaces and more shade and rain protection would better support their teaching needs now and in the future.

Assessment Findings

The Educational Suitability Assessment of Davis Elementary School earned a 63% overall score and places the campus in a category of Average. The assessment consists of seven General Building categories and seven Academic categories to determine areas that need more attention.

Unsatisfactory Categories (36-50%):

Academics & Learning

Score is unsatisfactory.

Studios are undersized per the district Education Specifications, and some spaces do not have the adequate storage required. There are no professional learning centers provided for different learning neighborhoods nor open and small group spaces for collaborative work. There is a dedicated maker space studio on campus. Special education studios are not adequate or equipped with the correct support spaces.

Administration Spaces

Score is unsatisfactory.

. Visitors pass by kindergarten wing before coming to office. The office has line of sight to front door, but limited viewing. The reception area is small and dated, making it less welcoming.

Average Categories (51-65%):

General Building

Score is average.

Interior corridors vary in width, but average around 8 feet. Community use areas such as the cafeteria and gym can be accessed securely during after-school hours. Library cannot be securely accessed during after-school hours. The general appearance of the school is not very inviting from the front entry, but other areas within the interior of the building are more well maintained and welcoming.

Security

Score is average.

Educational Suitability Summary Report

Davis Elementary School

Controllability of Systems

Score is average.

All studios have individual temperature controls and blinds that are in satisfactory condition for the control of daylighting. Artificial lights in studios are only controlled by a single switch.

Media Resources

Score is average.

The library has limited transparency and is not easily accessible to visitors. There are no windows or access to daylight. The furniture is flexible and mobile, but the stacks are more cumbersome to move, limiting quick reconfiguration.

Satisfactory Categories (66-80%):

Exterior

Score is satisfactory.

Bus and car traffic are separated, and buses have a large area of stack space. There are no dedicated canopies at these areas for inclement weather. Building signage could be improved, but the layout of the building and approach on the campus makes it easier to identify.

Outdoor Learning and Activity

Score is satisfactory.

Although there are two playgrounds in good condition with full shade coverage, the campus does not have dedicated gardens, but there are areas of opportunity throughout the site. Outdoor studios are disconnected and in need of updates and better maintenance.

Environmental Quality

Score is satisfactory.

All studios have windows that provide natural light and views. Acoustics and artificial lighting throughout the campus are adequate.

Furniture, Fixtures, Equipment

Score is satisfactory.

The furniture on campus is a mix of old and new items, but most are in good condition. There is no variety in furniture type in common spaces such as the cafeteria or library. While furniture is appropriately sized per grade level, most items are not as flexible and are more cumbersome to move.

Visual and Performing Arts

Score is satisfactory.

The stage at the cafeteria is small but has new A/V equipment, including a projector and screen. The music room is well-connected to the stage and appropriately configured per the Education Specifications. The art room is missing some support elements, including a sink, but is otherwise adequate.

Perkins&Will

Educational Suitability Summary Report

Davis Elementary School

PE and Wellness

Score is satisfactory.

The gym and its support spaces are a good size and in good condition. The gym is not well-connected to the outdoor activity areas due to the layout of the campus.

Food Services

Score is satisfactory.

The cafeteria and kitchen are adequately sized and configured. The acoustics are not satisfactory for the space. The location at the front of the school makes it easier for guests to navigate, but it is less connected to the studio wings.

Technology

Score is satisfactory.

Most studios have projectors, mobile TV displays, and markerboards or tackboards. There is no A/V in the gym, but the cafeteria has new equipment that is in good condition.



There is no secure vestibule at the main entry. Windows to the reception area provide some visibility to the corridor. There are opportunities for display throughout the campus.



The library is centralized on campus and has good visibility. Furniture is flexible but the stacks are cumbersome to move and make reconfiguration difficult.



All playgrounds are in good condition and have shade structures, as does the paved outdoor court.



The gym is not well-connected with the outdoor activity areas but can be secured from the rest of the campus for after-hours functions.



Cafeteria is adequately sized but only has one seating option. It is not connected to the outdoor areas but shares an operable wall with the gym.



A few areas for outdoor studios around campus but they are disconnected and in average condition.




Interior corridors vary in width, but some are narrow and more difficult to navigate and lack natural lighting.



All studios have access to natural light and views and have blinds to control daylighting.



Grass playfields and a walking trail are present and well-connected to the building.



Furniture is sized appropriately per grade level but is a mix of old and new and some teacher-provided items. Projectors and mobile TVs are present in most studios.



Perkins&Will

Austin ISD Educational Suitability Assessment Criteria

General Building

School Name	Walk Attendees:	Date:	
Davis Elementary School	Emilie Ogburn and Lynn Petermann	1.4.2021	


1 - Exterior		1	2	3	4	5	N/A		8.75	66%
1.1 Does the site permit desirable separate pedestrian traffic?	ation of vehicular, bus and				4			Comments	1.00	4.00
at the same location 2 Unsatisfactory - Cars a separated 3 Average - Buses, cars, stack space is small 4 Satisfactory - Buses, ca but drop off does not h	s, cars, and pedestrians are							The back pickup loop is large with a lot of stack space Principal's comment - There is a mix of car and pedest back lot, along with a mix of bus and pedestrian picku. Although the back drive is long, the configuration of the some students wait for car pickup within the marked oparking lot rather than along the exterior of the school presents many concerns.	rian pickup in p in the front ne drive requi of section of th	lot. res that ie
N/A Does not apply										
1.2 ls the building easily identified with community wayfinding?	appropriate signage and			3				Comments	0.25	0.75
wayfinding 2 Unsatisfactory - Signage 3 Average - Signage / w 4 Satisfactory - Signage good condition	e/wayfinding is faded/hidden ayfinding visible but not apparent / wayfinding is visible but not age and wayfinding is visible									

O2/11/2022 ²

1 - E	xterior (cor	nt.)	1	2	3	4	5	N/A			
1.3	Is the dump	oster accessible for trash / compost disposal?		2					Comments	0.50	1.00
	1 2 3 4 5	Very unsatisfactory - No compost present, route has obstacles (stairs, curbs, barriers) to dumpster Unsatisfactory - Compost is present. Route has obstacles to dumpster Average - Compost is present (<100' to cafeteria), Route to dumpster is free and clear but the two are not directly adjacent. Satisfactory - Compost and dumpster are directly adjacent and route is barrier free Very Satisfactory - Compost and dumpster are directly adjacent and route is barrier free. Dumpster are shaped / positioned so people of all heights can access it.							Have to navigate steps to get to them and all three no	ot directly adja	cent.
2 (N/A	Does not apply arning and Activity	1	2	3	4	5	N/A		15.00	80%
2.1		r studios and support spaces appropriately configured per	'	2	3	4	3	IN/A	Comments	1.00	2.00
	1	Very unsatisfactory - No dedicated outdoor studios							Few opportunities but small and disconnected and no		
	2	Unsatisfactory - Too small, poor condition, disconnected from learning spaces, no flexibility, no shade provided									
	3	Average - Adequate size, adequate condition, needs some renovations or updates to function well, 50% or less shade coverage over studio area									
	4	Satisfactory - Good size, good condition, connected to learning spaces, good flexibility, more than 50% shade coverage over studio area									
	5	Very satisfactory - Generous size, excellent condition, connected to learning spaces, excellent flexibility, full shade coverage over studio area									
	N/A	Does not apply									
2.2		olaygrounds (elementary only) and support spaces per the ed spec?					5		Comments	1.00	5.00
	1	Very unsatisfactory - No dedicated active playground							Two good-condition playgrounds; full shade.		
	2	Unsatisfactory - Too small, poor condition, no shade provided									
	3	Average - Adequate size, adequate condition, needs									
		some renovations or updates to function well, 50% or									
	4	less shade coverage over play structure Satisfactory - Good size, good condition, more than 50% shade coverage over play structure									
	5	Very satisfactory - Generous size, excellent condition, full shade coverage over play structure									
	N/A	Does not apply									

2 - Outdoor Learning and Activity (cont)	1	2	3	4	5	N/A	4	
2.3 Are gardens and support spaces appropriately configured per the ed spec? (evaluation on infrastructure not condition of plants)	1						Comments 0.00	0.00
Very unsatisfactory - No dedicated gardens Unsatisfactory - Too small, poor condition, disconnected from learning spaces, no flexibility, no accessible water source Average - Adequate size, adequate condition, needs							Monitoring answer, does not affect score for Outdoor Learning an Activity. No dedicated garden present.	d
some renovations or updates to function well, water source is difficult to access 4 Satisfactory - Good size, good condition, connected to learning spaces, good flexibility, water source is accessible with 100 ft hose								
Very Satisfactory - Generous size, excellent condition, connected to learning spaces, excellent flexibility, water source is less than 50ft from the garden or has irrigation								
N/A Does not apply								
2.4 Are the rain gardens and/or cisterns appropriately configured per the ed spec?	1						Comments 0.00	0.00
Very unsatisfactory - No rain gardens or cisterns Unsatisfactory - Too small, poor condition, not functioning, disconnected Average - Adequate size, adequate condition, is connected, needs some renovations or updates to function well							Monitoring answer, does not affect score for Outdoor Learning an Activity. Not present.	d
4 Satisfactory - Good size, good condition, functions properly 5 Very Satisfactory - Generous size, excellent condition, exceptional functionality, connected to learning spaces, educational signage provided								
N/A Does not apply								
2.5 Does the school have animal husbandry? (optional)	1						Comments 0.00	0.00
1 No 5 Yes								
2.6 Does the school have nature loop trails? (optional)	1						Comments 0.00	0.00
1 No 5 Yes								
2.7 Does the school have a learning pond? (optional)	1						Comments 0.00	0.00
1 No 5 Yes								
2.8 Does the school have a grass play field and walking trail?					5		Comments 1.00	5.00
1 No 5 Yes								

3 - General Building		1	2	3	4	5	N/A		11.25	51%
3.1 Are interior circulation routes wide enough to safel accommodate student movement?	y and effectively				4			Comments	0.50	2.00
1 Very unsatisfactory - Primary circulation	on is 5'-0" to 6'-0"	ı						Interior corridors vary in width, but average around 8	feet.	
wide										
2 Unsatisfactory - Primary circulation is	6'-0" to 7'-0" wide									
3 Average - Primary circulation is 7'-0" t	o 8'-0" wide									
4 Satisfactory - Primary circulation is 8'-	0"-10'-0" wide									
5 Very satisfactory - Primary circulation	is 10'-0"+ wide									
N/A Does not apply										
Are community use areas arranged so that the scho	ool can allow night			3				Comments		
functions without full school access?				3				Comments	0.75	2.25
l Very unsatisfactory - Cafeteria, gym, o	and library cannot							Community use areas such as the cafeteria and gym	can be access	ed
be accessed after hours								securely during after-school hours. Library cannot be	securely acces	ssed
2 Unsatisfactory - Only one of the publi- Gym and Library) can be accessed fro	•							during after-school hours.		
secured after hours	in parking and									
3 Average - Only two of the public space	es can be accessed									
from parking and secured after hours										
4 Satisfactory - All of the public spaces	can be accessed									
from parking and secured from the re	st of the building									
but not individually										
5 Very satisfactory - Cafeteria, gym, and	•									
accessed from parking and locked off campus for night/evening use with the										
N/A Does not apply	en own entrance									
Is there a community room that is a dedicated mee	ting space outside	1								
3.3 of school function?	ang space outside	1						Comments	0.75	0.75
1 Very unsatisfactory - No dedicated co	mmunity room	ı								
2 Unsatisfactory - Community room but	within school									
function, no access after school hours										
3 Average - Community room, moderat										
some renovations or updates to funct										
4 Satisfactory - Community room, good needs /functions well	size / layout, meets									
5 Very Satisfactory - Community room,	generous size, nice									
condition, functions appropriately out	-									
function										
N/A Does not apply								,		
Does the general appearance of the school convey	pride for the			3				Comments	1	
students and community?									0.25	0.75
1 Very unsatisfactory - General appear	·							Front of school off of Duval is in average condition ar	•	iting.
2 Unsatisfactory - General appearance 3 Average - General appearance is god	-							Inside of school and area between wings is better ter	ided.	
4 Satisfactory - General appearance sh										
campus and student works	om pride in									
5 Very Unsatisfactory - General appear	ance shows pride									
in campus and student works and is w	elcoming to the									
community										
N/A Does not apply										



Perkins&Will 02/11/2022 ⁶

	5 - Environmental Quality	1	2	3	4	5	N/A		25.00	68%
	5.1 How are acoustics in studios in general?			3				Comments	1.00	3.00
	Very unsatisfactory - Recognized word/sound from adjacent studio/corridor Unsatisfactory - Audible sound from adjacent studio/corridor Average - Slight sound from outside room Satisfactory - Walls to deck insulated only white noise from mechanical system Very satisfactory - Able to hear quiet speaking from across the room N/A Does not apply									
	5.2 Is the studio artificial lighting adequate quality?			3				Comments	1.00	3.00
	1 Very unsatisfactory - Sporadic lights work, glare, less than 20 FC 2 Unsatisfactory - 10-19 FC or serious glare 3 Average- 20-29 FC minor glare 4 Satisfactory - 30-39 FC and no glare 5 Very satisfactory - 40+ FC and no glare N/A Does not apply	•								
	5.3 Is there access to natural light in studios?					5		Comments	1.00	5.00
	1 Very unsatisfactory - No learning spaces have natural light 2 Unsatisfactory - 1-25% of learning spaces have natural light or windows are too small to let in light 3 Average - 26-50% of learning spaces have natural light 4 Satisfactory - 51-75% of learning spaces have natural light 5 Very satisfactory - 76-100% of learning spaces have natural light N/A Does not apply									
Ī	N/A Does not apply 5.4 Is there access to outside views from learning spaces?	Τ	l			5		Comments		
	1 Very unsatisfactory - No learning spaces have views 2 Unsatisfactory - 1-25% of learning spaces have views or windows are too small to see out 3 Average - 26-50% of learning spaces have views 4 Satisfactory - 51-75% of learning spaces have views 5 Very satisfactory - 76-100% of learning spaces have views					3		Continents	1.00	5.00
	N/A Does not apply									

Perkins&Will 02/11/2022 ⁷

5 - Environme	ntal Quality (cont.)	1	2	3	4	5	N/A	X.		
5.5 Does the b	uilding have odor or pest problems?	1						Comments	1.00	1.00
1	Very unsatisfactory - Evidence of both pests and odors							Little bit of odor around cafeteria. School has huge ro	ate rat problem	
2	Unsatisfactory - Evidence of pests or odors							according to principal.		
3	Average - Limited evidence of pests, no odors									
4	Satisfactory - No evidence of pests / odors, school									
	cleanliness in good condition									
5	Very Satisfactory - No evidence, school cleanliness in									
	excellent condition									
N/A	Does not apply									
6 - Controllabi	ility of Systems	1	2	3	4	5	N/A		12.50	60%
6.1 Does the st	tudio thermostat allow for individual control?					5		Comments	0.50	2.50
1	No									
5	Yes									
6.2 Are shades	s provided to control natural light in learning spaces?				4			Comments	1.00	4.00
1	Very unsatisfactory - No, windows are covered with							Blinds in okay condition.		
	boards/paper									
2	Unsatisfactory - No, windows have no light control									
3	Average - Yes, but poor condition blinds									
4	Satisfactory - Yes, blinds									
5	Very satisfactory - Blackout shades									
N/A	Does not apply									
6.3 What is the	e quality of lighting controls in the studios?	1						Comments	1.00	1.00
1	Very unsatisfactory - Single switch only per room							Single switch on/off.		
2	Unsatisfactory - Alternating rows switch off									
3	Average - Alternating lamps in single fixtures switch off									
4	Satisfactory - Tri level switching									
5	Very satisfactory - Dimmable									
N/A	Does not apply							L		

7 - I	Furniture, F	ixtures & Equipment	1	2	3	4	5	N/A	1	18.75	69%
7.1	What is the	e current condition of the furniture?				4			Comments	0.75	3.00
	1	Very unsatisfactory - Damaged or broken, non-									
	2	functioning Unsatisfactory - Torn/ bent/ wrong size									
	3	Average - Scratched/dented/marked									
	4	Satisfactory - Not new, but sturdy and clean									
	5	Very satisfactory - New									
	N/A	Does not apply									
7.2		ty of furniture types being accommodated throughout the			3				Comments		
\ \ \ \ \ \ \ \ \ \ \ \ \ \ \ \ \ \ \	school - lec	arning commons, dining commons, other multi-use spaces?							Comments	1.00	3.00
	1	Very Unsatisfactory - Same furniture used in all spaces			<u> </u>				No variety in cafeteria or library. Some studios have s	l .	3.00
	2								movement and regular chairs to sit in.		
		Unsatisfactory - Furniture variety in one multi-use space									
	3	Average - Furniture variety in more than one multi-use									
	4	space Satisfactory - All multi-use spaces have greater than one									
	4	type of furniture									
	5	Very satisfactory - All multi-use spaces have greater									
		than two types of furniture									
	N/A	Does not apply			ı	1	1	ı			
7.3	space?	oes furniture accommodate rapid reconfiguration of a			3				Comments	1.00	3.00
	1	Very Unsatisfactory - Furniture is fixed or very heavy			<u> </u>			<u> </u>			
	2	Unsatisfactory - Furniture does not allow desks to be									
		configured as individuals, small groups, or large groups									
	3	Average - Mix of furniture that can reconfigure but is									
	4	cumbersome to move									
	4	Satisfactory - Furniture is flexible for multiple configurations of space									
	5	Very satisfactory - Furniture is flexible for multiple									
		configurations of space, easy to move and stack									
	N/A	Does not apply					,				
7.4	ls the furnit	cure ergonomic and size appropriate for grade level?				4			Comments	1.00	4.00
	1	Very unsatisfactory - Desk with attached chair									
	2	combinations too small for grade level									
		Unsatisfactory - Desk with attached chair combinations									
	3	Average - Mix of studios with tables/loose chairs and desks with fixed seats									
	4	Very satisfactory - Tables with loose chairs									
	5	Very satisfactory - Tables with loose chairs that allow									
	N/A	students to be active									
	IN/A	Does not apply									

Perkins&Will 02/11/2022 ⁹

Waste		1	2	3	4	5	N/A		5.00	80
	s and corridors have blue recycle bins with bilingual ns and/or image sorting instructions?				4			Comments	0.50	2.0
1 2 3 4 5	Very unsatisfactory - There are no recycling and landfill bins and signage are sparse or infrequent, OR there are only landfill bins with no recycling bins. Unsatisfactory - Bins and signage are sparse or infrequent and/or lack clear signage. Average - 50% of corridors and studios have both a landfill bin and a recycle bin in an accessible location. The containers have clear signage. Satisfactory - 75% of studios and corridors have a visible landfill and recycle collection containers in an accessible location. The containers have clear signage. Very satisfactory - All studios / corridors (100%) have visible landfill and recycle collection containers in accessible locations. The containers have clear signage, and the style and format is consistent and uniform across campus.							A score for this category is being recorded, but this category calculated in the overall ESA average.	tegory is not	
	Does not apply cafeteria (or wherever meals are served) have at least one reen compost bin, blue recycle bin, and landfill bin? Are the				4			Comments		
•	led clearly with bilingual and/or image sorting?								0.50	2.
1	Very unsatisfactory- There may be landfill bins, but there are no compost and/or recycle bins. There is not clear sorting signage.						1	A score for this category is being recorded, but this category calculated in the overall ESA average.		
2	Unsatisfactory- Recycle, landfill, and compost bins are present, but the bins are scattered and no co-located next to one another. Signage is absent or inconsistent.									
3	Average- There is at least one waste station with all three bins (recycle, compost, landfill) located with close proximity to one another. The signage is visible and consistent.									
4	Satisfactory- There are several waste stations as									
4 5	Satisfactory- There are several waste stations as described above Very Satisfactory - There are several waste stations as described above, and additional signage in the cafeteria that encourages recycling/composting.									



Perkins&Will

Austin ISD Educational Suitability Assessment Criteria

Academics - Elementary School

School Name	Walk Attendees:	Date:
Davis Elementary School	Emilie Ogburn and Lynn Petermann	1.4.2021

Academic	s & Learning	1	2	3	4	5	N/A	1	70.00	40%
.1 Are studio	os appropriately configured per the ed spec?			3				Comments	1.00	3.0
1	Very unsatisfactory - Too small, no flexibility,							Studios are slightly undersized, per Ed Spec, at 820 SF	. Kinder studi	os are
0	disconnected							larger at 940 SF.		
2	Unsatisfactory - Too small, only one area for all teaching methods, limited flexibility, disconnected									
3	Neutral - Adequate size, multiple areas for different									
	teaching methods, adequate flexibility, limited									
	transparency and connection to other studios and									
	shared learning spaces, needs updates or renovations to									
	function well.									
4	Satisfactory - Good size, multiple areas for different									
	teaching methods, good flexibility, good transparency									
	and connection to other studios and shared learning									
	spaces									
5	Very Satisfactory - Generous size, multiple areas for									
	different teaching methods, excellent flexibility,									
	generous display area and visual teaching tools, excellent transparency and connection with other									
	studios and shared learning spaces									
N/A	Does not apply									
Do Pre-K	and Kinder have appropriate support spaces such as					1				
•)	s and storage per the ed spec?				4			Comments	1.00	4.00
1	Very unsatisfactory - None provided						<u> </u>	No storage closet. Only have casework. Kinder rooms		
2								Two storage closet. Only have casework. Kinder rooms	are large at 7	740 31 .
-	Unsatisfactory - Too small, disconnected, poor condition									
3	Neutral - Adequate size, average condition, needs									
	updates or renovations to function well									
4	Satisfactory - Good size, connected, good condition									
5	Very Satisfactory - Generous size, connected, excellent									
	condition									
N/A	Does not apply								•	

Perkins&Will 02/11/2022 ²

8 - Academics & Learning (cont.)	1	2	3	4	5	N/A			
8.3 Do studios have appropriate support spaces such as storage per the ed spec?			3				Comments	1.00	3.00
1 Very unsatisfactory - None provided									
2 Unsatisfactory - Too small, disconnected, poor condition									
3 Neutral - Adequate size, average condition, needs updates or renovations to function well									
4 Satisfactory - Good size, connected, good condition									
5 Very Satisfactory - Generous size, connected, excellent									
condition									
N/A Does not apply									
8.4 Do typical learning neighborhoods have small group rooms and open collaboration space?	1						Comments	1.00	1.00
Very unsatisfactory - No breakout rooms or open		1			1	1			
collaboration spaces are provided									
2 Unsatisfactory - Too small or too few, poor condition, no									
flexibility, lacks visual connection to learning									
neighborhood, poor acoustic privacy									
3 Average - Adequate size, adequate condition, needs									
some renovations or updates to function well									
4 Satisfactory - Good size, good condition and flexibility,									
transparency and connection to learning neighborhood,									
acoustic privacy 5 Very Satisfactory - Generous size, excellent condition									
and flexibility, transparency and connection to learning									
neighborhood, acoustic privacy									
N/A Does not apply									
Are general studios large enough to support project-based learning									
and multiple teaching modalities?		2					Comments	1.00	2.00
 Very unsatisfactory - Too small, no flexibility, does not 									
support project-based learning									
2 Unsatisfactory - Undersized, decentralized resources,									
limited flexibility									
3 Average - Adequate size, needs some renovations or									
updates to function well									
4 Satisfactory - Good size, centralized resources, good flexibility									
5 Very Satisfactory - Generous size, centralized project									
resources, excellent flexibility									
N/A Does not apply									

Perkins&Will 02/11/2022 ³

8 - <i>A</i>		& Learning (cont.)	1	2	3	4	5	N/A	4		
8.6	Are Maker S the ed spec	Spaces and support spaces appropriately configured per?	1						Comments	1.00	1.00
	1 2 3 4 5	Very unsatisfactory - No dedicated maker spaces Unsatisfactory - Too small, poor condition, disconnected from learning spaces, no flexibility Average - Adequate size, adequate condition, needs some renovations or updates to function well Satisfactory - Good size, good condition, connected to learning spaces Very Satisfactory - Generous size, excellent condition, connected to learning spaces							There is not a dedicated maker space studio on campethe library that teachers can check out and take to the makerspace activities.		
8.7	N/A Is there a Pr	Does not apply rofessional Learning Center in the learning neighborhood?	1						Comments	1.00	1.00
	1 2 3 4 5	Very unsatisfactory - No dedicated space for Professional Learning Center Unsatisfactory - Too small, poor condition, disconnected Average - Adequate size, adequate condition, needs some renovations or updates to function well Satisfactory - Good size, good condition, connected Very Satisfactory - Generous size, excellent condition, connected									
H	N/A	Does not apply						l			
8.8	Is there a d	edicated science room and support space?					5		Comments	0.00	0.00
	1 5	No Yes							Monitoring answer, but doesn't affect overall score.		
8.9		dequate places to display the evidence and artifacts of oth 2D and 3D)?			3				Comments	1.00	3.00
	1 2 3 4 5 N/A	Very unsatisfactory - No dedicated space Unsatisfactory - Too small, non-dedicated, poor condition Average - Adequate size, adequate condition, needs updates or renovations to function well Satisfactory - Good size, good condition Very Satisfactory - Generous size, excellent condition Does not apply									

Perkins&Will 02/11/2022 ⁴

8 - A	cademics	& Learning (cont.)	1	2	3	4	5	N/A			
8.10	Does the bu	uilding provide adequate opportunities for		2					Comments		
8.10	students/te	eachers to collaborate in varying group sizes?							Comments	1.00	2.00
	1	Very unsatisfactory - No space to support collaboration									
		in various sizes.									
	2	Unsatisfactory - Too small, inflexible, only one option,									
		does not support a variety of group sizes									
	3	Average - Adequate space for collaboration, needs									
		updates or renovations to function well.									
	4	Satisfactory - Good size, good condition, multiple									
	_	options to support a variety of group sizes									
	5	Very Satisfactory - Generous size, excellent condition,									
	N1/A	multiple options to support a variety of group sizes									
	N/A	Does not apply		1	1	1	ı		T	I	
8.11	Does the bu	uilding provide opportunities for informal interaction?		2					Comments	1.00	2.00
	1	Very unsatisfactory - No space			l	1	l		Main entry space is generous but studio hallways are		
	2	Unsatisfactory - Too small, poor condition, layout and							loaded.		
		furnishings do not support informal interaction well									
	3	Average - Adequate size and condition, needs updates									
		or renovations to function well.									
	4	Satisfactory - Good size, good condition, layout and									
		furnishings support informal interactions									
	5	Very Satisfactory - Generous size, excellent condition,									
		layout and furnishings support informal interactions									
	N/A	Does not apply								T	
8.12		arning neighborhood / building provide adequate	1						Comments		
0.12	opportuniti	es for students to work independently?							Commente	1.00	1.00
	1	Very unsatisfactory - No breakout rooms/small study									
		spaces									
	2	Unsatisfactory - Too small, poor condition, no acoustic									
		privacy, only one space for independent work,									
		disconnected from learning neighborhood									
	3	Average - Adequate size and condition, needs updates									
		or renovations to function well.									
	4	Satisfactory - Good size and condition, acoustic privacy,									
		variety of independent work space options, connected to									
	-	learning neighborhood									
	5	Very Satisfactory - Generous size, excellent condition,									
		acoustic privacy, variety of independent work space									
	N/A	options, connected to learning neighborhood									

O2/11/2022 ⁵

8 - <i>A</i>	cademics 8	& Learning (cont.)							
8.13	Are Special spec?	Education spaces appropriately configured per the ed		2			Comments	1.00	2.00
	1	Very unsatisfactory - Too small, no flexibility, disconnected		•	•		Special education located in portables are disconnect the school.	ted from the re	est of
	2	Unsatisfactory - Too small, only one area for all teaching methods, limited flexibility, disconnected							
	3	Neutral - Adequate size, multiple areas for different teaching methods, adequate flexibility, limited transparency and connection to other studios and shared learning spaces, needs updates or renovations to function well.							
	4	Satisfactory - Good size, multiple areas for different teaching methods, good flexibility, good transparency and connection to other studios and shared learning spaces							
	5	Very Satisfactory - Generous size, multiple areas for different teaching methods, excellent flexibility, generous display area and visual teaching tools, excellent transparency and connection with other studios and shared learning spaces							
	N/A	Does not apply							
8.14		Education support spaces, such as storage, space for er, appropriately configured per the ed spec?		2			Comments	1.00	2.00
	1 2	Very unsatisfactory - None provided Unsatisfactory - Too small, disconnected, poor condition					Special education studios do not have attached ADA or any life skills instruction areas	restrooms or s	showers,
	3	Neutral - Adequate size, average condition, needs updates or renovations to function well							
	4	Satisfactory - Good size, connected, good condition							
	5	Very Satisfactory - Generous size, connected, excellent condition							
	N/A	Does not apply							
8.15		ble restrooms and changing rooms readily available to the location spaces?	1				Comments	1.00	1.00
	1	No							
	5	Yes							

Perkins&Will 02/11/2022 ⁶

9 - Visual and	Performing Arts	1	2	3	4	5	N/A	4	15.00	73%
9.1 Are music s	paces and the cafeteria stage appropriately configured spec?				4			Comments	1.00	4.00
1	Very unsatisfactory - Too small, missing program spaces							Stage is small but A/V is new and has projector and so	reen.	
2	Unsatisfactory - Too small, poor condition									
3	Neutral - Adequate size, adequate condition, needs									
	updates or renovations to function well.									
4	Satisfactory - Good size, good condition									
5	Very Satisfactory - Generous size, excellent condition									
N/A	Does not apply									
9.2 Are music o	and performance storage spaces appropriately configured				4			Comments		
per the ed	spec?				4			Comments	1.00	4.00
1	Very unsatisfactory - None provided							The music room is well-connected to the stage and ap	propriately	
2	Unsatisfactory - Too small, disconnected, poor condition							configured per the Education Specifications.		
3	Neutral - Adequate size, average condition, needs									
	updates or renovations to function well									
4	Satisfactory - Good size, connected, good condition									
5	Very Satisfactory - Generous size, connected, excellent									
	condition									
N/A	Does not apply		,							
9.3	Arts spaces and storage appropriately configured per the			3				Comments		
ed spec?									1.00	3.00
1	Very unsatisfactory - Too small, missing program spaces							The school notes they need 2 art rooms for 2 art teach	ers.	
2	Unsatisfactory - Too small, poor condition									
3	Average - Adequate size, adequate condition, needs							The art room is missing some support elements, includ	ing a sink, bu	t is
	some renovations or updates to function well							otherwise adequate.		
4	Satisfactory - Good size, good condition									
5	Very Satisfactory - Generous size, excellent condition									
N/A	Does not apply									

Perkins&Will 02/11/2022 ⁷

10	0 - PE and We	llness	1	2	3	4	5	N.	/A	10.00	80%
1	n i	impus meet the ed spec standard for physical education				4			Comments		
Ľ	program sp	paces?				_			Comments	1.00	4.00
	1	Very unsatisfactory - Too small, missing program spaces							Gym and support spaces are good size and adequate	•	
	2	Unsatisfactory - Too small, poor condition							connected to the outdoor activity areas due to the lay	yout of the car	npus.
	3	Average - Adequate size, adequate condition, needs							No A/V present.		
		some renovations or updates to function well									
	4	Satisfactory - Good size, good condition							School notes they have 2 gym teachers and not adeq	uate gym spac	e.
	5	Very Satisfactory - Generous size, excellent condition									
_	N/A	Does not apply	1	1	1	1					
1	0.2 Are the phy per the ed s	rsical education storage spaces appropriately configured spec?				4			Comments	1.00	4.00
	1	Very unsatisfactory - None provided									
	2	Unsatisfactory - Too small, disconnected, poor condition									
	3	Neutral - Adequate size, average condition, needs									
		updates or renovations to function well									
	4	Satisfactory - Good size, connected, good condition									
	5	Very Satisfactory - Generous size, connected, excellent									
		condition									
	N/A	Does not apply	_	_	_		_				
11	l - Food Servic	es	1	2	3	4	5	N.	/A	10.00	70%
1	11.1 Is the Dining	g Commons appropriately configured per the ed spec?			3				Comments	1.00	3.00
	1	Very unsatisfactory - Too small, missing program spaces							Cafeteria is adequately sized and an operable wall co	onnects to gym	٦.
	2	Unsatisfactory - Too small, poor condition, only one							Finishes and lighting are dated, and there is no acces	s to outdoor d	ining
		option for eating space provided, inadequate circulation							areas.		
	3	Average - Adequate size and condition, needs updates									
	4	or renovations to function well									
	4	Satisfactory - Good size and condition, good circulation, multiple options for eating space (ex: connection to									
		outdoor eating space (ex. connection to									
	5	Very Satisfactory - Generous size, excellent condition									
		and circulation, multiple options for eating space (ex:									
		connection to outdoor eating space)									
	N/A	Does not apply									
١,	11 2	d Services support spaces appropriately configured per				4			Comments		
Ľ	the ed spec								Comments	1.00	4.00
	1	Very unsatisfactory - None provided									
	2	Unsatisfactory - Too small, disconnected, poor condition									
	3	Neutral - Adequate size, average condition, needs updates or renovations to function well									
	4	Satisfactory - Good size, connected, good condition									
	5	Very Satisfactory - Generous size, connected, excellent									
	ŭ	condition									
	N/A	Does not apply							-		

12 - Media Res	sources	1	2	3	4	5	N/A	4	30.00	60%
121	ry/Media Center easily accessible for the occupants and		2					Comments		
visitors to t	the school?							Comments	1.00	2.00
1	Very unsatisfactory - Not accessible							Buried in school with limited to no transparency. No ac	cess to dayli	ght or
2	Unsatisfactory - Limited access, difficult to find, no							windows.		
	transparency									
3	Average - Adequate accessibility, needs updates or									
,	renovations to function well									
4	Satisfactory - Accessible, easy to find, good									
_	transparency, good condition									
5	Very Satisfactory - Accessible, easy to find, excellent									
N/A	transparency, excellent condition Does not apply									
N/A	Boes not apply		l		T	l	I			
12.2 How well o	does the Library/Media Center support quiet study?		2					Comments	1.00	2.00
1	Very unsatisfactory - No quiet study spaces									
2	Unsatisfactory - One area in poor condition, poor									
	acoustic privacy									
3	Average - One or more areas provided, needing									
	updates or renovations to function well									
4	Satisfactory - Clusters or small rooms adjacent to media									
_	center, good condition, good acoustic privacy									
5	Very Satisfactory - Multiple clusters or small rooms									
	adjacent to media center, excellent condition, excellent									
N/A	acoustic privacy									
	Does not apply	l				I	I			
12.3 How well o	does the Library/Media Center support social interaction?				4			Comments	1.00	4.00
1	Very unsatisfactory - No space					•	•	Nice movable, lightweight furniture. Newer furniture.		
2	Unsatisfactory - Too small, poor condition, layout and									
	furnishings do not support informal interaction well									
3	Average - Adequate size and condition, needs updates									
	or renovations to function well.									
4	Satisfactory - Good size, good condition, layout and									
	furnishings support informal interactions									
5	Very Satisfactory - Generous size, excellent condition,									
N1/4	layout and furnishings support informal interactions									
N/A	Does not apply		1	l		1	1	Ţ		
12/1	does the Library/Media Center support collaborative work oups (4-8 students)?			3				Comments	1.00	3.00
in sinding in	Very unsatisfactory - No breakout rooms, no flexible	<u> </u>		<u> </u>	1	<u> </u>	1		1.00	3.00
	furniture, no support									
2	Unsatisfactory - Too small, one area, poor condition									
3	Average - Adequate size, multiple areas provided,									
ű	needing updates or renovations to function well									
4	Satisfactory - Clusters or small rooms adjacent to media									
	center, flexible furniture, good condition									
5	Very Satisfactory - Multiple clusters or small rooms									
	adjacent to media center, flexible furniture, excellent									
	condition									
N/A	Does not apply									

12	- Media Res	sources - Continued	1	2	3	4	5	N/A	·		
1/	How well c	does the Library/Media Center support collaborative work				4			Comments		
12	in larger gr	roups (10-25)?				4			Comments	1.00	4.00
	1	Very unsatisfactory - No gathering areas					•	•		•	
	2	Unsatisfactory - Too small, one common space, limited									
		seating, poor condition									
	3	Average - Adequate size, one common space, needs									
		updates or renovations to function well									
	4	Satisfactory - Good size, multiple common spaces with									
		seating, good condition									
	5	Very Satisfactory - Generous size, multiple commons									
		spaces with seating, excellent condition									
	N/A	Does not apply		,			,		<u></u>	T	
12	2.6 How well o	does the Library/Media Center support technology?			3				Comments	1.00	3.00
_	1	Very unsatisfactory - No vis comm tools				<u> </u>		1		1.00	3.00
	2	Unsatisfactory - Outdated, poorly functioning, or									
	2	insufficient									
	3	Good - Mix of old and new whiteboards/projectors/etc.									
	4	Satisfactory - Projectors, marker boards, smart boards in									
	•	most spaces - good condition									
	5	Very Satisfactory - Projectors, marker boards, smart									
	_	boards in most spaces - new condition									
	N/A	Does not apply									
13	- Technolog	ıv	1	2	3	4	5	N/A		20.00	70%
							l	T	6 .		
13	3.1 How well e	equipped are the facilities with instructional technology?				4			Comments	1.00	4.00
	1	Very unsatisfactory - Limited to no technology present in					•	•	Most classrooms have projection, mobile TV displays	and marker bo	oards
		instructional spaces							and tack boards.		
	2	Unsatisfactory - One type of technology present									
	3	Average - Multiple types of technology, smart boards,									
		poor condition, limited to only certain areas of school									
	4	Satisfactory - Multiple types of technology, smart									
		boards, good condition.									
	5	Very Satisfactory - Multiple types of technology, smart									
		boards, excellent condition									
_	N/A	Does not apply								Т	
13	₹ <i>?</i>	adequate number of power and data outlets in learning			3				Comments		
	spaces?									1.00	3.00
	1	Very unsatisfactory - Outlet configuration does not									
	•	support digital devices throughout school (1 per wall)									
	2	Unsatisfactory - Outlet configuration support digital									
	0	devices only in certain areas of school (2 per wall)									
	3	Average - Outlet configuration support digital devices									
		but not enough capacity throughout school (3 per wall)									
	4	Catiofactory Outlet configuration and district									
	4	Satisfactory - Outlet configuration support digital									
	4	devices with adequate coverage and capacity									
		devices with adequate coverage and capacity throughout school (>3 per wall)									
	4 5	devices with adequate coverage and capacity throughout school (>3 per wall) Very Satisfactory - Excellent outlet configuration to									
		devices with adequate coverage and capacity throughout school (>3 per wall)									

13 - Technology (cont.)	1	2	3	3 4	5	N/	Ą		
13.3 Are there adequate charging locations for devices?			3	3			Comments	1.00	3.00
1 Very unsatisfactory - No centralized charging location				.,	•	•	Charging carts are sparse and scattered around building	ng.	
Unsatisfactory - Centralized charging location, but									
inadequate in size for number of devices									
3 Average - Charging cart or tower but not adequately sized for number of devices									
4 Satisfactory - Charging cart or tower not centralized									
5 Very Satisfactory - Charging cart or tower located									
centralized location. Excellent condition									
N/A Does not apply					1	1			
13.4 Is there adequate AV for presentations spaces – cafeteria and gym?				4			Comments	1.00	4.00
1 Very unsatisfactory - AV not present in one or more							No A/V in the gym but good A/V in the cafeteria.		
space									
Unsatisfactory - AV undersized for room, poor condition									
3 Average - Adequately sized / poor condition OR AV									
undersized / adequate condition									
4 Satisfactory - Good size, good condition									
5 Very Satisfactory - Generous sized, excellent condition									
N/A Does not apply									
13.5 Is there digital media signage at the reception area?			3	3			Comments	0.00	0.00
Very unsatisfactory - No digital media present in reception area							Yes, small.		
2 Unsatisfactory - Undersized, poor condition									
3 Average - Adequately sized / poor condition OR									
undersized / adequate condition									
4 Satisfactory - Media signage present, good sized, good condition									
5 Very Satisfactory - Generously sized, excellent condition									
N/A Does not apply							L		

ation Spaces		2	3	4	į	5 I	N/A		20.00	509
reception area that functions as a security checkpoint for all								Comments	1.00	
Very unsatisfactory - No security checkpoint Unsatisfactory - Checkpoint is too small, poor condition Average - Needs updates or renovations to function well						Į.)
Satisfactory - Good size, good condition Very Satisfactory - Generous size, excellent condition Does not apply										
administration area feel welcoming?		2						Comments	1.00	2.0
Very unsatisfactory - No welcome space Unsatisfactory - Too small, poor lighting and transparency, limited informal seating, poor condition					•			Reception area is small and dated.		
Average - Adequate size and layout, needs updates or renovations to feel welcoming Satisfactory - Good size and layout, good lighting and transparency, informal seating provided Very Satisfactory - Generous size and layout, plenty of										
light and transparency, informal seating provided, excellent condition Does not apply				T					1	
spaces that require it, does the administration area have acoustic privacy?			3					Comments	1.00	3.0
Very unsatisfactory - No acoustic separations Unsatisfactory - Acoustic separations do not perform well Average - Some acoustic separations function okay, but portions need updates or renovations Satisfactory - Good acoustic separations Very Satisfactory - Excellent acoustic separations										
Does not apply										
Very unsatisfactory - Not accessible for public/parent use Unsatisfactory - Limited access, no transparency, poor condition, difficult to find Average - Adequate accessibility, needs updates or renovations to function well Satisfactory - Good accessibility, good transparency, good size and condition		2						Comments	1.00	2.0
3	Unsatisfactory - Checkpoint is too small, poor condition Average - Needs updates or renovations to function well Satisfactory - Good size, good condition Very Satisfactory - Generous size, excellent condition Does not apply Idministration area feel welcoming? Very unsatisfactory - No welcome space Unsatisfactory - Too small, poor lighting and transparency, limited informal seating, poor condition Average - Adequate size and layout, needs updates or renovations to feel welcoming Satisfactory - Good size and layout, good lighting and transparency, informal seating provided Very Satisfactory - Generous size and layout, plenty of light and transparency, informal seating provided, excellent condition Does not apply spaces that require it, does the administration area have acoustic privacy? Very unsatisfactory - No acoustic separations Unsatisfactory - Acoustic separations do not perform well Average - Some acoustic separations function okay, but portions need updates or renovations Satisfactory - Good acoustic separations Very Satisfactory - Excellent acoustic separations Does not apply ence rooms easily accessed for public / parent use? Very unsatisfactory - Limited access, no transparency, poor condition, difficult to find Average - Adequate accessibility, needs updates or renovations to function well	Unsatisfactory - Checkpoint is too small, poor condition Average - Needs updates or renovations to function well Satisfactory - Good size, good condition Very Satisfactory - Generous size, excellent condition Does not apply Idministration area feel welcoming? Very unsatisfactory - No welcome space Unsatisfactory - Too small, poor lighting and transparency, limited informal seating, poor condition Average - Adequate size and layout, needs updates or renovations to feel welcoming Satisfactory - Good size and layout, good lighting and transparency, informal seating provided Very Satisfactory - Generous size and layout, plenty of light and transparency, informal seating provided, excellent condition Does not apply spaces that require it, does the administration area have acoustic privacy? Very unsatisfactory - No acoustic separations Unsatisfactory - Acoustic separations do not perform well Average - Some acoustic separations function okay, but portions need updates or renovations Satisfactory - Good acoustic separations Very Satisfactory - Excellent acoustic separations Does not apply Pence rooms easily accessed for public / parent use? Very unsatisfactory - Limited access, no transparency, poor condition, difficult to find Average - Adequate accessibility, needs updates or renovations to function well	Unsatisfactory - Checkpoint is too small, poor condition Average - Needs updates or renovations to function well Satisfactory - Good size, good condition Very Satisfactory - Generous size, excellent condition Does not apply Idministration area feel welcoming? Very unsatisfactory - No welcome space Unsatisfactory - Too small, poor lighting and transparency, limited informal seating, poor condition Average - Adequate size and layout, needs updates or renovations to feel welcoming Satisfactory - Good size and layout, good lighting and transparency, informal seating provided Very Satisfactory - Generous size and layout, plenty of light and transparency, informal seating provided, excellent condition Does not apply spaces that require it, does the administration area have acoustic privacy? Very unsatisfactory - No acoustic separations Unsatisfactory - Acoustic separations do not perform well Average - Some acoustic separations function okay, but portions need updates or renovations Satisfactory - Good acoustic separations Very Satisfactory - Excellent acoustic separations Does not apply ence rooms easily accessed for public / parent use? Very unsatisfactory - Not accessible for public/parent use Unsatisfactory - Limited access, no transparency, poor condition, difficult to find Average - Adequate accessibility, needs updates or renovations to function well	Unsatisfactory - Checkpoint is too small, poor condition Average - Needs updates or renovations to function well Satisfactory - Good size, good condition Very Satisfactory - Generous size, excellent condition Does not apply Idministration area feel welcoming? Very unsatisfactory - No welcome space Unsatisfactory - Too small, poor lighting and transparency, limited informal seating, poor condition Average - Adequate size and layout, needs updates or renovations to feel welcoming Satisfactory - Good size and layout, good lighting and transparency, informal seating provided Very Satisfactory - Generous size and layout, plenty of light and transparency, informal seating provided, excellent condition Does not apply Spaces that require it, does the administration area have acoustic privacy? Very unsatisfactory - No acoustic separations Unsatisfactory - Acoustic separations function okay, but portions need updates or renovations Satisfactory - Good acoustic separations Very Satisfactory - Excellent acoustic separations Does not apply Pence rooms easily accessed for public / parent use? Very unsatisfactory - Limited access, no transparency, poor condition, difficult to find Average - Adequate accessibility, needs updates or renovations to function well	Unsatisfactory - Checkpoint is too small, poor condition Average - Needs updates or renovations to function well Satisfactory - Good size, good condition Very Satisfactory - Generous size, excellent condition Does not apply Idministration area feel welcoming? Very unsatisfactory - No welcome space Unsatisfactory - Too small, poor lighting and transparency, limited informal seating, poor condition Average - Adequate size and layout, needs updates or renovations to feel welcoming Satisfactory - Good size and layout, good lighting and transparency, informal seating provided Very Satisfactory - Generous size and layout, plenty of light and transparency, informal seating provided, excellent condition Does not apply spaces that require it, does the administration area have acoustic privacy? Very unsatisfactory - No acoustic separations Unsatisfactory - Acoustic separations function okay, but portions need updates or renovations Satisfactory - Good acoustic separations Very Satisfactory - Excellent acoustic separations Does not apply ence rooms easily accessed for public / parent use? Very unsatisfactory - Limited access, no transparency, poor condition, difficult to find Average - Adequate accessibility, needs updates or renovations to function well	Unsatisfactory - Checkpoint is too small, poor condition Average - Needs updates or renovations to function well Satisfactory - Good size, good condition Very Satisfactory - Generous size, excellent condition Does not apply Idministration area feel welcoming? Very unsatisfactory - No welcome space Unsatisfactory - Too small, poor lighting and transparency, limited informal seating, poor condition Average - Adequate size and layout, needs updates or renovations to feel welcoming Satisfactory - Good size and layout, good lighting and transparency, informal seating provided Very Satisfactory - Generous size and layout, plenty of light and transparency, informal seating provided, excellent condition Does not apply spaces that require it, does the administration area have acoustic privacy? Very unsatisfactory - No acoustic separations Unsatisfactory - Acoustic separations do not perform well Average - Some acoustic separations function okay, but portions need updates or renovations Satisfactory - Good acoustic separations Very Satisfactory - Excellent acoustic separations Does not apply ence rooms easily accessed for public / parent use? Very unsatisfactory - Not accessible for public/parent use Unsatisfactory - Limited access, no transparency, poor condition, difficult to find Average - Adequate accessibility, needs updates or renovations to function well	Unsatisfactory - Checkpoint is too small, poor condition Average - Needs updates or renovations to function well Satisfactory - Good size, good condition Very Satisfactory - Generous size, excellent condition Does not apply Idministration area feel welcoming? Very unsatisfactory - No welcome space Unsatisfactory - Too small, poor lighting and transparency, limited informal seating, poor condition Average - Adequate size and layout, needs updates or renovations to feel welcoming Satisfactory - Good size and layout, good lighting and transparency, informal seating provided Very Satisfactory - Generous size and layout, plenty of light and transparency, informal seating provided, excellent condition Does not apply spaces that require it, does the administration area have acoustic privacy? Very unsatisfactory - No acoustic separations Unsatisfactory - Acoustic separations do not perform well Average - Some acoustic separations function okay, but portions need updates or renovations Satisfactory - Good acoustic separations Very Satisfactory - Excellent acoustic separations Does not apply ence rooms easily accessed for public / parent use? Very unsatisfactory - Excellent acoustic separations Unsatisfactory - Limited access, no transparency, poor condition, difficult to find Average - Adequate accessibility, needs updates or renovations to function well	Unsatisfactory - Checkpoint is too small, poor condition Average - Needs updates or renovations to function well Satisfactory - Good size, good condition Very Satisfactory - Generous size, excellent condition Does not apply Idministration area feel welcoming? Very unsatisfactory - No welcome space Unsatisfactory - Too small, poor lighting and transparency, limited informal seating, poor condition Average - Adequate size and layout, needs updates or renovations to feel welcoming Satisfactory - Good size and layout, good lighting and transparency, informal seating provided Very Satisfactory - Generous size and layout, plenty of light and transparency, informal seating provided, excellent condition Does not apply spaces that require it, does the administration area have acoustic privacy? Very unsatisfactory - No acoustic separations Unsatisfactory - Acoustic separations function okay, but portions need updates or renovations Satisfactory - Good acoustic separations Very Satisfactory - Excellent acoustic separations Does not apply ence rooms easily accessed for public / parent use? Very unsatisfactory - Not accessible for public/parent use Unsatisfactory - Limited access, no transparency, poor condition, difficult to find Average - Adequate accessibility, needs updates or renovations to function well	Very unsatisfactory - No security checkpoint Unsatisfactory - Checkpoint is too small, poor condition Average - Needs updates or renovations to function well Satisfactory - Good size, good condition Very Satisfactory - Generous size, excellent condition Does not apply Idministration area feel welcoming? Very unsatisfactory - No welcome space Unsatisfactory - Too small, poor lighting and transparency, limited informal seating, poor condition Average - Adequate size and layout, good lighting and transparency, informal seating provided Very Satisfactory - Goenerous size and layout, plenty of light and transparency, informal seating provided, excellent condition Does not apply Pages that require it, does the administration area have acoustic privacy? Very unsatisfactory - Acoustic separations Unsatisfactory - Acoustic separations function okay, but portions need updates or renovations Very Satisfactory - Some acoustic separations Very Satisfactory - Food accoustic separations Very Satisfactory - Food accoustic separations Very Satisfactory - Loud coessible for public/parent use Unsottisfactory - Limited access, no transparency, poor condition, difficult to find Average - Adequate accessibility, needs updates or renovations to function well	Very unsatisfactory - No security checkpoint Unsatisfactory - Checkpoint is too small, poor condition Average - Needs updates or renovations to function well Satisfactory - Good size, good condition Very Satisfactory - Generous size, excellent condition Does not apply Administration area feel welcoming? Very unsatisfactory - No welcome space Unsatisfactory - Too small, poor lighting and transparency, limited informal seating, poor condition Average - Adequate size and layout, needs updates or renovations to feel welcoming Satisfactory - Good size and layout, peod lighting and transparency, informal seating provided Very Satisfactory - Generous size and layout, plenty of light and transparency, informal seating provided, very Satisfactory - Generous size and layout, plenty of light and transparency, informal seating provided, vexcellent condition Does not apply Very unsatisfactory - No acoustic separations Unsatisfactory - Acoustic separations do not perform well Average - Some acoustic separations function okay, but portions need updates or renovations Very Satisfactory - Cood acoustic separations Unsatisfactory - Cood acoustic separations Does not apply Very unsatisfactory - Excellent acoustic separations Does not apply Very Satisfactory - Excellent acoustic separations Does not apply Very Satisfactory - Limited access, no transparency, poor condition, difficult to find Average - Adequate accessibility, needs updates or renovations to function well