

Educational Suitability Summary Report

Govalle Elementary School

Date: 01/05/2021 Score 94% Very Satisfactory

Govalle Elementary School, serving an enrollment of approximately 370 students, is in east Austin. It was one of the first projects completed as part of the 2017 bond program and fully replaced the old Govalle Elementary School originally built in 1931. The school opened in mid-February 2020 and has 81,000 square feet on 9 acres. The school offers a wide range of programs, including pre-K, dual language and STEM education.

The building has two stories at the studio wing, and there is ample access to daylight throughout. The school has a generous collection of learning spaces, from appropriately sized studios to small group rooms and flexible learning spaces, all meeting the district's Educational Specifications. The outdoor spaces are nicely designed to accommodate both outdoor studios and a generous garden. Existing old growth trees on the site are focal points and provide shade within the courtyards.

Interview Overview

The attendees for the interview included Principal Paula Reyes, Assistant Principal Natasha Canlas, librarian Stacey Smith, special education team leader Candace Fox, special education teacher Henry Jaeger, reading assistant team leader Diana Clemens and head custodian Jose Cazares. When designing the new campus, the community wanted to preserve as many trees on site as possible, and that is a feature that they would like to preserve into the future as well. The interviewees also mentioned their new apiary and artwork they have inherited as important features that should be kept at the school. The playground is important to remain, as it offers a sense of place and connection to the Govalle community.

The staff indicated that it was difficult to predict what programs would need the most space in the school as programs can change over the years. They felt that they did not plan for enough space for support staff in addition to the professional learning center spaces that are present. They lack additional spaces for programs, such as material storage for instructional specialists, or their new SCORES unit. They would like to be able to add programs such as preK-3, but do not have the space for it. Teachers have struggled with material storage and the flexibility of shared spaces but think that better mobile storage solutions could solve these issues. Requests for more adult restrooms were unanimous, as teachers typically wait to use one restroom on the second floor, and it does not lock.

Regarding outdoor learning and the future of teaching environments, they would like better outdoor classroom settings with proper shading and furniture. There is an outdoor garden space, but it is isolated next to the parking lot and outdoor basketball courts. They have learned that when the community uses the courts, they trample through the gardens to retrieve balls, so a fence to protect these areas is needed. Additional seating in the gardens would support teaching opportunities in those spaces. They would like to utilize outdoor spaces to be a more integral part of the teaching

Perkins&Will

Educational Suitability Summary Report

Govalle Elementary School

experience.

The staff would like educational resources on how their building works, including informational signage about its green features. These would help teachers, students and visitors better understand the building. Post-occupancy support for teachers and staff was a point of focus, as most teachers and students have never used these newer types of furniture and teaching spaces. Having time for students to test out their new space would help, since students require more supervision with the space and autonomy to do things on their own.



Assessment Findings

The Educational Suitability Assessment of Govalle Elementary School earned a 94% overall score and places the campus in a category of Very Satisfactory. The assessment consists of seven General Building categories and seven Academic categories. All categories scored within the Very Satisfactory score range.

Very Satisfactory Categories (81-100%):

Exterior

Score is very satisfactory.

There is excellent separation of bus and vehicle pickup and drop-off and adequate stack space. The signage is very clear for the school and circulation, and all three dumpsters adjacent to cafeteria are present.

Outdoor Learning and Activity

Score is very satisfactory.

There is an outdoor studio with some shade and a whiteboard available. There are excellent gardens and a large cistern in the courtyard. One of the two playgrounds has shade.

General Building

Score is very satisfactory.

The corridors are wide and daylit. There is a community room with a stove and small kitchenette available. The gym and cafeteria can be used after-hours with a separate entrance from the parking lot.

Security

Score is very satisfactory.

Educational Suitability Summary Report

Govalle Elementary School

Environmental Quality

Score is very satisfactory.

All studios have ample daylight and views to the exterior. The acoustics in the studios are average as it appears from construction drawings that the walls do not extend all the way to structure above. Sound transmission was mentioned in the interview, with staff stating that noise levels could get high and cause them to raise their voices.

Controllability of Systems

Score is very satisfactory.

Each studio has a thermostat, and there are blinds in all studios and room darkening shades in some spaces, such as the art room. Per lighting drawings, all lighting is dimmable.

Furniture, Fixtures, Equipment

Score is very satisfactory.

There is new furniture throughout the school that is flexible and reconfigurable in most spaces. Dining commons has regular table seating and booth seating.

Academics & Learning

Score is very satisfactory.

Studios are appropriately sized and have excellent access to common collaboration spaces and small group rooms. Many studios have foldable partitions that open to the hallway. There are two maker spaces, one on each level, and there are excellent display opportunities throughout the school.

Visual and Performing Arts

Score is very satisfactory.

Music room and art room are adequately sized and meet Ed Spec requirements. The stage is appropriately sized and was set up with choir risers during the assessment.

PE and Wellness

Score is very satisfactory.

Gym is appropriately sized per Ed Spec. The gym office does not have its own locker and restroom per Ed Spec.

Food Services

Score is very satisfactory.

Cafeteria is appropriately sized per Ed Spec. There is chair storage but no dedicated stage storage.

Media Resources

Score is very satisfactory.

The media center is a light-filled space that can accommodate larger groups as well as space for individual reading. There are nooks at the windows for kids to sit, and there is a connection to the adjacent maker space and outdoor learning area.

Technology

Score is very satisfactory.

Instructional technology is new, and there are charging towers in certain locations. There is a large

Perkins&Will

Educational Suitability Summary Report

Govalle Elementary School

digital display at the school entrance for announcements.

Administration Spaces

Score is very satisfactory.

The admin area feels welcoming. The seating at the entry is not large, but the space is light-filled and has adequate seating. There are two conference rooms available within the admin space, but talking could be heard between the room and the corridor, which indicates that acoustic privacy between rooms may be an issue.

Supporting Photographs




Library is located off main corridor near entry. A moveable glass partition can open the Library up to the corridor where additional informal seating is located. The main corridor is daylit and has a generous amount of space for informal interaction.



Media center has different types of flexible seating and small nooks for individual reading. Doors (shown beyond) open to a secured courtyard with shade and seating.

Supporting Photographs



Learning neighborhood collaboration space has excellent daylight and flexible furniture.



Typical studio has flexible furniture, casework storage and excellent daylight/views.

Supporting Photographs



Outdoor teaching space adjacent to collaboration space has some shade and a whiteboard.



Cafetorium has movable partition between gym and cafeteria. All program elements are appropriately sized per Ed Spec. Stage A/V is new and satisfactory.

Supporting Photographs



Hallway in learning neighborhoods is wide enough with flexible furniture to allow small groups to meet. Glass in the studios to the hallway allows for passive supervision of students.



Maker space on second floor provides power for a variety of activities. Large sliding doors open the room to a large commons area.

Supporting Photographs



Outdoor gardens with an additional outdoor classroom space adjacent. This space is far removed from studios.



Entry has generous overhang and lower canopy for weather protection at pickup and drop-off.



Perkins&Will

Austin ISD Educational Suitability Assessment Criteria

General Building

School Name	Walk Attendees:	Date:
Govalle Elementary School	Carlos Cruz / Lynn Petermann	01.05.2021
<u> </u>		

1 - F	xterior		1	2	3	4	5	N/A		8.75	100%
1 - 6		e permit desirable separation of vehicular, bus and	<u> </u>		<u>ა</u>	4	3	IN/ A		6.75	100%
1.1	pedestrian						5		Comments	1.00	5.00
	1	Very unsatisfactory - Bus, car and pedestrian all happen							Excellent site circulation and adequate queueing space	ce.	
		at the same location									
	2	Unsatisfactory - Cars and buses mix, pedestrians are separated									
	3	Average - Buses, cars, and pedestrians are separate but									
		stack space is small									
	4	Satisfactory - Buses, cars, and pedestrians are separate									
		but drop off does not have a canopy or a holding place									
		like a commons or cafeteria									
	5	Very satisfactory - Buses, cars, and pedestrians are									
		separate and drop off area has a canopy and									
		destination									
	N/A	Does not apply	,	, ,				,	,		
1.2		ng easily identified with appropriate signage and					5		Comments		
1.2	community	wayfinding?					0		Comments	0.25	1.25
	1	Very unsatisfactory - Campus has no signage /							Signage is clear and easy to use. Nice digital marque	e at front of so	chool.
		wayfinding									
	2	Unsatisfactory - Signage/wayfinding is faded/hidden									
	3	Average - Signage / wayfinding visible but not apparent									
	4	Satisfactory - Signage / wayfinding is visible but not									
		good condition									
	5	Very satisfactory - Signage and wayfinding is visible									
		and easy to use									
	N/A	Does not apply									

O2/11/2022 ²

1 - E	xterior (co	1	2	3	4	5	N/A	4			
1.3	Is the dump	oster accessible for trash / compost disposal?					5		Comments	0.50	2.50
	1 2 3 4 5	Very unsatisfactory - No compost present, route has obstacles (stairs, curbs, barriers) to dumpster Unsatisfactory - Compost is present. Route has obstacles to dumpster Average - Compost is present (<100' to cafeteria), Route to dumpster is free and clear but the two are not directly adjacent. Satisfactory - Compost and dumpster are directly adjacent and route is barrier free Very Satisfactory - Compost and dumpster are directly adjacent and route is barrier free. Dumpster are shaped / positioned so people of all heights can access it.							3 dumpsters for recycling/trash/compost near kitche	n/cafeteria.	
2 - (N/A Outdoor Le	Does not apply arning and Activities	1	2	3	4	5	N/A		15.00	93%
2.1	Are outdoo	r studios and support spaces appropriately configured per				T	5		Comments	1.00	5.00
	1 2 3 4	Very unsatisfactory - No dedicated outdoor studios Unsatisfactory - Too small, poor condition, disconnected from learning spaces, no flexibility, no shade provided Average - Adequate size, adequate condition, needs some renovations or updates to function well, 50% or less shade coverage over studio area Satisfactory - Good size, good condition, connected to learning spaces, good flexibility, more than 50% shade coverage over studio area Very satisfactory - Generous size, excellent condition, connected to learning spaces, excellent flexibility, full shade coverage over studio area							Nice studio outdoor with white board. Shade provide area in courtyard. Shade is not provided at additionathe garden.		_
2.2		Does not apply claygrounds (elementary only) and support spaces per the ed spec?				4			Comments	1.00	4.00
	3	Very unsatisfactory - No dedicated active playground Unsatisfactory - Too small, poor condition, no shade provided Average - Adequate size, adequate condition, needs some renovations or updates to function well, 50% or less shade coverage over play structure				•		ı	No shade over playground big kid playground. Shad playground		
	4 5 N/A	Satisfactory - Good size, good condition, more than 50% shade coverage over play structure Very satisfactory - Generous size, excellent condition, full shade coverage over play structure Does not apply									

2 - Outdoor Learning and Activities (cont)	1	2	3	4	5	N/A	A.		
2.3 Are gardens and support spaces appropriately configured per the ed spec? (evaluation on infrastructure not condition of plants)				4			Comments	0.00	0.00
1 Very unsatisfactory - No dedicated gardens 2 Unsatisfactory - Too small, poor condition, disconnected from learning spaces, no flexibility, no accessible water source 3 Average - Adequate size, adequate condition, needs some renovations or updates to function well, water source is difficult to access 4 Satisfactory - Good size, good condition, connected to learning spaces, good flexibility, water source is accessible with 100 ft hose 5 Very Satisfactory - Generous size, excellent condition, connected to learning spaces, excellent flexibility, water source is less than 50ft from the garden or has irrigation							Monitoring answer, but does not affect overall score f & Activity. Excellent gardens with irrigation. Somewhat removed studios.		
N/A Does not apply Are the rain gardens and/or cisterns appropriately configured per the ed spec?					5		Comments	0.00	0.00
1 Very unsatisfactory - No rain gardens or cisterns 2 Unsatisfactory - Too small, poor condition, not functioning, disconnected 3 Average - Adequate size, adequate condition, is connected, needs some renovations or updates to function well 4 Satisfactory - Good size, good condition, functions properly 5 Very Satisfactory - Generous size, excellent condition, exceptional functionality, connected to learning spaces, educational signage provided							Monitoring answer, but does not affect overall score f & Activity , Large cistern in courtyard		
N/A Does not apply 2.5 Does the school have animal husbandry? (optional)	1						Comments	0.00	0.00
1 No 5 Yes	-						Comments	0.00	0.00
2.6 Does the school have nature loop trails? (optional) No 5 Yes					5		Comments	0.00	0.00
2.7 Does the school have a learning pond? (optional) 1 No 5 Yes					5		Comments	0.00	0.00
2.8 Does the school have a grass play field and walking trail? 1 No 5 Yes					5		Comments	1.00	5.00

	3 - General Bu	1	2	3	4	5	N/A		11.25	93%	
	3.1	r circulation routes wide enough to safely and effectively					5		Comments	0.50	0.50
	1 2 3 4 5	Very unsatisfactory - Primary circulation is 5'-0" to 6'-0" wide Unsatisfactory - Primary circulation is 6'-0" to 7'-0" wide Average - Primary circulation is 7'-0" to 8'-0" wide Satisfactory - Primary circulation is 8'-0"-10'-0" wide Very satisfactory - Primary circulation is 10'-0"+ wide							Review per construction documents from 2017 Bond. O" and over in some locations.	0.50 Primary circulo	2.50 ation 10'
	N/A	Does not apply									
	3.2 functions w	unity use areas arranged so that the school can allow night vithout full school access?				4			Comments	0.75	3.00
	1 2 3	Very unsatisfactory - Cafeteria, gym, and library cannot be accessed after hours Unsatisfactory - Only one of the public spaces (Cafeteria, Gym and Library) can be accessed from parking and secured after hours Average - Only two of the public spaces can be accessed from parking and secured after hours							Gym and cafeteria (not library) can be accessed from parking lot.	n separate doc	or at
	4	Satisfactory - All of the public spaces can be accessed from parking and secured from the rest of the building but not individually									
	5	Very satisfactory - Cafeteria, gym, and library can be accessed from parking and locked off from rest of campus for night/evening use with their own entrance									
	N/A	Does not apply									
	3.3 Is there a co	community room that is a dedicated meeting space outside unction?					5		Comments	0.75	3.75
	1 2 3 4 5	Very unsatisfactory - No dedicated community room Unsatisfactory - Community room but within school function, no access after school hours Average - Community room, moderate size, but need some renovations or updates to function well Satisfactory - Community room, good size /layout, meets needs /functions well Very Satisfactory - Community room, generous size, nice condition, functions appropriately outside of school function							Community Room B108 is directly accessible from ent amenities of a full kitchen, restroom and an office.	ry vestibule wi	th all
-	N/A	Does not apply		l				l	T	T	
	3.4 students ar	eneral appearance of the school convey pride for the nd community?					5		Comments	0.25	1.25
	1 2 3 4 5	Very unsatisfactory - General appearance is poor Unsatisfactory - General appearance is aged but ok Average - General appearance is good Satisfactory - General appearance shows pride in campus and student works Very satisfactory - General appearance shows pride in campus and student works and is welcoming to the community Does not apply									

	4 - Security		1	2	3	4	5	N/A	1	16.25	
	4.1 Does the fa	cility have key card access at all major entries?							Comments	0.25	
	1	Very unsatisfactory - No entries			1						
	2	Unsatisfactory - 1/4 of major entries									
	3	Average - 1/2 of major entries									
	4	Satisfactory - 3/4 of major entries									
	5	Very satisfactory - All of major entries									
	N/A	Does not apply									
r	IN/A	Does not apply									
	4.2 How adequ	rate is site lighting and security for the campus overall?							Comments	1.00	
	1	Very unsatisfactory - No exterior lighting, no secure perimeter									
	2	Unsatisfactory - Lighting is limited to front entry only, parking lot lighting poor, security is minimal									
	3	Average - Lighting at all night-use entries and parking lot, but poor condition. Security is moderate									
	4	Satisfactory - Lighting at all night-use entries and									
		parking lots, good condition, signage less visible,									
		perimeter is well secured but needs updates									
	5	Very satisfactory - Signage, parking lots, and entries are									
		well lit, visible and easy to use, perimeter is very secure									
	N/A	Does not apply									
ſ		office located at the school entry and configured with a									
	71.3	ibule to the main corridor?							Comments	1.00	
L	1	Very unsatisfactory - No secure vestibule, office located		1 1							
		far from main entry, allows visitors access to school									
		unsupervised									
	2	Unsatisfactory - No secure vestibule, office located									
		somewhat far from main entry, minimal supervision of									
		visitors									
	3	Average - Office close to entry, views of front door, but									
		no secure vestibule									
	4	Satisfactory - Office is well-located with a secure									
		vestibule, but needs updates									
	5	Very satisfactory - Office well-located with secure									
		vestibule and all appropriate security features									
	N/A	Does not apply									
ſ	ls there end	ough interior transparency for faculty to passively supervise					_		Comment		
	4.4 learners an	d their activities who are not in studios?					5		Comments	1.00	5.00
	1	Very unsatisfactory - No transparency of walls			l l				Large and windows adjacent to full glass aluminum f	rame doors into	1
	2	Unsatisfactory - Limited transparency in certain locations							classrooms and folding glass partitions to views into		
		, , , , , , , , , , , , , , , , , , , ,									
	3	Average - Good transparency in certain locations but									
		inadequate or missing in other locations of school									
	4	Satisfactory - Adequate transparency throughout the									
		school									
	5	Very satisfactory - Excellent transparency throughout the									
		school									
	N/A	Does not apply									

Perkins&Will 02/11/2022 ⁶

3			Comments Review per construction documents from 2017 Bond. studios, wall tagged as F3 (detailed on sheet A7.00A does not show any insulation and only goes to 6" about the comments of the co) between class	
			studios, wall tagged as F3 (detailed on sheet A7.00A) between class	
			Possible sound transmission at this wall location. Oth are detailed going to structure above with insulation	ner walls tagge	ling.
	5		Comments	1.00	5.00
	5		Comments	1.00	5.00
			Typical studio has two large windows.		
	5		Comments	1.00	5.00
·	,		Each studio has two large windows as well as collaborate windows.	oration spaces h	have
		5	5	5 Comments Typical studio has two large windows. 5 Comments Each studio has two large windows as well as collaborations.	5 Comments 1.00 Typical studio has two large windows. 5 Comments 1.00 Each studio has two large windows as well as collaboration spaces

Perkins&Will 02/11/2022 ⁷

5 - E	nvironmer	1	2	3	4	5	N/A				
5.5	Does the b	uilding have odor or pest problems?					5		Comments	1.00	5.00
	1 2 3 4 5 N/A	Very unsatisfactory - Evidence of both pests and odors Unsatisfactory - Evidence of pests or odors Average - Limited evidence of pests, no odors Satisfactory - No evidence of pests / odors, school cleanliness in good condition Very Satisfactory - No evidence, school cleanliness in excellent condition Does not apply									
6 - C	Controllabi	lity of Systems	1	2	3	4	5	N/A		12.50	100%
6.1	Does the st	udio thermostat allow for individual control?					5		Comments	0.50	2.50
	1 5	No Yes									
6.2	Are shades	provided to control natural light in learning spaces?					5		Comments	1.00	5.00
	1 2 3 4 5 N/A	Very unsatisfactory - No, windows are covered with boards/paper Unsatisfactory - No, windows have no light control Average - Yes, but poor condition blinds Satisfactory - Yes, blinds Very satisfactory - Blackout shades Does not apply							Horizontal blinds scheduled for most rooms. Room descheduled at some other special rooms, such as Art Rareas with electrical window shades.	•	
6.3	What is the	quality of lighting controls in the studios?					5		Comments	1.00	5.00
	1 Very unsatisfactory - Single switch only per room 2 Unsatisfactory - Alternating rows switch off 3 Average - Alternating lamps in single fixtures switch off 4 Satisfactory - Tri level switching 5 Very satisfactory - Dimmable N/A Does not apply								Per lighting drawings all lighting dimmable.		

7 - Furniture, Fixtures & Equipment	1	2	3	4	5	N/A		18.75	95%
7.1 What is the current condition of the furniture?					5		Comments	0.75	3.75
1 Very unsatisfactory - Damaged or broken, non- functioning				•					
2 Unsatisfactory - Torn/ bent/ wrong size									
3 Average - Scratched/dented/marked									
4 Satisfactory - Not new, but sturdy and clean									
5 Very satisfactory - New									
N/A Does not apply									
Are a variety of furniture types being accommodated throughout the									
7.2 school - learning commons, dining commons, other multi-use spaces?					5		Comments		
								1.00	5.00
 Very Unsatisfactory - Same furniture used in all spaces 							All collaboration spaces have flexible moveable furni	iture. Dining co	mmons
2 Unsatisfactory - Furniture variety in one multi-use space							has booths and regular table seating.		
3 Average - Furniture variety in more than one multi-use									
space									
4 Satisfactory - All multi-use spaces have greater than one									
type of furniture									
5 Very satisfactory - All multi-use spaces have greater than two types of furniture									
N/A Does not apply									
7.3 How well does furniture accommodate rapid reconfiguration of a				4			Community		
7.3 space?				4			Comments	1.00	4.00
l Very Unsatisfactory - Furniture is fixed or very heavy							Multiple configurations are possible, but some of it is	not easy to mo	ove.
2 Unsatisfactory - Furniture does not allow desks to be									
configured as individuals, small groups, or large groups 3 Average - Mix of furniture that can reconfigure but is									
cumbersome to move									
4 Satisfactory - Furniture is flexible for multiple									
configurations of space									
5 Very satisfactory - Furniture is flexible for multiple									
configurations of space, easy to move and stack N/A Does not apply									
N/A Does not apply									
7.4 Is the furniture ergonomic and size appropriate for grade level?					5		Comments	1.00	5.00
Very unsatisfactory - Desk with attached chair									
combinations too small for grade level									
2 Unsatisfactory - Desk with attached chair combinations									
3 Average - Mix of studios with tables/loose chairs and desks with fixed seats									
4 Very satisfactory - Tables with loose chairs									
5 Very satisfactory - Tables with loose chairs that allow									
students to be active									
N/A Does not apply									

Perkins&Will 02/11/2022 ⁹

Waste	1	2	3	4	5	N/A	5.00	8
Do studios and corridors have blue recycle bins with bilingual instructions and/or image sorting instructions?				4			Comments 0.50	2
1 Very unsatisfactory - There are no recycling and landfill bins and signage are sparse or infrequent, OR there are only landfill bins with no recycling bins. 2 Unsatisfactory - Bins and signage are sparse or infrequent and/or lack clear signage. 3 Average - 50% of corridors and studios have both a landfill bin and a recycle bin in an accessible location. The containers have clear signage. 4 Satisfactory - 75% of studios and corridors have a visible landfill and recycle collection containers in an accessible location. The containers have clear signage. 5 Very satisfactory - All studios / corridors (100%) have visible landfill and recycle collection containers in accessible locations. The containers have clear signage, and the style and format is consistent and uniform							A score for this category is being recorded, but this category is not calculated in the overall ESA average. Difficult to tell during Covid protocols.	•
across campus. N/A Does not apply Does the cafeteria (or wherever meals are served) have at least one of each: green compost bin, blue recycle bin, and landfill bin? Are the bins labelled clearly with bilingual and/or image sorting?				4			Comments	
1 Very unsatisfactory- There may be landfill bins, but there are no compost and/or recycle bins. There is not clear sorting signage. 2 Unsatisfactory- Recycle, landfill, and compost bins are present, but the bins are scattered and no co-located next to one another. Signage is absent or inconsistent. 3 Average- There is at least one waste station with all three bins (recycle, compost, landfill) located with close proximity to one another. The signage is visible and consistent. 4 Satisfactory- There are several waste stations as described above 5 Very Satisfactory - There are several waste stations as described above, and additional signage in the cafeteria that encourages recycling/composting. N/A Does not apply							Difficult to tell during Covid protocols.	<u> </u>



Perkins&Will

Austin ISD Educational Suitability Assessment Criteria

Academics - Elementary School

condition

Does not apply

N/A

	School No	ime							Walk Attendees:	Date:	
	Govalle E	lementary School							Carlos Cruz / Lynn Petermann	01.05.2021	
3 - A	cademics	& Learning	1	2	3	4	5	N/A		70.00	93%
8.1	Are studios	appropriately configured per the ed spec?					5		Comments	1.00	5.00
	1	Very unsatisfactory - Too small, no flexibility, disconnected							Studios at 855 SF		
	2	Unsatisfactory - Too small, only one area for all teaching methods, limited flexibility, disconnected									
	3	Neutral - Adequate size, multiple areas for different teaching methods, adequate flexibility, limited transparency and connection to other studios and shared learning spaces, needs updates or renovations to function well.									
	4	Satisfactory - Good size, multiple areas for different teaching methods, good flexibility, good transparency and connection to other studios and shared learning spaces									
	5	Very Satisfactory - Generous size, multiple areas for different teaching methods, excellent flexibility, generous display area and visual teaching tools, excellent transparency and connection with other studios and shared learning spaces									
	N/A	Does not apply									
8.2		and Kinder have appropriate support spaces such as and storage per the ed spec?					5		Comments	1.00	5.00
	1	Very unsatisfactory - None provided									
	2	Unsatisfactory - Too small, disconnected, poor condition									
	3	Neutral - Adequate size, average condition, needs updates or renovations to function well									
	4	Satisfactory - Good size, connected, good condition									
	5	Very Satisfactory - Generous size, connected, excellent									

O2/11/2022 ²

8 - Acade	mics &	Learning (cont.)	1	2	3	4	5	N/A			
8.3 Do st ed sp		ve appropriate support spaces such as storage per the					5		Comments	1.00	5.00
		/ery unsatisfactory - None provided Jnsatisfactory - Too small, disconnected, poor condition							Casework storage		
	ι	Neutral - Adequate size, average condition, needs updates or renovations to function well									
	5 V	Satisfactory - Good size, connected, good condition /ery Satisfactory - Generous size, connected, excellent condition									
٨	N/A [Does not apply									
	pical lea boration	rning neighborhoods have small group rooms and open space?					5		Comments	1.00	5.00
	2 L f r 3 A 4 S 4 S	Very unsatisfactory - No breakout rooms or open collaboration spaces are provided Unsatisfactory - Too small or too few, poor condition, no elexibility, lacks visual connection to learning neighborhood, poor acoustic privacy Average - Adequate size, adequate condition, needs some renovations or updates to function well Catisfactory - Good size, good condition and flexibility, ransparency and connection to learning neighborhood, acoustic privacy Very Satisfactory - Generous size, excellent condition and flexibility, transparency and connection to learning neighborhood, acoustic privacy									
Areo		Does not apply sudios large enough to support project-based learning									
	multiple t	teaching modalities?				4			Comments	1.00	4.00
	2 l	Very unsatisfactory - Too small, no flexibility, does not support project-based learning Unsatisfactory - Undersized, decentralized resources, imited flexibility							Studios are not overly generous but still have a satisf flexibility.	actory amount	of
	ι	Average - Adequate size, needs some renovations or updates to function well satisfactory - Good size, centralized resources, good									
	f	lexibility									
	r	/ery Satisfactory - Generous size, centralized project esources, excellent flexibility									
N	1/A [Does not apply									

Perkins&Will 02/11/2022 ³

8 - A	cademics 8	& Learning (cont.)	1	2	3	4	5	N/A	1		
8.6	Are Maker S the ed spec	Spaces and support spaces appropriately configured per ?					5		Comments	1.00	5.00
	1 2 3 4 5 N/A	Very unsatisfactory - No dedicated maker spaces Unsatisfactory - Too small, poor condition, disconnected from learning spaces, no flexibility Average - Adequate size, adequate condition, needs some renovations or updates to function well Satisfactory - Good size, good condition, connected to learning spaces Very Satisfactory - Generous size, excellent condition, connected to learning spaces Does not apply							Two maker spaces - one on first floor, one on second. and infrastructure	Excellent flex	ibility
8.7		rofessional Learning Center in the learning neighborhood?				4			Comments	1.00	4.00
	1 2 3 4 5	Very unsatisfactory - No dedicated space for Professional Learning Center Unsatisfactory - Too small, poor condition, disconnected Average - Adequate size, adequate condition, needs some renovations or updates to function well Satisfactory - Good size, good condition, connected Very Satisfactory - Generous size, excellent condition, connected							Only one PLC per level, not per learning neighborhoo shares with maker space.	d. PLC on secc	and floor
8.8	N/A Is there a de	Does not apply edicated science room and support space?	1						Comments	0.00	0.00
	1 5	No Yes							Monitoring answer, but doesn't affect overall score.	3.33	
8.9		dequate places to display the evidence and artifacts of oth 2D and 3D)?					5		Comments	1.00	5.00
	1 2 3 4 5	Very unsatisfactory - No dedicated space Unsatisfactory - Too small, non-dedicated, poor condition Average - Adequate size, adequate condition, needs updates or renovations to function well Satisfactory - Good size, good condition Very Satisfactory - Generous size, excellent condition							Nice displays for 3-D artifacts at music and art room.		
	NI/A	Door not apply									

Perkins&Will 02/11/2022 ⁴

8 - A	cademics &	& Learning (cont.)	_1	2	3	4	5	N/A			
0.10	Does the bu	uilding provide adequate opportunities for					_		6		
8.10		achers to collaborate in varying group sizes?					5		Comments	1.00	5.00
	1	Very unsatisfactory - No space to support collaboration						•			
		in various sizes.									
	2	Unsatisfactory - Too small, inflexible, only one option,									
		does not support a variety of group sizes									
	3	Average - Adequate space for collaboration, needs									
		updates or renovations to function well.									
	4	Satisfactory - Good size, good condition, multiple									
		options to support a variety of group sizes									
	5	Very Satisfactory - Generous size, excellent condition,									
		multiple options to support a variety of group sizes									
	N/A	Does not apply									
8.11	Does the bu	uilding provide opportunities for informal interaction?					5		Comments		
										1.00	5.00
	1	Very unsatisfactory - No space							Multiple lobby spaces to support informal interaction	n and collabor	ation
	2	Unsatisfactory - Too small, poor condition, layout and							spaces / small groups in studio wings.		
		furnishings do not support informal interaction well									
	3	Average - Adequate size and condition, needs updates									
	4	or renovations to function well.									
	4	Satisfactory - Good size, good condition, layout and furnishings support informal interactions									
	5	Very Satisfactory - Generous size, excellent condition,									
	3	layout and furnishings support informal interactions									
	N/A	Does not apply									
	Does the lea	arning neighborhood / building provide adequate						l		1	
8.12		es for students to work independently?				4			Comments	1.00	4.00
	1	Very unsatisfactory - No breakout rooms/small study							There are small group rooms and breakout space in		
	•	spaces							independent study is dependent upon furniture set-u		Jut
	2	Unsatisfactory - Too small, poor condition, no acoustic							Independent study is dependent apoil furniture set-t	ap.	
	_	privacy, only one space for independent work,									
		disconnected from learning neighborhood									
	3	Average - Adequate size and condition, needs updates									
	-	or renovations to function well.									
	4	Satisfactory - Good size and condition, acoustic privacy,									
		variety of independent work space options, connected to									
		learning neighborhood									
	5	Very Satisfactory - Generous size, excellent condition,									
	acoustic privacy, variety of independent work space										
		options, connected to learning neighborhood									
	N/A	Does not apply									

O2/11/2022 ⁵

8 - A	cademics (& Learning (cont.)						
8.13	Are Special spec?	Education spaces appropriately configured per the ed		4		Comments	1.00	4.00
	1 2	Very unsatisfactory - Too small, no flexibility, disconnected Unsatisfactory - Too small, only one area for all teaching						
	3	methods, limited flexibility, disconnected Neutral - Adequate size, multiple areas for different teaching methods, adequate flexibility, limited transparency and connection to other studios and shared learning spaces, needs updates or renovations to						
	4	function well. Satisfactory - Good size, multiple areas for different teaching methods, good flexibility, good transparency and connection to other studios and shared learning						
	5	spaces Very Satisfactory - Generous size, multiple areas for different teaching methods, excellent flexibility, generous display area and visual teaching tools, excellent transparency and connection with other studios and shared learning spaces						
	N/A	Does not apply						
8.14		Education support spaces, such as storage, space for ver, appropriately configured per the ed spec?		4		Comments	1.00	4.00
	1 2 3	Very unsatisfactory - None provided Unsatisfactory - Too small, disconnected, poor condition Neutral - Adequate size, average condition, needs updates or renovations to function well				Storage missing within Special Education Room A130	on first floor.	
	4 5	Satisfactory - Good size, connected, good condition Very Satisfactory - Generous size, connected, excellent condition						
	N/A	Does not apply						
8.15		ble restrooms and changing rooms readily available to the ucation spaces?			5	Comments	1.00	5.00
	1 5	No Yes						

Perkins&Will 02/11/2022 ⁶

9	- Visual and	Performing Arts	1	2	3	4	5	N/A	A	15.00	100%
ç	Are music s per the ed	paces and the cafeteria stage appropriately configured spec?					5		Comments	1.00	5.00
	1	Very unsatisfactory - Too small, missing program spaces							Cafeteria stage is adequately sized - accommodates	choir risers. Ex	cellent
	2	Unsatisfactory - Too small, poor condition							A/V equipment. Just outside of cafeteria is an exterio	r theater area	that
	3	Neutral - Adequate size, adequate condition, needs							provides a presentation space outside.		
		updates or renovations to function well.									
	4	Satisfactory - Good size, good condition									
	5	Very Satisfactory - Generous size, excellent condition									
	N/A	Does not apply									
	Are music o	and performance storage spaces appropriately configured					5		Comments		
7	per the ed	spec?					5		Comments	1.00	5.00
	1	Very unsatisfactory - None provided									
	2	Unsatisfactory - Too small, disconnected, poor condition									
	3	Neutral - Adequate size, average condition, needs									
		updates or renovations to function well									
	4	Satisfactory - Good size, connected, good condition									
	5	Very Satisfactory - Generous size, connected, excellent									
		condition									
	N/A	Does not apply			ı						
9		Arts spaces and storage appropriately configured per the					5		Comments		
	ed spec?				<u> </u>					1.00	5.00
	ļ	Very unsatisfactory - Too small, missing program spaces									
	2	Unsatisfactory - Too small, poor condition									
	3	Average - Adequate size, adequate condition, needs									
		some renovations or updates to function well									
	4	Satisfactory - Good size, good condition									
	5	Very Satisfactory - Generous size, excellent condition									
	N/A	Does not apply									

Perkins&Will 02/11/2022 ⁷

ľ	10 - PE and \		1	2	3	4	5	N/A	4	10.00	90%
		e campus meet the ed spec standard for physical education					5		Comments		
	progran	n spaces?					0		Comments	1.00	5.00
	1	Very unsatisfactory - Too small, missing program spaces							Light-filled space. Square footage is right at 3,000SF	and meets Ed	Spec.
	2	Unsatisfactory - Too small, poor condition									
	3	Average - Adequate size, adequate condition, needs									
		some renovations or updates to function well									
	4	Satisfactory - Good size, good condition									
	5	Very Satisfactory - Generous size, excellent condition									
	N/A	Does not apply									
	10.2 Are the	physical education storage spaces appropriately configured				4			Comments		
	per the	ed spec?				4			Comments	1.00	4.00
	1	Very unsatisfactory - None provided				•			PE office doesn't have its own restroom/locker.		
	2	Unsatisfactory - Too small, disconnected, poor condition									
	3	Neutral - Adequate size, average condition, needs									
		updates or renovations to function well									
	4	Satisfactory - Good size, connected, good condition									
	5	Very Satisfactory - Generous size, connected, excellent									
		condition									
	N/A	Does not apply									
	11 - Food Sei	vices	1	2	3	4	5	N/A	4	10.00	90%
	11.1 Is the Di	ning Commons appropriately configured per the ed spec?					5		Comments	1.00	5.00
	1	Very unsatisfactory - Too small, missing program spaces							Adequately sized and has two types of seating. Has a	access to outdo	oor
	2	Unsatisfactory - Too small, poor condition, only one							picnic tables.		
	3	option for eatina space provided. inadeauate circulation Average - Adequate size and condition, needs updates									
		or renovations to function well									
	4	Satisfactory - Good size and condition, good circulation,									
		multiple options for eating space (ex: connection to									
		outdoor eating space)									
	5	Very Satisfactory - Generous size, excellent condition									
		and circulation, multiple options for eating space (ex:									
	N1/A	connection to outdoor eating space)									
-	N/A	11.2	1	ı	1	1	1	1			
	11.2 Are the	Food Services support spaces appropriately configured per				4			Comments	1.00	4.00
L	the ea s	•	<u> </u>		<u> </u>	1				1.00	4.00
	•	Very unsatisfactory - None provided							Chair storage but no stage storage.		
	2	Unsatisfactory - Too small, disconnected, poor condition									
	3	Neutral - Adequate size, average condition, needs									
	4	updates or renovations to function well									
	4 5	Satisfactory - Good size, connected, good condition									
	5	Very Satisfactory - Generous size, connected, excellent									
	N/A	condition Does not apply									

12 - Media Res	ources	1	2	3	4	5	N/A	4	30.00	87%
ls the Libra	ry/Media Center easily accessible for the occupants and				4			Comments		
12.1 visitors to the	he school?				4			Comments	1.00	4.00
1	Very unsatisfactory - Not accessible			•				Visitors can access directly from outside, but not easily	found since i	t is
2	Unsatisfactory - Limited access, difficult to find, no							obscured from the parking lot. Centralized location w	ithin school.	
	transparency									
3	Average - Adequate accessibility, needs updates or									
	renovations to function well									
4	Satisfactory - Accessible, easy to find, good									
	transparency, good condition									
5	Very Satisfactory - Accessible, easy to find, excellent									
N1/A	transparency, excellent condition									
N/A	Does not apply	1	1	ı		1				
12.2 How well d	oes the Library/Media Center support quiet study?				4			Comments	1.00	4.00
1	Very unsatisfactory - No quiet study spaces							One small meeting room adjacent to library share wit	h Maker Spac	e. Small
2	Unsatisfactory - One area in poor condition, poor							nooks provided but not acoustically separate.		
	acoustic privacy									
3	Average - One or more areas provided, needing									
4	updates or renovations to function well									
4	Satisfactory - Clusters or small rooms adjacent to media									
5	center, good condition, good acoustic privacy Very Satisfactory - Multiple clusters or small rooms									
J	adjacent to media center, excellent condition, excellent									
	acoustic privacy									
N/A	Does not apply									
12.3 How well d	oes the Library/Media Center support social interaction?					5		Comments	1.00	5.00
1	Very unsatisfactory - No space			<u> </u>	<u> </u>	<u> </u>	<u> </u>	Learning stair in corridor seen as an extension of Med		5.00
2	Unsatisfactory - Too small, poor condition, layout and							Learning stair in comdor seem as an extension of Med	iu.	
-	furnishings do not support informal interaction well									
3	Average - Adequate size and condition, needs updates									
	or renovations to function well.									
4	Satisfactory - Good size, good condition, layout and									
	furnishings support informal interactions									
5	Very Satisfactory - Generous size, excellent condition,									
	layout and furnishings support informal interactions									
N/A	Does not apply	,						<u>, </u>		
1.7 /1	oes the Library/Media Center support collaborative work				4			Comments		
in small gro	oups (4-8 students)?							Comments	1.00	4.00
1	Very unsatisfactory - No breakout rooms, no flexible							Areas that appear to support small groups, but no sm	all rooms. Smo	all
	furniture, no support							conference room next to maker space to allow for sm	all groups to n	neet.
2	Unsatisfactory - Too small, one area, poor condition									
3	Average - Adequate size, multiple areas provided,									
	needing updates or renovations to function well									
4	Satisfactory - Clusters or small rooms adjacent to media									
5	center, flexible furniture, good condition Very Satisfactory - Multiple clusters or small rooms									
3	adjacent to media center, flexible furniture, excellent									
	condition									
N/A	Does not apply									

12 - Media Resources - Continued	1	2	3	4	5	N/A	N.		
How well does the Library/Media Center support collaborative work					5		Comments		
in larger groups (10-25)?					3		Comments	1.00	5.00
1 Very unsatisfactory - No gathering areas							Learning stair adjacent to Media and flexible seating	g in library to a	llow for
 Unsatisfactory - Too small, one common space, limited 							larger groups to meet.		
seating, poor condition									
3 Average - Adequate size, one common space, needs									
updates or renovations to function well									
4 Satisfactory - Good size, multiple common spaces with									
seating, good condition									
5 Very Satisfactory - Generous size, multiple commons									
spaces with seating, excellent condition									
N/A Does not apply				1	ı	1	T		
12.6 How well does the Library/Media Center support technology?				4			Comments	1.00	4.00
1 Very unsatisfactory - No vis comm tools							Appears to have one area with multiple computer st	ations and one	;
 Unsatisfactory - Outdated, poorly functioning, or 							location with marker board. Digital display on wheel	ls present.	
insufficient									
3 Good - Mix of old and new whiteboards/projectors/etc.									
4 Satisfactory - Projectors, marker boards, smart boards in									
most spaces - good condition									
5 Very Satisfactory - Projectors, marker boards, smart									
boards in most spaces - new condition									
N/A Does not apply									
13 - Technology	1	2	3	4	5	N/A		20.00	100%
13.1 How well equipped are the facilities with instructional technology?					5		Comments	1.00	5.00
1 Very unsatisfactory - Limited to no technology present in				ļ		ļ		1.00	5.00
instructional spaces									
2 Unsatisfactory - One type of technology present									
3 Average - Multiple types of technology, smart boards,									
poor condition, limited to only certain areas of school									
4 Satisfactory - Multiple types of technology, smart									
boards, good condition.									
5 Very Satisfactory - Multiple types of technology, smart									
boards, excellent condition									
N/A Does not apply									
ls there an adequate number of power and data outlets in learning					5		Comments		
spaces?					5		Comments	1.00	5.00
Very unsatisfactory - Outlet configuration does not							Each studio shows adequate power and data outlets	s, and wireless	access
support digital devices throughout school (1 per wall)							point.		
Unsatisfactory - Outlet configuration support digital									
devices only in certain areas of school (2 per wall)									
Average - Outlet configuration support digital devices									
but not enough capacity throughout school (3 per wall)									
4 Satisfactory - Outlet configuration support digital									
devices with adequate coverage and capacity									
throughout school (>3 per wall)									
5 Very Satisfactory - Excellent outlet configuration to									
support digital devices throughout school (>3 per wall)									
N/A Does not apply									

O2/11/2O22 ¹⁰

13 - Technolog	y (cont.)	1	2	3	4	5	N/	′A	
13.3 Are there of	adequate charging locations for devices?					5		Comments 1.00 5. 0	00
1	Very unsatisfactory - No centralized charging location							Appear to have multiple outlets per wall. Charging towers located in	
								certain spaces - maker space.	
2	Unsatisfactory - Centralized charging location, but								
•	inadequate in size for number of devices								
3	Average - Charging cart or tower but not adequately sized for number of devices								
4	Satisfactory - Charging cart or tower not centralized								
5	Very Satisfactory - Charging cart or tower located								
ŭ	centralized location. Excellent condition								
N/A	Does not apply								
13.4 Is there ad	equate AV for presentations spaces – cafeteria and gym?					5		Comments	
								1.00 5.0	00
ı	Very unsatisfactory - AV not present in one or more								
0	space								
2	Unsatisfactory - AV undersized for room, poor condition								
3	Average - Adequately sized / poor condition OR AV								
· ·	undersized / adequate condition								
4	Satisfactory - Good size, good condition								
5	Very Satisfactory - Generous sized, excellent condition								
N/A	Does not apply								
13.5 Is there did	gital media signage at the reception area?					5		Comments	
10:0 10 11:0:0 4:9						Ü		0.00 0.0	00
1	Very unsatisfactory - No digital media present in							Yes. Large display.	
•	reception area								
2	Unsatisfactory - Undersized, poor condition								
3	Average - Adequately sized / poor condition OR undersized / adequate condition								
4	Satisfactory - Media signage present, good sized, good								
4	condition								
5	Very Satisfactory - Generously sized, excellent condition								
N/A	Does not apply								

- Administr	ation Spaces	1	2	3	4	5	N/A	A	20.00	90%
4.1 Is there a r	reception area that functions as a security checkpoint for all							Comments	1.00	
1 2	Very unsatisfactory - No security checkpoint Unsatisfactory - Checkpoint is too small, poor condition		•		•	•	•		•	
3	Average - Needs updates or renovations to function well									
4	Satisfactory - Good size, good condition									
5 N/A	Very Satisfactory - Generous size, excellent condition									
	Does not apply						1			
4.2 Does the o	administration area feel welcoming?					5		Comments	1.00	5.0
1	Very unsatisfactory - No welcome space									
2	Unsatisfactory - Too small, poor lighting and									
•	transparency, limited informal seating, poor condition									
3	Average - Adequate size and layout, needs updates or renovations to feel welcoming									
4	Satisfactory - Good size and layout, good lighting and									
	transparency, informal seating provided									
5	Very Satisfactory - Generous size and layout, plenty of									
	light and transparency, informal seating provided,									
	excellent condition									
N/A	Does not apply		ı		1	1	1	T	Ī	
13	spaces that require it, does the administration area have acoustic privacy?			3				Comments	1.00	
1 adequate	Very unsatisfactory - No acoustic separations							Per construction document review, most partitions be	1.00	3.0
2	Unsatisfactory - Acoustic separations Unsatisfactory - Acoustic separations do not perform							to deck with insulation. Speech office has good soun		
3	Average - Some acoustic separations function okay, but							and office doors do not. Talking voice could be heard		
J	portions need updates or renovations							Principal confirmed that private discussions are chall	•	
4	Satisfactory - Good acoustic separations							can be heard in the hallway.	leriging becaus	e tries
5	Very Satisfactory - Excellent acoustic separations							can be neard in the natiway.		
N/A	Does not apply									
4.4 Are confer	ence rooms easily accessed for public / parent use?					5		Comments	1.00	5.0
1	Very unsatisfactory - Not accessible for public/parent			-		•		Community B108 is directly accessed within the entry	vestibule and	there
2	Unsatisfactory - Limited access, no transparency, poor							are two conference rooms within Admin. Location is	easy to use.	
	condition, difficult to find									
3	Average - Adequate accessibility, needs updates or									
4	renovations to function well Satisfactory - Good accessibility, good transparency,									
4	good size and condition									
5	Very Satisfactory - Excellent accessibility, excellent									
	transparency, generous size, excellent condition									
N/A	Does not apply									