

Educational Suitability Summary Report

Gullett Elementary School

Date: 01/11/2021 Score 51% Average

Gullett Elementary School serves an enrollment of approximately 525 students in north central Austin. It was built in 1957 and consists of approximately 41,000 square feet with an additional 13,000 square feet in portables. While this assessment does not cover the portables, it is assumed spaces in portables will be found deficient. Gullett Elementary is a neighborhood school and serves Early Childhood Special Education (3-year-olds) through fifth grade. The school has programs to teach students about animals, gardening, sustainability and philanthropy.

The main school building is approaching 65 years old. The original building (41,000 square feet) has an extensive list of deficiencies and is too small for its current enrollment. Each programmatic element that was measured in the education suitability does not meet the current Ed Spec requirements in terms of square footage, aside from the library that was constructed five years ago. Three grades (first, second and third) are fully located in portables.

Due to the open nature of the school, each studio has ample daylight and a great visual connection out to the gardens.

The gardens, mature trees, pond and outdoor learning areas are huge assets to the school. These spaces highlight the mission of teaching students about gardening, animals and sustainability. The site has old-growth live oak trees that are a stately presence on the campus and provide shade in many of the courtyard spaces.

Interview Overview

The interview was held in the library and attendees included Principal Brown, Assistant Principal Bromberg, teachers and the front office administrative assistant. Tenure at the school for the group ranged from one to 22 years. As mentioned above, the existing building and portables have many challenges, and the group created a thorough list of programs that are not in suitable spaces. In general, the teaching and learning spaces are not sized appropriately for the number of students. School programs cannot include the entire school since the cafetorium is so undersized. An entire grade cannot be on the stage at the same time for performances, and the stage is not accessible with a lift or a ramp. They have had to pick up students with mobility issues to get them on the stage.

The art room and music room are in existing studios, and the spaces are not appropriate for their functions. The school is part of the Fine Arts vertical team, and the current art room does not have the support spaces to create an optimal environment. The kiln is in a janitors'/electrical closet. The administration area has many shortcomings. The principal and assistant principal do not have individual offices. There is not a staff lounge, men's restroom, conference room or a nurse's office that

Perkins&Will

Educational Suitability Summary Report

Gullett Elementary School

can accommodate a cot. They need space for speech therapy, an office for a diagnostician and studio space for special education classes, CALT and speech. Proper special education space is a huge priority for the campus. Currently, four of the seven special education classes must share studio space (two classrooms in one studio space). A dedicated computer lab/STEAM lab is an important need for the campus as well, and they would like the technology for multimedia, including a green screen room.

The studio count does not allow the school to grow. They are making do with their studio numbers; however, since only certain studios have restrooms, there is very limited flexibility in moving entire grades around. The school has several after-school programs and all of those are housed out of studios. This conflict prevents some teachers from working in their studios after the school day ends.

The outdoor spaces around the school are a huge source of pride, and they feel they have creatively used these outdoor learning spaces to help offset some of the shortcomings in the building. The space for the campus animals is very important; however, the location can change. They have a 150-pound tortoise named Tina, guinea pigs (inside), and others. The campus has mature trees and there are garden beds dedicated to each teacher. The trees and gardens must never change due to community importance.

Future-thinking ideas for the campus include studios that facilitate small group and whole group interactions; flexible furniture; STEAM spaces; updated technology; multimedia space; and indoor courtyards that house a grade level for performances, presentations and collaborative learning.

Assessment Findings

The Educational Suitability Assessment of Gullett Elementary School earned a 51% overall score and places the campus in a category of Average. The assessment consists of seven General Building categories and seven Academic categories to determine areas that need more attention.

Very Unsatisfactory Categories (0-35%):

Exterior

Score is very unsatisfactory.

The student pickup and drop-off as well as special education bus pickup and drop-off all occur on the street. The exterior signage on the building is adequate, but wayfinding to front entry is difficult. Trash is separate, but all dumpsters are present.

Visual and Performing Arts

Score is very unsatisfactory.

Music/art rooms are too small and missing support spaces such as storage and dedicated kiln room. The stage performance space is severely deficient in meeting the Ed Spec standard.

Administration Spaces

Score is very unsatisfactory.

The administration area does not feel welcoming and is too small.

There is no conference room available for teacher/parent use. The nurse's office does not accommodate a cot.

Educational Suitability Summary Report

Gullett Elementary School

Unsatisfactory Categories (36-50%):

General Building

Score is unsatisfactory.

Exterior corridor width varies from 7-10 feet. The library and cafeteria can be secured after-hours. There is no community room available. General appearance is aged, but personalized touches convey pride for the students and community.

Security

Score is unsatisfactory.

Academics & Learning

Score is unsatisfactory.

All studios are undersized per Ed Spec. Collaboration takes place outdoors. Special education studios are in portables and do not have changing tables.

PE and Wellness

Score is unsatisfactory.

Gym is undersized and missing support spaces. There is no storage or PE instructor office.

Food Services

Score is unsatisfactory.

Cafeteria and kitchen are undersized, and finishes are very unsatisfactory.

Technology

Score is unsatisfactory.

There are not adequate outlets for charging devices. The A/V in the gym is on a mobile cart and the cafeteria A/V is old and does not work consistently.

Average Categories (51-65%):

Controllability of Systems

Score is average.

There are individually controlled thermostats in the studios. The 400 wing has older HVAC units that are frequently broken. Mobile units are brought in. Studios have blinds, but they are in poor condition.

Furniture, Fixtures, Equipment

Score is average.

Furniture is a mix of old and new. The library has a nice variety of new furniture, though cafeteria only has one type. The furniture size is appropriately sized for grade level.

Satisfactory Categories (66-80%):

Perkins&Will

Educational Suitability Summary Report

Gullett Elementary School

Outdoor Learning and Activity

Score is satisfactory.

There are numerous locations for outdoor studios. The active playgrounds are in good shape and have shade. The gardens are in excellent shape throughout the school grounds. There are many rain gardens and cisterns around the campus. Animal husbandry and a learning pond are also present.

Environmental Quality

Score is satisfactory.

All studios have excellent access to daylight and views. The acoustics are adequate since all studios have exterior corridors.

Media Resources

Score is satisfactory.

Library is adequately sized and has a mixture of seating types. The adjacent conference room is being used as half storage and half teaching space, possibly due to COVID-19 protocols.

Supporting Photographs



The school was built in the late-1950s and is nicely integrated with the surrounding old growth trees and the neighborhood.



Cafeteria and kitchen are very undersized. Kitchen is 850 square feet and requires exterior freezer/coolers. Stage within cafeteria is not accessible.

Supporting Photographs



Administration: Main office is located near the primary entry. It is missing many programmatic elements, such as a conference room, staff lounge, separate offices for principal / Asst. Principal, and nurse's office.



All studios are undersized. There is some casework storage, but storage is severely lacking throughout the school. Studios all have ample access to daylight with windows on both sides of the room,

Supporting Photographs



Art studio does not have any storage and is a regular studio turned into an art room. Kiln is in janitors' closet/electrical room, creating a safety concern.



Gym is undersized and there is no office or storage available. .

Supporting Photographs



Media Center is about five years old and is satisfactory. There are multiple types of seating. Media Center is accessed from exterior, and there is no key card access.



Main Hallway: There is a lot of natural light and great connection to the outdoors and the gardens. Storage is nonexistent throughout the school and many corridors have storage cabinets. Main corridor also does not have any climate control, no heating or cooling.

Supporting Photographs



Space between the wings provides garden space and informal seating.


Large trees are found throughout

the site.



Throughout the campus, the school has created these informal studio areas with little benches. Active playgrounds are in good shape and have shade.

Supporting Photographs



Gardens are a beloved feature of Gullett. Each teacher has their own garden bed.



Running track is uneven and creates trip-and-fall hazards.



Perkins&Will

Austin ISD Educational Suitability Assessment Criteria

General Building

School Name	Walk Attendees:	Date:
Gullett ES	Lynn Petermann and Emilie Ogburn	1.11.2021

1 - E	xterior		1	2	3	4	5	N/A	1	8.75	34%
1.1	Does the sit pedestrian	te permit desirable separation of vehicular, bus and traffic?	1						Comments	1.00	1.00
	1	Very unsatisfactory - Bus, car and pedestrian all happen at the same location							No dedicated bus or car loops; all drop-offs occur on	street.	
	2	Unsatisfactory - Cars and buses mix, pedestrians are separated									
	3	Average - Buses, cars, and pedestrians are separate but stack space is small									
	4	Satisfactory - Buses, cars, and pedestrians are separate but drop off does not have a canopy or a holding place									
	5	like a commons or cafeteria Very satisfactory - Buses, cars, and pedestrians are separate and drop off area has a canopy and destination									
	N/A	Does not apply									
1.2		ing easily identified with appropriate signage and wayfinding?		2					Comments	0.25	0.50
	1	Very unsatisfactory - Campus has no signage /							Exterior signage on building is visible, but wayfinding	is difficult due	to
		wayfinding							layout of building on site.		
	2	Unsatisfactory - Signage/wayfinding is faded/hidden									
	3	Average - Signage / wayfinding visible but not apparent									
	4	Satisfactory - Signage / wayfinding is visible but not good condition									
	5	Very satisfactory - Signage and wayfinding is visible and easy to use									
	N/A	Does not apply									

Perkins&Will 02/11/2022 ²

1 - E	xterior (co	nt.)	1	2	3	4	5	N/A	4		
1.3	Is the dump	oster accessible for trash / compost disposal?			3				Comments	0.50	1.50
	1 2 3 4 5	Very unsatisfactory - No compost present, route has obstacles (stairs, curbs, barriers) to dumpster Unsatisfactory - Compost is present. Route has obstacles to dumpster Average - Compost is present (<100' to cafeteria), Route to dumpster is free and clear but the two are not directly adjacent. Satisfactory - Compost and dumpster are directly adjacent and route is barrier free Very Satisfactory - Compost and dumpster are directly adjacent and route is barrier free. Dumpster are shaped / positioned so people of all heights can access it.							Ramp from loading dock but curb present; landfill separa	ite from oth	ners.
2 - 0	N/A Dutdoor Le	Does not apply arning and Activity	1	2	3	4	5	N/A		15.00	80%
2.1		r studios and support spaces appropriately configured per	•		3			14,7,	Comments	1.00	3.00
	3 4 5	Very unsatisfactory - No dedicated outdoor studios Unsatisfactory - Too small, poor condition, disconnected from learning spaces, no flexibility, no shade provided Average - Adequate size, adequate condition, needs some renovations or updates to function well, 50% or less shade coverage over studio area Satisfactory - Good size, good condition, connected to learning spaces, good flexibility, more than 50% shade coverage over studio area Very satisfactory - Generous size, excellent condition, connected to learning spaces, excellent flexibility, full shade coverage over studio area							Lots of outdoor classrooms scattered around the campus consistency in coverage or resources. Looks like they have the spaces to avoid being inside building.		y of
2.2	•	Does not apply blaygrounds (elementary only) and support spaces per the ed spec?				4			Comments	1.00	4.00
	1 2 3 4 5	Very unsatisfactory - No dedicated active playground Unsatisfactory - Too small, poor condition, no shade provided Average - Adequate size, adequate condition, needs some renovations or updates to function well, 50% or less shade coverage over play structure Satisfactory - Good size, good condition, more than 50% shade coverage over play structure Very satisfactory - Generous size, excellent condition, full shade coverage over play structure Does not apply		ı		1	ı		New play structure is covered; older structures have plent coverage from trees.		

2 - Outdo	oor Le	arning and Activity (cont)	1	2	3	4	5	N/A	4		
2.3 Are	garden	s and support spaces appropriately configured per the ed				4			Comments		
2.3 spec	c? (evalı	uation on infrastructure not condition of plants)				4			Comments	0.00	0.00
	1	Very unsatisfactory - No dedicated gardens							Monitoring answer, does not affect score for Outdoor	r Learning and	
	2	Unsatisfactory - Too small, poor condition, disconnected							Activity. Many gardens throughout campus are in cou	urtyards	
		from learning spaces, no flexibility, no accessible water									
	•	source									
	3	Average - Adequate size, adequate condition, needs some renovations or updates to function well, water									
		source is difficult to access									
	4	Satisfactory - Good size, good condition, connected to									
		learning spaces, good flexibility, water source is									
		accessible with 100 ft hose									
	5	Very Satisfactory - Generous size, excellent condition,									
		connected to learning spaces, excellent flexibility, water									
		source is less than 50ft from the garden or has irrigation									
	N/A	Does not apply									
2.4 Are	the rain	gardens and/or cisterns appropriately configured per the				4			Comments		
ed s	spec?					4			Comments	0.00	0.00
	1	Very unsatisfactory - No rain gardens or cisterns			•	•	•		Monitoring answer, does not affect score for Outdoor	r Learning and	
	2	Unsatisfactory - Too small, poor condition, not							Activity. Dozens of gardens and many rainwater colle	ection barrels o	around
		functioning, disconnected							campus.		
	3	Average - Adequate size, adequate condition, is									
		connected, needs some renovations or updates to									
	4	function well Satisfactory - Good size, good condition, functions									
	7	properly									
	5	Very Satisfactory - Generous size, excellent condition,									
		exceptional functionality, connected to learning spaces,									
		educational signage provided									
	N/A	Does not apply									
2.5 Doe	s the scl	nool have animal husbandry? (optional)					5		Comments	0.00	0.00
	1	No									
0 (D	5	Yes	-	ı			1	1		0.00	0.00
2.6 Doe		nool have nature loop trails? (optional)						<u> </u>	Comments	0.00	0.00
	1 5	No Yes									
2.7 Doe		nool have a learning pond? (optional)					5	l	Comments	0.00	0.00
2.7 500	1	No					J	l	Comments	0.00	0.00
	5	Yes									
2.8 Doe		nool have a grass play field and walking trail?					5		Comments	1.00	5.00
	1	No							1		
	5	Voo									

3 - General Building	1	2	3	4	5	N/A		11.25	49%
3.1 Are interior circulation routes wide enough to safely and effectively accommodate student movement?			3				Comments	0.50	1.50
1 Very unsatisfactory - Primary circulation is 5'-0" to 6'-0"							Sizes vary from 7 to 10 ft; lots of exterior corridors.		
wide									
2 Unsatisfactory - Primary circulation is 6'-0" to 7'-0" wide									
3 Average - Primary circulation is 7'-0" to 8'-0" wide									
4 Satisfactory - Primary circulation is 8'-0"-10'-0" wide									
5 Very satisfactory - Primary circulation is 10'-0"+ wide									
N/A Does not apply									
Are community use areas arranged so that the school can allow night			3				Comments		
functions without full school access?								0.75	2.25
1 Very unsatisfactory - Cafeteria, gym, and library cannot							Library and cafeteria could be secured with limited a	ccess to the sch	nool.
be accessed after hours 2 Unsatisfactory - Only one of the public spaces (Cafeteria,									
Gym and Library) can be accessed from parking and									
secured after hours									
3 Average - Only two of the public spaces can be accessed									
from parking and secured after hours									
4 Satisfactory - All of the public spaces can be accessed									
from parking and secured from the rest of the building									
but not individually									
5 Very satisfactory - Cafeteria, gym, and library can be accessed from parking and locked off from rest of									
campus for night/evening use with their own entrance									
N/A Does not apply									
Is there a community room that is a dedicated meeting space outside									
3.3 of school function?	ı						Comments	0.75	0.75
Very unsatisfactory - No dedicated community room									
Unsatisfactory - Community room but within school									
function, no access after school hours									
3 Average - Community room, moderate size, but need some renovations or updates to function well									
4 Satisfactory - Community room, good size /layout, meets									
needs / functions well									
5 Very Satisfactory - Community room, generous size, nice									
condition, functions appropriately outside of school									
function									
N/A Does not apply		ı	ı				T		
3.4 Does the general appearance of the school convey pride for the students and community?				4			Comments	0.25	1.00
Very unsatisfactory - General appearance is poor							Despite aged condition. there are many personalized		
2 Unsatisfactory - General appearance is aged but ok							in throughout the school.	r touches and c	are put
3 Average - General appearance is good							an an oughout the school.		
4 Satisfactory - General appearance shows pride in									
campus and student works									
5 Very Unsatisfactory - General appearance shows pride in									
campus and student works and is welcoming to the									
community N/A Does not apply									
N/A Does not apply									

4 - Security	2 3	4	5	N/A		16.25
4.1 Does the facility have key card access at all major entries?					Comments	0.25
1 Very unsatisfactory - No entries 2 Unsatisfactory - 1/4 of major entries 3 Average - 1/2 of major entries 4 Satisfactory - 3/4 of major entries 5 Very satisfactory - All of major entries						
N/A Does not apply	1 1	ı				T
4.2 How adequate is site lighting and security for the campus overall?					Comments	1.00
Very unsatisfactory - No exterior lighting, no secure perimeter						
Unsatisfactory - Lighting is limited to front entry only, parking lot lighting poor, security is minimal						
3 Average - Lighting at all night-use entries and parking lot, but poor condition. Security is moderate						
4 Satisfactory - Lighting at all night-use entries and parking lots, good condition, signage less visible, perimeter is well secured but needs updates						
Very satisfactory - Signage, parking lots, and entries are well lit, visible and easy to use, perimeter is very secure						
N/A Does not apply						
Is the main office located at the school entry and configured with a					Comments	
secure vestibule to the main corridor?					-	1.00
 Very unsatisfactory - No secure vestibule, office located far from main entry, allows visitors access to school unsupervised Unsatisfactory - No secure vestibule, office located 						,
somewhat far from main entry, minimal supervision of visitors						
3 Average - Office close to entry, views of front door, but no secure vestibule						
4 Satisfactory - Office is well-located with a secure						
vestibule, but needs updates						
5 Very satisfactory - Office well-located with secure vestibule and all appropriate security features						
N/A Does not apply						
Is there enough interior transparency for faculty to passively supervise						
learners and their activities who are not in studios?		4			Comments	1.00 4.00
1 Very unsatisfactory - No transparency of walls					All studios have two full walls of glazing with views ir	•
Unsatisfactory - Limited transparency in certain locations					corridors; however, this also poses a security issue as	there is no way to
3 Average - Good transparency in certain locations but					effectively lock down the campus.	
inadequate or missing in other locations of school Satisfactory - Adequate transparency throughout the						
school Very satisfactory - Excellent transparency throughout the						
school N/A Does not apply						

Perkins&Will 02/11/2022 ⁶

5 - Environmer	ntal Quality	1	2	3	4	5	N/A		25.00	80%
5.1 How are ac	coustics in studios in general?					5		Comments	1.00	5.00
1 2 3 4 5 N/A	Very unsatisfactory - Recognized word/sound from adjacent studio/corridor Unsatisfactory - Audible sound from adjacent studio/corridor Average - Slight sound from outside room Satisfactory - Walls to deck insulated only white noise from mechanical system Very satisfactory - Able to hear quiet speaking from across the room Does not apply							Most corridors lead to the exterior, so sound seal is a	dequate.	
5.2 Is the studio	o artificial lighting adequate quality?			3				Comments	1.00	3.00
1 2 3 4 5 N/A	Very unsatisfactory - Sporadic lights work, glare, less than 20 FC Unsatisfactory - 10-19 FC or serious glare Average- 20-29 FC minor glare Satisfactory - 30-39 FC and no glare Very satisfactory - 40+ FC and no glare Does not apply									
5.3 Is there acc	ess to natural light in studios?					5		Comments	1.00	5.00
1 2 3 4 5 N/A	Very unsatisfactory - No learning spaces have natural light Unsatisfactory - 1-25% of learning spaces have natural light or windows are too small to let in light Average - 26-50% of learning spaces have natural light Satisfactory - 51-75% of learning spaces have natural light Very satisfactory - 76-100% of learning spaces have natural light Does not apply									
5.4 Is there acc	ess to outside views from learning spaces?					5		Comments	1.00	5.00
1 2 3 4 5	Very unsatisfactory - No learning spaces have views Unsatisfactory - 1-25% of learning spaces have views or windows are too small to see out Average - 26-50% of learning spaces have views Satisfactory - 51-75% of learning spaces have views Very satisfactory - 76-100% of learning spaces have views							All studios in the original building have views to natulight.	re and ample r	natural

5 - Environme	ntal Quality (cont.)	1	2	3	4	5	N/A	N.		
5.5 Does the b	ouilding have odor or pest problems?		2					Comments	1.00	2.00
1	Very unsatisfactory - Evidence of both pests and odors	•				•	•	Agave plant in courtyard has wasp nests and creates	potential safet	y
2	Unsatisfactory - Evidence of pests or odors							issues. Rodents live under stage area and regularly c	hew through A/	V
3	Average - Limited evidence of pests, no odors							cords.	· ·	
4	Satisfactory - No evidence of pests / odors, school									
	cleanliness in good condition									
5	Very Satisfactory - No evidence, school cleanliness in									
	excellent condition									
N/A	Does not apply									
6 - Controllab	ility of Systems	1	2	3	4	5	N/A	\	12.50	60%
6.1 Does the s	tudio thermostat allow for individual control?					5		Comments	0.50	2.50
1	No									
5	Yes									
6.2 Are shades	s provided to control natural light in learning spaces?			3				Comments	1.00	3.00
1	Very unsatisfactory - No, windows are covered with							Blinds are bent or broken in some spaces and in good	d condition in of	thers.
	boards/paper									
2	Unsatisfactory - No, windows have no light control									
3	Average - Yes, but poor condition blinds									
4	Satisfactory - Yes, blinds									
5	Very satisfactory - Blackout shades									
N/A	Does not apply			,				<u></u>		
6.3 What is the	e quality of lighting controls in the studios?		2					Comments	1.00	2.00
1	Very unsatisfactory - Single switch only per room									
2	Unsatisfactory - Alternating rows switch off									
3	Average - Alternating lamps in single fixtures switch off									
4	Satisfactory - Tri level switching									
5	Very satisfactory - Dimmable									
N/A	Does not apply							'		

7 - Furnitu	re, Fixtures & Equipment	1	2	3	4	5	N/A		18.75	64%
7.1 What	is the current condition of the furniture?				4			Comments	0.75	3.00
3 2 5	Very unsatisfactory - Damaged or broken, non- functioning Unsatisfactory - Torn/ bent/ wrong size Average - Scratched/dented/marked Satisfactory - Not new, but sturdy and clean Very satisfactory - New Does not apply							Mix of old and newer furniture throughout		
1 1 ')	variety of furniture types being accommodated throughout the I - learning commons, dining commons, other multi-use spaces?		2					Comments	1.00	2.00
1	Very Unsatisfactory - Same furniture used in all spaces							Variety provided in library; cafeteria has only one type	e.	
2	Unsatisfactory - Furniture variety in one multi-use space									
4	Average - Furniture variety in more than one multi-use space Satisfactory - All multi-use spaces have greater than one type of furniture Very satisfactory - All multi-use spaces have greater than two types of furniture A Does not apply									
7.3 How v	vell does furniture accommodate rapid reconfiguration of a ?			3				Comments	1.00	3.00
2	Very Unsatisfactory - Furniture is fixed or very heavy Unsatisfactory - Furniture does not allow desks to be configured as individuals, small groups, or large groups Average - Mix of furniture that can reconfigure but is cumbersome to move Satisfactory - Furniture is flexible for multiple configurations of space Very satisfactory - Furniture is flexible for multiple configurations of space, easy to move and stack Does not apply							Larger tables are more cumbersome in studios but deflexible.	sks and chairs	are
7.4 Is the	furniture ergonomic and size appropriate for grade level?				4			Comments	1.00	4.00
3	Very unsatisfactory - Desk with attached chair combinations too small for grade level Unsatisfactory - Desk with attached chair combinations Average - Mix of studios with tables/loose chairs and desks with fixed seats Very satisfactory - Tables with loose chairs that allow students to be active									
IN)	A Does not apply									

Perkins&Will 02/11/2022 ⁹

		1	2	3	4	5	N/A	5.00	2
	and corridors have blue recycle bins with bilingual and/or image sorting instructions?	1						Comments 0.50	(
1 2 3 4 5	Very unsatisfactory - There are no recycling and landfill bins and signage are sparse or infrequent, OR there are only landfill bins with no recycling bins. Unsatisfactory - Bins and signage are sparse or infrequent and/or lack clear signage. Average - 50% of corridors and studios have both a landfill bin and a recycle bin in an accessible location. The containers have clear signage. Satisfactory - 75% of studios and corridors have a visible landfill and recycle collection containers in an accessible location. The containers have clear signage. Very satisfactory - All studios / corridors (100%) have visible landfill and recycle collection containers in accessible locations. The containers have clear signage, and the style and format is consistent and uniform across campus.							A score for this category is being recorded, but this category is not calculated in the overall ESA average.	
of each: gre	Does not apply feteria (or wherever meals are served) have at least one ten compost bin, blue recycle bin, and landfill bin? Are the d clearly with bilingual and/or image sorting?	1						Comments 0.50	
1 2	Very unsatisfactory- There may be landfill bins, but there are no compost and/or recycle bins. There is not clear sorting signage. Unsatisfactory- Recycle, landfill, and compost bins are present, but the bins are scattered and no co-located							A score for this category is being recorded, but this category is not calculated in the overall ESA average.	



Perkins&Will

Austin ISD Educational Suitability Assessment Criteria

Academics - Elementary School

School Name	Walk Attendees:	Date:
Gullett ES	Lynn Petermann and Emilie Ogburn	1.11.2021

8 - A	cademics 8	& Learning	1	2	3	4	5	N//	A	70.00	36%
8.1	Are studios	appropriately configured per the ed spec?		2					Comments	1.00	2.00
	1	Very unsatisfactory - Too small, no flexibility, disconnected							Connected via excellent outdoor spaces, but studios of scattered.	are undersized	and
	2	Unsatisfactory - Too small, only one area for all teaching methods, limited flexibility, disconnected									
	3	Neutral - Adequate size, multiple areas for different teaching methods, adequate flexibility, limited transparency and connection to other studios and shared learning spaces, needs updates or renovations to function well.									
	4	Satisfactory - Good size, multiple areas for different teaching methods, good flexibility, good transparency and connection to other studios and shared learning spaces									
	5	Very Satisfactory - Generous size, multiple areas for different teaching methods, excellent flexibility, generous display area and visual teaching tools, excellent transparency and connection with other studios and shared learning spaces									
	N/A	Does not apply									
8.2		nd Kinder have appropriate support spaces such as and storage per the ed spec?		2					Comments	1.00	2.00
	1	Very unsatisfactory - None provided							Kindergarten studios are undersized by 100 sq. ft.		
	2	Unsatisfactory - Too small, disconnected, poor condition									
	3 4	Neutral - Adequate size, average condition, needs updates or renovations to function well Satisfactory - Good size, connected, good condition									
	5	Very Satisfactory - Generous size, connected, excellent condition									
	N/A	Does not apply									

8 - 8	cademics 8	& Learning (cont.)	1	2	3	4	5	N/A	4		
8.3		nave appropriate support spaces such as storage per the		2					Comments		
0.5	ed spec?								Comments	1.00	2.00
	1	Very unsatisfactory - None provided							No PLC for teacher storage, but built-in cabinets are	present in each	า
	2	Unsatisfactory - Too small, disconnected, poor condition							studio.		
	3	Neutral - Adequate size, average condition, needs									
		updates or renovations to function well									
	4	Satisfactory - Good size, connected, good condition									
	5	Very Satisfactory - Generous size, connected, excellent									
		condition									
	N/A	Does not apply									
8.4		earning neighborhoods have small group rooms and open		2					Comments		
0.4	collaboration	•		_					Comments	1.00	2.00
	1	Very unsatisfactory - No breakout rooms or open							Exterior courtyards can be used for collaboration in g	jood weather, l	but no
		collaboration spaces are provided							dedicated interior spaces are present.		
	2	Unsatisfactory - Too small or too few, poor condition, no									
		flexibility, lacks visual connection to learning									
	0	neighborhood, poor acoustic privacy									
	3	Average - Adequate size, adequate condition, needs some renovations or updates to function well									
	4	Satisfactory - Good size, good condition and flexibility,									
	4	transparency and connection to learning neighborhood,									
		acoustic privacy									
	5	Very Satisfactory - Generous size, excellent condition and									
		flexibility, transparency and connection to learning									
		neighborhood, acoustic privacy									
	N/A	Does not apply									
8.5	•	studios large enough to support project-based learning		2					Comments		
0.5	and multipl	e teaching modalities?							Comments	1.00	2.00
	1	Very unsatisfactory - Too small, no flexibility, does not							Studios are small and lack adequate storage, and te	aching flexibilit	ty is
		support project-based learning							limited due to two full walls of windows in studios.		
	2	Unsatisfactory - Undersized, decentralized resources,									
		limited flexibility									
	3	Average - Adequate size, needs some renovations or									
	4	updates to function well Satisfactory - Good size, centralized resources, good									
	flexibility										
	5 Very Satisfactory - Generous size, centralized project										
	· ·	resources, excellent flexibility									
	N/A	Does not apply									

Perkins&Will 02/11/2022 ³

8 - A	cademics (& Learning (cont.)	1	2	3	4	5	N/A	4		
8.6	Are Maker	Spaces and support spaces appropriately configured per		2					Comments		•
0.0	the ed spec	?							Comments	1.00	2.00
	1	Very unsatisfactory - No dedicated maker spaces							More of a computer lab but lacks open space for flex	ibility and acti	vities.
	2	Unsatisfactory - Too small, poor condition, disconnected									
		from learning spaces, no flexibility									
	3	Average - Adequate size, adequate condition, needs									
		some renovations or updates to function well									
	4	Satisfactory - Good size, good condition, connected to									
	_	learning spaces									
	5	Very Satisfactory - Generous size, excellent condition,									
	N1/A	connected to learning spaces									
	N/A	Does not apply		1		1	ı	1			
8.7	Is there a Pr	rofessional Learning Center in the learning neighborhood?	1						Comments	1.00	1.00
	1	Very unsatisfactory - No dedicated space for									
		Professional Learning Center									
	2	Unsatisfactory - Too small, poor condition, disconnected									
	3	Average - Adequate size, adequate condition, needs									
		some renovations or updates to function well									
	4	Satisfactory - Good size, good condition, connected									
	5	Very Satisfactory - Generous size, excellent condition,									
		connected									
	N/A	Does not apply							1		
8.8	Is there a de	edicated science room and support space?	1						Comments		
										0.00	0.00
	1	No							Monitoring answer, but doesn't affect overall score.		
	5	Yes									
8.9		dequate places to display the evidence and artifacts of		2					Comments		
0.7	learning (bo	oth 2D and 3D)?							Comments	1.00	2.00
	1	Very unsatisfactory - No dedicated space							No 3D display; limited 2D display due to exterior corr	idors.	
	2	Unsatisfactory - Too small, non-dedicated, poor									
		condition									
	3	Average - Adequate size, adequate condition, needs									
		updates or renovations to function well									
	4	Satisfactory - Good size, good condition									
	5	Very Satisfactory - Generous size, excellent condition									
	NI/A	Does not apply									

Perkins&Will 02/11/2022 ⁴

8 - A	cademics	& Learning (cont.)	1	2	3	4	5	N/A	1		
0.10	Does the bu	uilding provide adequate opportunities for		2					Comments		
8.10	students/te	achers to collaborate in varying group sizes?		2					Comments	1.00	2.00
	1	Very unsatisfactory - No space to support collaboration							Courtyards are available for this function but other th	nan the library,	
		in various sizes.							cafeteria or gym, there are no additional spaces for a	collaboration.	
	2	Unsatisfactory - Too small, inflexible, only one option,									
		does not support a variety of group sizes									
	3	Average - Adequate space for collaboration, needs									
		updates or renovations to function well.									
	4	Satisfactory - Good size, good condition, multiple options									
		to support a variety of group sizes									
	5	Very Satisfactory - Generous size, excellent condition,									
		multiple options to support a variety of group sizes									
	N/A	Does not apply		,		,	,		,		
8.11	Does the bu	uilding provide opportunities for informal interaction?		2					Comments	1.00	
	1	Vancousantisfastano Na sanas				<u> </u>			Estados a substituto de la constitución de la const	1.00	2.00
	0	Very unsatisfactory - No space							Exterior courtyards have the space and furniture to s	upport this, but	
	2	Unsatisfactory - Too small, poor condition, layout and							interior spaces do not.		
	3	furnishings do not support informal interaction well Average - Adequate size and condition, needs updates									
	3	or renovations to function well.									
	4	Satisfactory - Good size, good condition, layout and									
	-	furnishings support informal interactions									
	5	Very Satisfactory - Generous size, excellent condition,									
	Ŭ	layout and furnishings support informal interactions									
	N/A	Does not apply									
	Does the le	arning neighborhood / building provide adequate									
8.12		es for students to work independently?		2					Comments	1.00	2.00
	1	Very unsatisfactory - No breakout rooms/small study				1	<u> </u>		Courtyards can be used as breakout spaces but there		
	•	spaces							or dedicated interior space.	o is no acoustic	privacy
	2	Unsatisfactory - Too small, poor condition, no acoustic							or dedicated interior space.		
		privacy, only one space for independent work,									
		disconnected from learning neighborhood									
	3	Average - Adequate size and condition, needs updates									
		or renovations to function well.									
	4	Satisfactory - Good size and condition, acoustic privacy,									
		variety of independent work space options, connected to									
		learning neighborhood									
	5	Very Satisfactory - Generous size, excellent condition,									
		acoustic privacy, variety of independent work space									
	options, connected to learning neighborhood										
	N/A	Does not apply									

O2/11/2022 ⁵

8 - A	cademics 8	& Learning (cont.)										
8.13	Are Special spec?	Education spaces appropriately configured per the ed		2			Comments	1.00	2.00			
	1	Very unsatisfactory - Too small, no flexibility, disconnected					Located in standard studios and in portables; not enough space for all classes for multiple teachers share the same rooms, limiting instruction					
	2	Unsatisfactory - Too small, only one area for all teaching methods, limited flexibility, disconnected					area.					
	3	Neutral - Adequate size, multiple areas for different teaching methods, adequate flexibility, limited transparency and connection to other studios and shared learning spaces, needs updates or renovations to					Principal's note: Two special education studios are in have changing tables. Four other special education c two studios.					
		function well.										
	4	Satisfactory - Good size, multiple areas for different teaching methods, good flexibility, good transparency and connection to other studios and shared learning spaces										
	5	Very Satisfactory - Generous size, multiple areas for different teaching methods, excellent flexibility, generous										
		display area and visual teaching tools, excellent										
		transparency and connection with other studios and shared learning spaces										
	N/A	Does not apply										
8.14	•	Education support spaces, such as storage, space for er, appropriately configured per the ed spec?	1				Comments	1.00	1.00			
	1	Very unsatisfactory - None provided					No direct access to restrooms; no other resources pre	sent; some loca	ated in			
	2	Unsatisfactory - Too small, disconnected, poor condition					portables.					
	3	Neutral - Adequate size, average condition, needs										
		updates or renovations to function well										
	4	Satisfactory - Good size, connected, good condition										
	5	Very Satisfactory - Generous size, connected, excellent condition										
	N/A	Does not apply										
8.15		ble restrooms and changing rooms readily available to the location spaces?	1				Comments	1.00	1.00			
1 No												
	5	Yes										

Perkins&Will 02/11/2022 ⁶

9.1 Are music spaces and the cafeteria stage appropriately configured per the ed spec?	Comments 1.00 2.00
1 Very unsatisfactory - Too small, missing program spaces No dedicate	d storage in music room; stage is not ADA accessible. The two
2 Unsatisfactory - Too small, poor condition spaces are r	nostly adjacent for ease of access. Rodents live under stage
3 Neutral - Adequate size, adequate condition, needs area and re	gularly chew through A/V cords.
updates or renovations to function well.	, ,
4 Satisfactory - Good size, good condition	
5 Very Satisfactory - Generous size, excellent condition	
N/A Does not apply	
Are music and performance storage spaces appropriately configured 9.2	Comments
per the ed spec?	1.00 2.00
1 Very unsatisfactory - None provided	
2 Unsatisfactory - Too small, disconnected, poor condition	
3 Neutral - Adequate size, average condition, needs	
updates or renovations to function well	
4 Satisfactory - Good size, connected, good condition	
5 Very Satisfactory - Generous size, connected, excellent	
condition	
N/A Does not apply	_
9.3 Are Visual Arts spaces and storage appropriately configured per the	Comments
ed spec?	1.00 1.00
1 Very unsatisfactory - Too small, missing program spaces No storage	oom; kiln is in janitors' closet/electrical room.
2 Unsatisfactory - Too small, poor condition	
3 Average - Adequate size, adequate condition, needs	
some renovations or updates to function well	
4 Satisfactory - Good size, good condition	
5 Very Satisfactory - Generous size, excellent condition	
N/A Does not apply	

Perkins&Will 02/11/2022 ⁷

10	O - PE and \	Vellness	1	2	3	4	5	N/A	1	10.00	40%
Ι,	0.1 Does the	campus meet the ed spec standard for physical education		2					Comments		
1	O.1 program	spaces?							Comments	1.00	2.00
	1	Very unsatisfactory - Too small, missing program spaces							Undersized by about 600 sq. ft.; small storage discon	nected from ir	nterior.
	2	Unsatisfactory - Too small, poor condition									
	3	Average - Adequate size, adequate condition, needs									
		some renovations or updates to function well									
	4	Satisfactory - Good size, good condition									
	5	Very Satisfactory - Generous size, excellent condition									
	N/A	Does not apply									
١,	0.2 Are the p	physical education storage spaces appropriately configured		2					Comments		
'	per the e	ed spec?							Comments	1.00	2.00
	1	Very unsatisfactory - None provided									
	2	Unsatisfactory - Too small, disconnected, poor condition									
	3	Neutral - Adequate size, average condition, needs									
		updates or renovations to function well									
	4	Satisfactory - Good size, connected, good condition									
	5	Very Satisfactory - Generous size, connected, excellent									
	_	condition									
	N/A	Does not apply									
11	- Food Ser	vices	1	2	3	4	5	N/A	1	10.00	40%
	11.1 Is the Dir	ning Commons appropriately configured per the ed spec?		2					Comments	1.00	2.00
	1	Very unsatisfactory - Too small, missing program spaces							For school's current enrollment (525), cafeteria should	be approx. 3	000 SF
	2	Unsatisfactory - Too small, poor condition, only one							(1/3 population * 17 NSF). Current cafeteria is 2,150 SF		
		option for eating space provided, inadequate circulation									
	3	Average - Adequate size and condition, needs updates									
		or renovations to function well									
	4	Satisfactory - Good size and condition, good circulation,									
		multiple options for eating space (ex: connection to									
	5	outdoor eating space) Very Satisfactory - Generous size, excellent condition and									
	3	circulation, multiple options for eating space (ex:									
		connection to outdoor eating space)									
	N/A	Does not apply									
H.	Are the f	Food Services support spaces appropriately configured per									
	1.2 the ed sp	pec?		2					Comments	1.00	2.00
	1	Very unsatisfactory - None provided							Very undersized kitchen, one small serving line. Freez	er / cooler are	
	2	Unsatisfactory - Too small, disconnected, poor condition							accessed from outside off of the main corridor.		
	3	Neutral - Adequate size, average condition, needs									
		updates or renovations to function well									
	4	Satisfactory - Good size, connected, good condition									
	5	Very Satisfactory - Generous size, connected, excellent									
		condition									
	N/A	Does not apply									

12 - Media Resources	1	2	3	4	5	N/A		30.00	73%
Is the Library/Media Center easily accessible for the occupants and				4			Comments		
visitors to the school?		L	L	4	L		Comments	1.00	4.00
Very unsatisfactory - Not accessible							Good access to exterior/public with location along the	e front of the s	cool.
2 Unsatisfactory - Limited access, difficult to find, no							There is one restroom available.		
transparency									
3 Average - Adequate accessibility, needs updates or							Principal's note: There is no key card access to the library	ary, so student	ts
renovations to function well							cannot readily access it during the school day.		
4 Satisfactory - Accessible, easy to find, good									
transparency, good condition 5 Very Satisfactory - Accessible, easy to find, excellent									
5 Very Satisfactory - Accessible, easy to find, excellent transparency, excellent condition									
N/A Does not apply									
***				T					
12.2 How well does the Library/Media Center support quiet study?			3				Comments	1.00	3.00
Very unsatisfactory - No quiet study spaces				1		1	Small nooks for quiet study		5.50
2 Unsatisfactory - One area in poor condition, poor							and the quiet study		
acoustic privacy									
3 Average - One or more areas provided, needing updates									
or renovations to function well									
4 Satisfactory - Clusters or small rooms adjacent to media									
center, good condition, good acoustic privacy									
5 Very Satisfactory - Multiple clusters or small rooms									
adjacent to media center, excellent condition, excellent									
acoustic privacy									
N/A Does not apply				ı	ı		Т		
12.3 How well does the Library/Media Center support social interaction?					5		Comments	1.00	5.00
1 Very unsatisfactory - No space				1	<u> </u>	1		1.00	0.00
2 Unsatisfactory - Too small, poor condition, layout and									
furnishings do not support informal interaction well									
3 Average - Adequate size and condition, needs updates									
or renovations to function well.									
4 Satisfactory - Good size, good condition, layout and									
furnishings support informal interactions									
5 Very Satisfactory - Generous size, excellent condition,									
layout and furnishings support informal interactions									
N/A Does not apply						1	T		
How well does the Library/Media Center support collaborative work in small groups (4-8 students)?				4			Comments	1.00	4.00
1 Very unsatisfactory - No breakout rooms, no flexible					<u> </u>	1	Concil available of informal formations there is the	1.00	4.00
furniture, no support							Small grouping of informal furniture throughout		
2 Unsatisfactory - Too small, one area, poor condition									
Average - Adequate size, multiple areas provided,									
needing updates or renovations to function well									
4 Satisfactory - Clusters or small rooms adjacent to media									
center, flexible furniture, good condition									
5 Very Satisfactory - Multiple clusters or small rooms									
adjacent to media center, flexible furniture, excellent									
condition									
N/A Does not apply									

ı	12 - Media Res	Media Resources - Continued			3	4	5	N/A	A		
	12.5 How well d	oes the Library/Media Center support collaborative work				Δ			Comments		
	in larger gr	oups (10-25)?				-			Comments	1.00	4.00
	1	Very unsatisfactory - No gathering areas							Good-sized presentation area with new furniture		
	2	Unsatisfactory - Too small, one common space, limited									
		seating, poor condition									
	3	Average - Adequate size, one common space, needs									
		updates or renovations to function well									
	4	Satisfactory - Good size, multiple common spaces with									
	_	seating, good condition									
	5	Very Satisfactory - Generous size, multiple commons									
		spaces with seating, excellent condition									
	N/A	Does not apply								T	
	12.6 How well d	oes the Library/Media Center support technology?		2					Comments	1.00	2.00
	1	Very unsatisfactory - No vis comm tools		1					No projection or whiteboards, Mobile display is avail	able.	
	2	Unsatisfactory - Outdated, poorly functioning, or									
		insufficient									
	3	Good - Mix of old and new whiteboards/projectors/etc.									
	4	Satisfactory - Projectors, marker boards, smart boards in									
		most spaces - good condition									
	5	Very Satisfactory - Projectors, marker boards, smart									
		boards in most spaces - new condition									
	N/A	Does not apply									
1	13 - Technolog	у	1	2	3	4	5	N/A	4	20.00	45%
	13.1 How well e	quipped are the facilities with instructional technology?		2					Comments	1.00	2.00
	1	Very unsatisfactory - Limited to no technology present in									
		instructional spaces									
	2	Unsatisfactory - One type of technology present									
	3	Average - Multiple types of technology, smart boards,									
		poor condition, limited to only certain areas of school									
	4	Satisfactory - Multiple types of technology, smart									
		boards, good condition.									
	5	Very Satisfactory - Multiple types of technology, smart									
		boards, excellent condition									
	N/A	Does not apply		,		,					
	13.2	adequate number of power and data outlets in learning		2					Comments		
	spaces?			_					Comments	1.00	2.00
	1	Very unsatisfactory - Outlet configuration does not									
		support digital devices throughout school (1 per wall)									
	2	Unsatisfactory - Outlet configuration support digital									
	•	devices only in certain areas of school (2 per wall)									
	3	Average - Outlet configuration support digital devices									
		but not enough capacity throughout school (3 per wall)									
	4	Satisfactory - Outlet configuration support digital									
		devices with adequate coverage and capacity									
	F	throughout school (>3 per wall)									
	5	Very Satisfactory - Excellent outlet configuration to									
	N/A	support digital devices throughout school (>3 per wall) Does not apply									
	IV/A	DOES HOL ODDIV									

02/11/2022 ¹⁰

13 - Technolog	gy (cont.)	1	2	3	4	5	N/	A		
13.3 Are there of	adequate charging locations for devices?		2					Comments	1.00	2.0
1	Very unsatisfactory - No centralized charging location							Located in some spaces but not all.		
2	Unsatisfactory - Centralized charging location, but									
	inadequate in size for number of devices									
3	Average - Charging cart or tower but not adequately									
4	sized for number of devices									
4 5	Satisfactory - Charging cart or tower not centralized Very Satisfactory - Charging cart or tower located									
5	centralized location. Excellent condition									
N/A	Does not apply									
	• • • • • • • • • • • • • • • • • • • •					1	I	T		
13.4 Is there ad	lequate AV for presentations spaces – cafeteria and gym?			3	1			Comments	1.00	3.00
1	Very unsatisfactory - AV not present in one or more	1		<u> </u>		1		Cafeteria has projector and screen; gym has audio on		
	space							, , , , , , , , , , , , , , , , , , , ,	,	
2	Unsatisfactory - AV undersized for room, poor condition									
3	Average - Adequately sized / poor condition OR AV									
	undersized / adequate condition									
4	Satisfactory - Good size, good condition									
5	Very Satisfactory - Generous sized, excellent condition									
N/A	Does not apply									
13.5 Is there dig	gital media signage at the reception area?			3	;			Comments	0.00	0.00
1	Very unsatisfactory - No digital media present in									
	reception area									
2	Unsatisfactory - Undersized, poor condition									
3	Average - Adequately sized / poor condition OR									
	undersized / adequate condition									
4	Satisfactory - Media signage present, good sized, good condition									
5	Very Satisfactory - Generously sized, excellent condition									
N/A	Does not apply									

14 - Administro	ation Spaces	1	2	3	4	5	N/A		20.00	30%
ls there a revisitors?	eception area that functions as a security checkpoint for all							Comments	1.00	
1	Very unsatisfactory - No security checkpoint	-			•		•			
2	Unsatisfactory - Checkpoint is too small, poor condition									
3	Average - Needs updates or renovations to function well									
4	Satisfactory - Good size, good condition									
5	Very Satisfactory - Generous size, excellent condition									
N/A	Does not apply									
14.2 Does the ac	dministration area feel welcoming?	1						Comments	1.00	1.00
1	Very unsatisfactory - No welcome space							Reception area is small and dated		
2	Unsatisfactory - Too small, poor lighting and									
	transparency, limited informal seating, poor condition									
3	Average - Adequate size and layout, needs updates or									
	renovations to feel welcoming									
4	Satisfactory - Good size and layout, good lighting and									
5	transparency, informal seating provided Very Satisfactory - Generous size and layout, plenty of									
3	light and transparency, informal seating provided,									
	excellent condition									
N/A	Does not apply									
For those sp	paces that require it, does the administration area have									
14.3 adequate of	acoustic privacy?			3				Comments	1.00	3.00
1	Very unsatisfactory - No acoustic separations				-					
2	Unsatisfactory - Acoustic separations do not perform									
	well									
3	Average - Some acoustic separations function okay, but									
	portions need updates or renovations									
4	Satisfactory - Good acoustic separations									
5	Very Satisfactory - Excellent acoustic separations									
N/A	Does not apply				1	1		T		
14.4 Are confere	ence rooms easily accessed for public / parent use?	1						Comments	1.00	1.00
1	Very unsatisfactory - Not accessible for public/parent							No conference room available for teacher/parent use		
	use									
2	Unsatisfactory - Limited access, no transparency, poor									
2	condition, difficult to find									
3	Average - Adequate accessibility, needs updates or renovations to function well									
4	Satisfactory - Good accessibility, good transparency,									
7	good size and condition									
5	Very Satisfactory - Excellent accessibility, excellent									
-	transparency, generous size, excellent condition									
N/A	Does not apply									