

Educational Suitability Summary Report

Sunset Valley Elementary School

Date: 01/21/2021 Score 56% Average

Sunset Valley Elementary School, serving an enrollment of approximately 500 students in south Austin, is known for its dual-language program. The school is an AVID and Austin Literacy Academy campus and offers the Creative Learning Initiative to its students.

The original building was built in 1971, and an annex classroom building was constructed in 1996 for a total of 67,000 square feet. The building is somewhat dated, but the learning spaces function quite well, with several large collaboration spaces surrounded by studios. This layout gives teachers flexibility to divide students into a variety of group sizes, while still supervising those students in the shared space. Acoustic privacy is difficult in these studios due to the fact that they are connected by sliding walls or open corridors. Only the newer fourth- and fifth-grade annex building is laid out with the traditional corridor lined with studios on both sides.

The grounds and play areas are well sized and well maintained. The school has multiple playscapes for different age groups; most of them look to be new and in good condition. The school has several outdoor learning gardens with good infrastructure including cisterns and compost areas. All gardens need some level of repairs, and some planting bed boards are rotting and need to be replaced. There are no outdoor studios on campus, although the site has the space and opportunity to create them.

Interview Overview

The interview for Sunset Valley Elementary School was conducted with Principal Marquez and several staff members, in addition to receiving a written response from a parent. They acknowledged that the school is 50 years old and much of it needs to be replaced or updated to meet modern standards. There are concerns that if the school is relocated, it would disrupt the ability for families to walk or bike to school.

The main building is designed around learning pods with studios surrounding a central common area. The studios are open to each other through short hallways with restrooms and sliding dividers. Although this does create some noise and privacy concerns, the staff likes the ability to co-teach when needed. If the studios were larger, they could better divide for small groups or different teaching methods. Principal Marquez would like to see improved furniture in the central spaces so that they could be more usable, in addition to better transparency between the studios and central spaces.

The staff is very proud of the cultural and community events they host. The annual talent show and student plays are popular and draw crowds from the community. They would like an improved stage with better storage to facilitate these events. The school needs a dedicated space for after-school events for parents and the community.

Educational Suitability Summary Report

Sunset Valley Elementary School



Improved outdoor learning spaces are needed. These spaces need to be covered and provided with durable furniture that does not need to be rebuilt or repainted annually. The school is working to update the learning gardens on campus and recently added a fruit tree orchard. These programs need additional storage spaces for supplies and tools to continue to function well.

Assessment Findings

The Educational Suitability Assessment of Sunset Valley Elementary School earned a 56% overall score and places the campus in a category of Average. The assessment consists of seven General Building categories and seven Academic categories to determine areas that need more attention.

Very Unsatisfactory Categories (0-35%):

General Building

Score is very unsatisfactory.

Building feels dated and does not convey pride. Hallways are only 7 feet wide, although the open learning areas between studios alleviate the feeling of congestion. No community use areas can function after-hours and be secured from the rest of the school.

Unsatisfactory Categories (36-50%):

Visual and Performing Arts

Score is unsatisfactory.

The cafeteria stage and music room are both of adequate size, but storage is limited. Art classes are split between a portable and an undersized studio within the building.

Food Services

Score is unsatisfactory.

Cafeteria is too small with no natural light and has only one option for eating space. There is only one serving line for students, which wraps out into the narrow corridor.

Technology

Score is unsatisfactory.

Studios are equipped with mobile flat screen TVs and digital projectors. Limited wall outlets force teachers and students to rely on extension cords and power strips. Some charging carts are seen in the building, but none that are in use in a studio.

Administration Spaces

Score is unsatisfactory.

The administration space feels large and open, but updates to furniture and finishes would make it feel more welcoming.

Educational Suitability Summary Report

Sunset Valley Elementary School

	A conference room across the hall is used for public and
parent use.	
Average Categories (51-65%):	
Security	
Score is average.	

Controllability of Systems

Score is average.

Lighting controls vary depending on the studio. Most have two lighting zones, but some have only one switch controlling all on or all off. Blinds throughout the school are very old but appear to be functional.

Furniture, Fixtures, Equipment

Score is average.

Furniture throughout the school is in good condition. The school currently has too many older desks that are not adjustable especially for younger students. Arrow desks are common and allow for easy reconfiguration for individual or group learning. In the library, a variety of informal seating options improves social interaction.

Academics & Learning

Score is average.

In the main building, studios are organized around large shared common areas. Transparency and access to both indoor collaboration spaces and outdoor areas give teachers maximum flexibility. The common spaces could be improved with a variety of seating and areas dedicated to individual activities. Special education takes place in retrofitted studios. The life skills class has an accessible restroom and changing table but lacks washer and dryer or training kitchen.

Media Resources

Score is average.

The library is close to the main entry, but the lack of transparency or signage makes it difficult to find. A single large room with no windows, the library can host large groups well. Heavy furniture and lack of breakout spaces makes it difficult for small group activities or individual study.

PE and Wellness

Score is average.

The gym is too small at 2,300 square feet with a low ceiling and no natural light. The hoops are original to the school and cannot be raised or lowered to increase the flexibility of the space. Support spaces for the gym were added in an addition and are spacious and well configured.

Satisfactory Categories (66-80%):

Exterior

Score is satisfactory.

Educational Suitability Summary Report

Sunset Valley Elementary School

Building signage is older and in average condition, with a monument sign and large block lettering on the building. The large drop-off canopy in the front of the building helps to indicate the location of the main entry. For pickup and drop-off, there are two locations used at the front and the side of the school. During inclement weather, buses and parent mix in the front due to lack of canopy coverage in the rear of the school. If students are dismissed on side parking lot, it is not designed for pickup, and students must walk between parked cars to get to their cars.

Outdoor Learning and Activity

Score is satisfactory.

The school has a serenity garden with a small stage and outdoor classroom. Several steel trellises are built around the exterior of the school that could be modified to provide better shade and protection from weather. There are several learning garden areas, but all of them need repairs and updates. The play areas are in good condition, with a large field and walking trail, and several playgrounds for students of different ages. More shade would help make the play areas safer and more usable in all weather.


Environmental Quality

Score is satisfactory.

Most studios have some access to natural light and views to the exterior even though the windows are not large. Acoustics are challenging because the studios are open to each other through shared bathroom hallways or sliding partitions.



Exterior: Drop-off canopy at main building entry.





Food Services: Cafeteria with updated floor and original walls and ceiling.



PE and Wellness: Gym floor is new, but rest of gym is very dated.



Academics and Learning: Typical studio with mobile furniture and access to natural light.



Academics and Learning: Typical common space between studios.



Outdoor Learning and Activity: Learning garden planters need repairs.



Outdoor Learning and Activity: Courtyard space is accessible from studios.



Visual and Performing Arts: Art studio is undersized but includes kiln room and storage.



Media Resources: Heavy furniture in library limits flexibility.



Outdoor Learning and Activity: Playscapes are in good condition but do not have shade.



Outdoor Learning and Activity: Trellised areas in corners of school could be modified to be functional outdoor studios.



Austin ISD Educational Suitability Assessment Criteria

General Building

School Name	Walk Attendees:	Date:
Sunset Valley Elementary School	Kevin Kinsey, Anacleto Rojas	1/21/2021

- Exterio	or		1	2	3	4	5	N/A	4	8.75	69%
11		te permit desirable separation of vehicular, bus and traffic?			3				Comments	1.00	3.0
	1	Very unsatisfactory - Bus, car and pedestrian all happen							There are two separate pickup and drop-off location	s. One in front	of
		at the same location							school that has a canopy and one on the side. If there	is inclement	
	2	Unsatisfactory - Cars and buses mix, pedestrians are							weather, both vehicle and bus occurs in the front and	creates issues	s with
		separated							queueing. Also dismissal on the side parking lot requ	ires students to	o walk
	3	Average - Buses, cars, and pedestrians are separate but							through parked cars.		
	_	stack space is small									
	4	Satisfactory - Buses, cars, and pedestrians are separate							Principal's note - The City of Sunset Valley has a dirt r	oad on the Eas	st side
		but drop off does not have a canopy or a holding place like a commons or cafeteria							of the property that AISD should consider acquiring fi		
	5	Very satisfactory - Buses, cars, and pedestrians are							canopy covered dismissal area for cars.	o a o, to	
	3	separate and drop off area has a canopy and							canopy covered distributed for card.		
		destination									
ı	N/A	Does not apply									
ls th	e buildi	ing easily identified with appropriate signage and									
1.2 com	nmunity	wayfinding?				4			Comments	0.25	1.00
	1	Very unsatisfactory - Campus has no signage /							Monument sign is analog but in good condition. Build	ling signage is	3
		wayfinding							adequate. Large drop-off canopy indicates entry.		
	2	Unsatisfactory - Signage/wayfinding is faded/hidden									
	3	Average - Signage / wayfinding visible but not apparent									
	4	Satisfactory - Signage / wayfinding is visible but not									
		good condition									
	5	Very satisfactory - Signage and wayfinding is visible									
	N/A	and easy to use Does not apply									

Perkins&Will 02/11/2022 ²

1 - E	Exterior (co	nt.)	1	2	3	4	5	N/A	A		
1.3	ls the dump	oster accessible for trash / compost disposal?				4			Comments	0.50	2.00
	1 2 3 4 5	Very unsatisfactory - No compost present, route has obstacles (stairs, curbs, barriers) to dumpster Unsatisfactory - Compost is present. Route has obstacles to dumpster Average - Compost is present (<100' to cafeteria), Route to dumpster is free and clear but the two are not directly adjacent. Satisfactory - Compost and dumpster are directly adjacent and route is barrier free Very Satisfactory - Compost and dumpster are directly adjacent and route is barrier free. Dumpster are shaped / positioned so people of all heights can access it.							Ramp from loading dock to parking lot level. Dumpst parking lot.	ers scattered in	n
	N/A	Does not apply	_	_	_		_				
2 - 0		arning and Activity	ı	2	3	<u> 4</u>	5	N/A	A 	15.00	67%
2.1	the ed spec	r studios and support spaces appropriately configured per ??		2					Comments	1.00	2.00
	1	Very unsatisfactory - No dedicated outdoor studios							School has a serenity garden with a small stage and	outdoor classro	oom.
	2	Unsatisfactory - Too small, poor condition, disconnected							The outdoor classroom stage needs all wood stage re	eplaced as wel	l as all
		from learning spaces, no flexibility, no shade provided							the wood benches.		
	3 4 5	Average - Adequate size, adequate condition, needs some renovations or updates to function well, 50% or less shade coverage over studio area Satisfactory - Good size, good condition, connected to learning spaces, good flexibility, more than 50% shade coverage over studio area Very satisfactory - Generous size, excellent condition,									
	Ü	connected to learning spaces, excellent flexibility, full									
		shade coverage over studio area									
	N/A	Does not apply									
2.2		playgrounds (elementary only) and support spaces per the ed spec?			3				Comments	1.00	3.00
	1	Very unsatisfactory - No dedicated active playground				•			Large play area with a wide variety of playscapes in	good conditior	n. Only
	2	Unsatisfactory - Too small, poor condition, no shade							the outdoor basketball court has shade canopy. The	school notes th	nat they
	•	provided							have older metal playground equipment that needs	to be removed	•
	3	Average - Adequate size, adequate condition, needs some renovations or updates to function well, 50% or									
		less shade coverage over play structure									
	4	Satisfactory - Good size, good condition, more than 50%									
		shade coverage over play structure									
	5	Very satisfactory - Generous size, excellent condition, full									
	N/A	shade coverage over play structure Does not apply									

2 - Outd	oor Le	arning and Activity (cont)	1	2	3	4	5	N/A			
		s and support spaces appropriately configured per the ed uation on infrastructure not condition of plants)			3				Comments	0.00	0.00
	3 4 5	Very unsatisfactory - No dedicated gardens Unsatisfactory - Too small, poor condition, disconnected from learning spaces, no flexibility, no accessible water source Average - Adequate size, adequate condition, needs some renovations or updates to function well, water source is difficult to access Satisfactory - Good size, good condition, connected to learning spaces, good flexibility, water source is accessible with 100 ft hose Very Satisfactory - Generous size, excellent condition, connected to learning spaces, excellent flexibility, water source is less than 50ft from the garden or has irrigation							Multiple garden areas on campus. The one next to po Many planters are not installed. The second, in a cou buildings, is in better condition and looks to be active Compost, small greenhouse, hose and tool shed are p are rotting out. (Monitoring answer, does not affect s Learning and Activity.)	rtyard betwee ly maintained oresent. Plante	n er beds
	N/A	Does not apply							1		1
7 4	the rain spec?	gardens and/or cisterns appropriately configured per the				4			Comments	0.00	0.00
	1 2 3 4 5	Very unsatisfactory - No rain gardens or cisterns Unsatisfactory - Too small, poor condition, not functioning, disconnected Average - Adequate size, adequate condition, is connected, needs some renovations or updates to function well Satisfactory - Good size, good condition, functions properly Very Satisfactory - Generous size, excellent condition, exceptional functionality, connected to learning spaces, educational signage provided							Cistern near rain gardens collects water from a porta function well and be in good condition. Learning pon between buildings. Additional cistern in this area but (Monitoring answer, does not affect score for Outdoo Activity.) School requests additional cistern since area where d continues to flood even though french drain was install.	d in a courtyar it is disconnec or Learning and isconnected ci	rd ted. d
	N/A	Does not apply	1						Community	0.00	0.00
2.5 DOG	1 5	hool have animal husbandry? No Yes	1						Comments	0.00	0.00
2.6 Doe	es the scl	hool have nature loop trails?	1						Comments	0.00	0.00
	1 5	No									
2.7 Doe		Yes hool have a learning pond?					5		Comments	0.00	0.00
	1 5	No Yes					-				
2.8 Doe	es the scl	hool have a grass play field and walking trail?					5		Comments	1.00	5.00
	1	No Ver									

3 - General Building	1	2	3	4	5	N/A		11.25	31%
3.1 Are interior circulation routes wide enough to safely and effectively accommodate student movement?			3				Comments	0.50	1.50
l Very unsatisfactory - Primary circulation is 5'-0" to 6'-0"							7.5 foot corridors		
wide									
2 Unsatisfactory - Primary circulation is 6'-0" to 7'-0" wide									
3 Average - Primary circulation is 7'-0" to 8'-0" wide									
4 Satisfactory - Primary circulation is 8'-0"-10'-0" wide									
5 Very satisfactory - Primary circulation is 10'-0"+ wide									
N/A Does not apply									
Are community use areas arranged so that the school can allow night	1						Comments		
functions without full school access?							Comments	0.75	0.75
1 Very unsatisfactory - Cafeteria, gym, and library cannot									
be accessed after hours									
2 Unsatisfactory - Only one of the public spaces (Cafeteria, Gym and Library) can be accessed from parking and									
secured after hours									
3 Average - Only two of the public spaces can be accessed									
from parking and secured after hours									
4 Satisfactory - All of the public spaces can be accessed									
from parking and secured from the rest of the building									
but not individually									
5 Very satisfactory - Cafeteria, gym, and library can be									
accessed from parking and locked off from rest of									
campus for night/evening use with their own entrance									
N/A Does not apply					ı			T	
3.3 Is there a community room that is a dedicated meeting space outside of school function?	1						Comments	0.75	
1 Very unsatisfactory - No dedicated community room								0.75	0.75
2 Unsatisfactory - No dedicated community room 2 Unsatisfactory - Community room but within school									
function, no access after school hours									
3 Average - Community room, moderate size, but need									
some renovations or updates to function well									
4 Satisfactory - Community room, good size /layout, meets									
needs /functions well									
5 Very Satisfactory - Community room, generous size, nice									
condition, functions appropriately outside of school function									
N/A Does not apply									
Does the general appearance of the school convey pride for the							_		
3.4 students and community?		2					Comments	0.25	0.50
Very unsatisfactory - General appearance is poor							School feels dated and in fair condition. School and g	grounds appea	r to be
Unsatisfactory - General appearance is aged but ok							not well maintained. Paint is peeling, gutters are pro	blematic, and	
3 Average - General appearance is good							landscaping needs work.		
4 Satisfactory - General appearance shows pride in									
campus and student works									
5 Very Satisfactory - General appearance shows pride in									
campus and student works and is welcoming to the									
community N/A Does not apply									
. A/A Boos not apply									

4 - Security	1	2	3	4	5 N/	'A	16.25
4.1 Does the facility have key card access at all major entries?						Comments	0.25
1 Very unsatisfactory - No entries							
2 Unsatisfactory - 1/4 of major entries							,
3 Average - 1/2 of major entries							
4 Satisfactory - 3/4 of major entries							
5 Very satisfactory - All of major entries							
N/A Does not apply						L	

4.2 How adequate is site lighting and security for the campus overall?	•					Comments	1.00
1 Very unsatisfactory - No exterior lighting, no secure perimeter		ı			1		
2 Unsatisfactory - Lighting is limited to front entry only, parking lot lighting poor, security is minimal							
Average - Lighting at all night-use entries and parkin lot, but poor condition. Security is moderate	g						
4 Satisfactory - Lighting at all night-use entries and parking lots, good condition, signage less visible, perimeter is well secured but needs updates							
5 Very satisfactory - Signage, parking lots, and entries	are						
well lit, visible and easy to use, perimeter is very secu							
N/A Does not apply							
ls the main office located at the school entry and configured with	a					Comments	
4.3 secure vestibule to the main corridor?						Confinents	1.00
 Very unsatisfactory - No secure vestibule, office locat 	ed						
far from main entry, allows visitors access to school							
unsupervised							
2 Unsatisfactory - No secure vestibule, office located	,						
somewhat far from main entry, minimal supervision o	PΤ						
visitors 3 Average - Office close to entry, views of front door, b							
3 Average - Office close to entry, views of front door, b no secure vestibule	ut						
4 Satisfactory - Office is well-located with a secure							
vestibule, but needs updates							
5 Very satisfactory - Office well-located with secure							
vestibule and all appropriate security features							
N/A Does not apply							
Is there enough interior transparency for faculty to passively		I					
4.4 supervise learners and their activities who are not in studios?			3			Comments	1.00 3.00
1 Very unsatisfactory - No transparency of walls					l l	Studios in learning pods have good transparency. C	
2 Unsatisfactory - Limited transparency in certain locat	ions					otadios in learning pous nave good transparency.	ther studies do not.
Average - Good transparency in certain locations but in address to a provide a straight and a straight	i						
inadequate or missing in other locations of school							
4 Satisfactory - Adequate transparency throughout the school	;						
scnool 5 Very satisfactory - Excellent transparency throughout	the						
school	. cric						
N/A Does not apply						L	

Perkins&Will 02/11/2022 ⁶

5 - Environme	ntal Quality	1	2	3	4	5	N/A	4	25.00	72%
5.1 How are a	coustics in studios in general?			3				Comments	1.00	3.00
1 2 3 4 5 N/A	Very unsatisfactory - Recognized word/sound from adjacent studio/corridor Unsatisfactory - Audible sound from adjacent studio/corridor Average - Slight sound from outside room Satisfactory - Walls to deck insulated only white noise from mechanical system Very satisfactory - Able to hear quiet speaking from across the room Does not apply							Muffled noise from corridor. Partitions and open con studios allow lots of noise.	nections betwee	en
5.2 Is the studi	io artificial lighting adequate quality?			3				Comments	1.00	3.00
1 2 3 4 5 N/A	Very unsatisfactory - Sporadic lights work, glare, less than 20 FC Unsatisfactory - 10-19 FC or serious glare Average- 20-29 FC minor glare Satisfactory - 30-39 FC and no glare Very satisfactory - 40+ FC and no glare Does not apply									
5.3 Is there ac	cess to natural light in studios?				4			Comments	1.00	4.00
1 2 3 4 5	Very unsatisfactory - No learning spaces have natural light Unsatisfactory - 1-25% of learning spaces have natural light or windows are too small to let in light Average - 26-50% of learning spaces have natural light Satisfactory - 51-75% of learning spaces have natural light Very satisfactory - 76-100% of learning spaces have natural light							Not all studios have natural light. Windows are small	when present.	
N/A	Does not apply							Community		
5.4 Is there ac	cess to outside views from learning spaces? Very unsatisfactory - No learning spaces have views					5		Comments	1.00	5.00
2 3 4 5	Unsatisfactory - 1-25% of learning spaces have views or windows are too small to see out Average - 26-50% of learning spaces have views Satisfactory - 51-75% of learning spaces have views Very satisfactory - 76-100% of learning spaces have views							Most studios have exterior views.		
N/A	Does not apply									

Perkins&Will 02/11/2022 ⁷

5 - Environme	ntal Quality (cont.)	1	2	3	4	5	N/A			
5.5 Does the b	ouilding have odor or pest problems?			3				Comments	1.00	3.00
1	Very unsatisfactory - Evidence of both pests and odors							The campus has found snakes. The campus has rat tr	aps.	
2	Unsatisfactory - Evidence of pests or odors							·		
3	Average - Limited evidence of pests, no odors									
4	Satisfactory - No evidence of pests / odors, school									
	cleanliness in good condition									
5	Very Satisfactory - No evidence, school cleanliness in									
	excellent condition									
N/A	Does not apply									
6 - Controllab	ility of Systems	1	2	3	4	5	N/A		12.50	60%
6.1 Does the s	tudio thermostat allow for individual control?					5		Comments	0.50	2.50
1	No									
5	Yes									
6.2 Are shade	s provided to control natural light in learning spaces?			3				Comments	1.00	3.00
1	Very unsatisfactory - No, windows are covered with							Blinds are very old.		
	boards/paper									
2	Unsatisfactory - No, windows have no light control									
3	Average - Yes, but poor condition blinds									
4	Satisfactory - Yes, blinds									
5	Very satisfactory - Blackout shades									
N/A	Does not apply									
6.3 What is th	e quality of lighting controls in the studios?		2					Comments	1.00	2.00
1	Very unsatisfactory - Single switch only per room							Two lighting zones in some studios. Others only have	1 switch.	
2	Unsatisfactory - Alternating rows switch off									
3	Average - Alternating lamps in single fixtures switch off									
4	Satisfactory - Tri level switching									
5	Very satisfactory - Dimmable									
N/A	Does not apply							•		

7 - Furniture, F	Fixtures & Equipment	1	2	3	4	5	N/A		18.75	59%
7.1 What is the	e current condition of the furniture?				4			Comments	0.75	3.00
1	Very unsatisfactory - Damaged or broken, non-							Mixed. Many studios have arrow desks and loose cha	irs.	
	functioning									
2	Unsatisfactory - Torn/ bent/ wrong size									
3	Average - Scratched/dented/marked									
4	Satisfactory - Not new, but sturdy and clean									
5	Very satisfactory - New									
N/A	Does not apply									
	ety of furniture types being accommodated throughout the arning commons, dining commons, other multi-use spaces?		2					Comments	100	2.00
1	Very Unsatisfactory - Same furniture used in all spaces		<u> </u>					Variation of Counitions and the Ulbrania Mark common and	1.00	2.00
1								Variety of furniture only in library. Most common spaced on not have furniture.	es between st	uaios
2	Unsatisfactory - Furniture variety in one multi-use space							do not nave furniture.		
3	Average - Furniture variety in more than one multi-use									
	space									
4	Satisfactory - All multi-use spaces have greater than one type of furniture									
5	Very satisfactory - All multi-use spaces have greater									
ŭ	than two types of furniture									
N/A	Does not apply							L		
How well o	does furniture accommodate rapid reconfiguration of a			3				Comments		
7.3 space?				3				Comments	1.00	3.00
1	Very Unsatisfactory - Furniture is fixed or very heavy							Arrow desks allow for individual or group activities.		
2	Unsatisfactory - Furniture does not allow desks to be									
	configured as individuals, small groups, or large groups									
3	Average - Mix of furniture that can reconfigure but is									
4	cumbersome to move									
4	Satisfactory - Furniture is flexible for multiple									
5	configurations of space Very satisfactory - Furniture is flexible for multiple									
ŭ	configurations of space, easy to move and stack									
N/A	Does not apply									
			1							
7.4 Is the furni	ture ergonomic and size appropriate for grade level?			3				Comments	1.00	3.00
1	Very unsatisfactory - Desk with attached chair							Principal's note - More individual student tables or de	sks are neede	d. We
	combinations too small for grade level							have too many old tables that are not adjustable esp	ecially in the l	ower
2	Unsatisfactory - Desk with attached chair combinations							grades.		
3	Average - Mix of studios with tables/loose chairs and									
4	desks with fixed seats									
	Very satisfactory - Tables with loose chairs									
5	Very satisfactory - Tables with loose chairs that allow									
N/A	students to be active Does not apply									

Perkins&Will 02/11/2022 ⁹

Zero Waste		1	2	3	4	5	N/A	4 5.00	80%
	and corridors have blue recycle bins with bilingual s and/or image sorting instructions?					5		Comments 0.50	2.50
1 2 3	Very unsatisfactory - There are no recycling and landfill bins and signage are sparse or infrequent, OR there are only landfill bins with no recycling bins. Unsatisfactory - Bins and signage are sparse or infrequent and/or lack clear signage. Average - 50% of corridors and studios have both a landfill bin and a recycle bin in an accessible location. The containers have clear signage.							A score for this category is being recorded, but this category is not calculated in the overall ESA average.	
4	Satisfactory - 75% of studios and corridors have a visible landfill and recycle collection containers in an accessible location. The containers have clear signage.								
5 N/A	Very satisfactory - All studios / corridors (100%) have visible landfill and recycle collection containers in accessible locations. The containers have clear signage, and the style and format is consistent and uniform across campus. Does not apply								
of each: gr	afeteria (or wherever meals are served) have at least one een compost bin, blue recycle bin, and landfill bin? Are the ed clearly with bilingual and/or image sorting?			3				Comments	
3 4	Very unsatisfactory- There may be landfill bins, but there are no compost and/or recycle bins. There is not clear sorting signage. Unsatisfactory- Recycle, landfill, and compost bins are present, but the bins are scattered and no co-located next to one another. Signage is absent or inconsistent. Average- There is at least one waste station with all three bins (recycle, compost, landfill) located with close proximity to one another. The signage is visible and consistent. Satisfactory- There are several waste stations as described above							Unch not being served in cafeteria so bins were not out at time of assessment.	1.50
5 N/A	described above Very Satisfactory - There are several waste stations as described above, and additional signage in the cafeteria that encourages recycling/composting. Does not apply								



Austin ISD Educational Suitability Assessment Criteria

Academics - Elementary School

School Name	Walk Attendees:	Date:
Sunset Valley Elementary School	Kevin Kinsey, Anacleto Rojas	1/21/2021

- Academics	& Learning	1	2	3	4	5	N/A		70.00	579
8.1 Are studios	appropriately configured per the ed spec?			3				Comments	1.00	3.0
1	Very unsatisfactory - Too small, no flexibility,							Studios built around open collaboration spaces with	some transpar	ency.
	disconnected							Each studio is also connected through a sliding partit	ion. Studios ra	nge in
2	Unsatisfactory - Too small, only one area for all teaching methods, limited flexibility, disconnected							size from ~780-850 square feet.		
3	Neutral - Adequate size, multiple areas for different							Principal's note - We have 2 classrooms in the PK pod	and 2 classroo	oms in
	teaching methods, adequate flexibility, limited							the K pod that are not suitable teaching rooms. They		
	transparency and connection to other studios and							the other rooms. These rooms were originally part of		
	shared learning spaces, needs updates or renovations to							pod and were later converted to classrooms	and open area	or ouc
	function well.							pod drid were later converted to classrooms		
4	Satisfactory - Good size, multiple areas for different									
	teaching methods, good flexibility, good transparency									
	and connection to other studios and shared learning									
_	spaces									
5	Very Satisfactory - Generous size, multiple areas for different teaching methods, excellent flexibility,									
	generous display area and visual teaching tools,									
	excellent transparency and connection with other									
	studios and shared learning spaces									
N/A	Does not apply									
Do Pre-K ‹	and Kinder have appropriate support spaces such as				Ι.			_		
8.2 restrooms	and storage per the ed spec?				4			Comments	1.00	4.0
1	Very unsatisfactory - None provided							All studios have restrooms and storage attached.		
2	Unsatisfactory - Too small, disconnected, poor condition							-		
3	Neutral - Adequate size, average condition, needs									
	updates or renovations to function well									
4	Satisfactory - Good size, connected, good condition									
5	Very Satisfactory - Generous size, connected, excellent									
	condition									
N/A	Does not apply									

8 - A	cademics	& Learning (cont.)	1	2	3	4	5	N/A	1		
8.3	Do studios ed spec?	have appropriate support spaces such as storage per the			3				Comments	1.00	3.00
	1	Very unsatisfactory - None provided							Storage in built-ins along wall. Original and somewh	at dated.	
	2	Unsatisfactory - Too small, disconnected, poor condition									
	3	Neutral - Adequate size, average condition, needs									
		updates or renovations to function well									
	4	Satisfactory - Good size, connected, good condition									
	5	Very Satisfactory - Generous size, connected, excellent									
		condition									
	N/A	Does not apply									
8.4		earning neighborhoods have small group rooms and open			3				Comments		
0.4	collaboration	•			3				Comments	1.00	3.00
	1	Very unsatisfactory - No breakout rooms or open							Large open collaboration space in center of studio cl	usters. No dedi	cated
		collaboration spaces are provided							small group rooms.		
	2	Unsatisfactory - Too small or too few, poor condition, no									
		flexibility, lacks visual connection to learning									
	•	neighborhood, poor acoustic privacy									
	3	Average - Adequate size, adequate condition, needs some renovations or updates to function well									
	4	Satisfactory - Good size, good condition and flexibility,									
	4	transparency and connection to learning neighborhood,									
		acoustic privacy									
	5	Very Satisfactory - Generous size, excellent condition									
		and flexibility, transparency and connection to learning									
		neighborhood, acoustic privacy									
	N/A	Does not apply									
8.5	Are genera	l studios large enough to support project-based learning				4			Comments		
0.5	and multipl	le teaching modalities?				4			Comments	1.00	4.00
	1	Very unsatisfactory - Too small, no flexibility, does not							Good connectivity to other studios and central collab	oration space.	
		support project-based learning							Transparency allows passive supervision.		
	2	Unsatisfactory - Undersized, decentralized resources,									
		limited flexibility									
	3	Average - Adequate size, needs some renovations or									
	4	updates to function well									
	4	Satisfactory - Good size, centralized resources, good flexibility									
	5	Very Satisfactory - Generous size, centralized project									
	3	resources, excellent flexibility									
	N/A	Does not apply							L		

Perkins&Will 02/11/2022 ³

8 - A	cademics	& Learning (cont.)	1	2	3	4	5	N/A			
8.6	Are Maker the ed spec	Spaces and support spaces appropriately configured per :?	1						Comments	1.00	1.00
	1 2 3	Very unsatisfactory - No dedicated maker spaces Unsatisfactory - Too small, poor condition, disconnected from learning spaces, no flexibility Average - Adequate size, adequate condition, needs									
	4	some renovations or updates to function well Satisfactory - Good size, good condition, connected to learning spaces									
	5 N/A	Very Satisfactory - Generous size, excellent condition, connected to learning spaces Does not apply									
8.7		rofessional Learning Center in the learning neighborhood?	1						Comments	1.00	1.00
	1	Very unsatisfactory - No dedicated space for Professional Learning Center									
	2	Unsatisfactory - Too small, poor condition, disconnected									
	3	Average - Adequate size, adequate condition, needs some renovations or updates to function well									
	4	Satisfactory - Good size, good condition, connected									
	5	Very Satisfactory - Generous size, excellent condition, connected									
	N/A	Does not apply									
8.8	Is there a d	edicated science room and support space?	1						Comments	0.00	0.00
	1 5	No Yes							Monitoring answer, but doesn't affect overall score.		
8.9		dequate places to display the evidence and artifacts of oth 2D and 3D)?		2					Comments	1.00	2.00
	1	Very unsatisfactory - No dedicated space							Tack strips and clips for 2D work. Some 3D display cas	es present but	t
	2	Unsatisfactory - Too small, non-dedicated, poor condition							limited.		
	3	Average - Adequate size, adequate condition, needs									
	4	updates or renovations to function well									
	4 5	Satisfactory - Good size, good condition Very Satisfactory - Generous size, excellent condition									
	N/A	Does not apply									

Perkins&Will 02/11/2022 ⁴

8 - A	cademics	& Learning (cont.)	1	2	3	4	5	N/A	4		
8.10	Does the bu	uilding provide adequate opportunities for				4			Comments		
8.10	students/te	achers to collaborate in varying group sizes?				4			Comments	1.00	4.00
	1	Very unsatisfactory - No space to support collaboration in various sizes. Unsatisfactory - Too small, inflexible, only one option,							Learning commons function well. Studios have flexibito indoor and outdoor collaboration spaces.	lity and transp	arency
	3	does not support a variety of group sizes Average - Adequate space for collaboration, needs updates or renovations to function well.									
	4	Satisfactory - Good size, good condition, multiple options to support a variety of group sizes									
	5	Very Satisfactory - Generous size, excellent condition, multiple options to support a variety of group sizes									
	N/A	Does not apply	ı	Ι		Ι	ı				
8.11	Does the bu	uilding provide opportunities for informal interaction?		2					Comments	1.00	2.00
	1	Very unsatisfactory - No space							No informal seating, but common spaces are large a	nd could easily	,
	2	Unsatisfactory - Too small, poor condition, layout and							accommodate.		
		furnishings do not support informal interaction well									
	3	Average - Adequate size and condition, needs updates							Principal's note - Need more furtniture to accommod	ate this and po	ssibly
		or renovations to function well.							to display student work 2D /3D since there is little to	no room to do t	that in
	4	Satisfactory - Good size, good condition, layout and							classrooms		
	_	furnishings support informal interactions									
	5	Very Satisfactory - Generous size, excellent condition,									
	N/A	layout and furnishings support informal interactions									
		Does not apply arning neighborhood / building provide adequate	l	T		T	<u> </u>			l .	
8.12		· · · · · · · · · · · · · · · ·		2					Comments	100	0.00
	opportuniti	es for students to work independently?								1.00	2.00
	1	Very unsatisfactory - No breakout rooms/small study							No individual study areas. Common areas are large	enough that the	ey
	0	spaces							could accommodate this. Furniture is needed.		
	2	Unsatisfactory - Too small, poor condition, no acoustic									
		privacy, only one space for independent work,									
	2	disconnected from learning neighborhood									
	3	Average - Adequate size and condition, needs updates									
	4	or renovations to function well. Satisfactory - Good size and condition, acoustic privacy,									
	4										
		variety of independent work space options, connected to									
	5	learning neighborhood Very Satisfactory - Generous size, excellent condition,									
	3	acoustic privacy, variety of independent work space									
		options, connected to learning neighborhood									
	N/A	Does not apply									

O2/11/2022 ⁵

8 - <i>A</i>	Academics	& Learning (cont.)						
8.13	Are Special spec?	Education spaces appropriately configured per the ed		3		Comments	1.00	3.00
	1	Very unsatisfactory - Too small, no flexibility, disconnected				Early childhood special education takes place in typi in retrofitted studio with accessible restroom and cha		skills is
	2	Unsatisfactory - Too small, only one area for all teaching methods, limited flexibility, disconnected						
	3	Neutral - Adequate size, multiple areas for different teaching methods, adequate flexibility, limited transparency and connection to other studios and shared learning spaces, needs updates or renovations to function well.						
	4	Satisfactory - Good size, multiple areas for different teaching methods, good flexibility, good transparency and connection to other studios and shared learning spaces						
	5	Very Satisfactory - Generous size, multiple areas for different teaching methods, excellent flexibility, generous display area and visual teaching tools, excellent transparency and connection with other studios and shared learning spaces						
	N/A	Does not apply						
8.14		Education support spaces, such as storage, space for ver, appropriately configured per the ed spec?		3		Comments	1.00	3.00
	1 2	Very unsatisfactory - None provided Unsatisfactory - Too small, disconnected, poor condition				No washer/dryer or support spaces present. Dedicat converted to computer lab.	ed life skills stu	dio
	3	Neutral - Adequate size, average condition, needs updates or renovations to function well						
	4	Satisfactory - Good size, connected, good condition						
	5	Very Satisfactory - Generous size, connected, excellent condition						
	N/A	Does not apply						
8.15		ble restrooms and changing rooms readily available to Education spaces?			5	Comments	1.00	5.00
	1	No						
	5	Yes						

Perkins&Will 02/11/2022 ⁶

9 - Visual and	Performing Arts	1	2	3	4	5	N/A	A	15.00	47%
9.1 Are music per the ed	spaces and the cafeteria stage appropriately configured spec?		2					Comments	1.00	2.00
1	Very unsatisfactory - Too small, missing program spaces							Stage in cafeteria is adequate size and condition. Mu	usic spaces are	located
2	Unsatisfactory - Too small, poor condition							directly behind stage.		
3	Neutral - Adequate size, adequate condition, needs updates or renovations to function well.									
4	Satisfactory - Good size, good condition									
5	Very Satisfactory - Generous size, excellent condition									
N/A	Does not apply									
Are music	and performance storage spaces appropriately configured									
9.2 per the ed			2					Comments	1.00	2.00
1	Very unsatisfactory - None provided							Minimal storage.	Į.	
2	Unsatisfactory - Too small, disconnected, poor condition									
3	Neutral - Adequate size, average condition, needs									
	updates or renovations to function well									
4	Satisfactory - Good size, connected, good condition									
5	Very Satisfactory - Generous size, connected, excellent condition									
N/A	Does not apply									
9.3 Are Visual	Arts spaces and storage appropriately configured per the			3				Comments		
9.3 ed spec?				3				Comments	1.00	3.00
1	Very unsatisfactory - Too small, missing program spaces							Art room undersized; additional studio is held in port kiln room and storage attached. No restroom.	able. Main roc	om has
2	Unsatisfactory - Too small, poor condition							Ĭ		
3	Average - Adequate size, adequate condition, needs some renovations or updates to function well							School notes there is no space to display work 2D or 3	3D.	
4	Satisfactory - Good size, good condition									
5	Very Satisfactory - Generous size, excellent condition									
N/A	Does not apply									

10 - PE and We	ellness	1	2	3	4	5	N/A		10.00	60%
Does the co	ampus meet the ed spec standard for physical education		2					Comments		
program sp	paces?							Confinencs	1.00	2.00
1	Very unsatisfactory - Too small, missing program spaces							Too small with low ceilings at 2,300 square feet, no no	atural light. Ho	ops
2	Unsatisfactory - Too small, poor condition							are original.		
3	Average - Adequate size, adequate condition, needs									
3	some renovations or updates to function well									
4	Satisfactory - Good size, good condition									
5	Very Satisfactory - Generous size, excellent condition									
N/A	Does not apply									
Are the phy	ysical education storage spaces appropriately configured									
10.2 per the ed					4			Comments	1.00	4.00
1	Very unsatisfactory - None provided		1				l	Gym office and storage have been updated. Storage		
2	Unsatisfactory - Too small, disconnected, poor condition							interior and exterior. Restroom in office.		
3	Neutral - Adequate size, average condition, needs									
	updates or renovations to function well									
4	Satisfactory - Good size, connected, good condition									
5	Very Satisfactory - Generous size, connected, excellent									
	condition									
N/A	Does not apply									
11 - Food Servi	ces	1	2	3	4	5	N/A		10.00	50%
11.1 Is the Dinin	g Commons appropriately configured per the ed spec?		2					Comments	1.00	
									1.00	2.00
	Vancous stief autom. To a small maissing a magnum on a second							Conferencial terms of the control of		L.
1	Very unsatisfactory - Too small, missing program spaces							Cafeteria too small with no natural light. Flooring is no	ew. Connected	l to
	, , , , , , , , , , , , , , , , , , , ,							Cafeteria too small with no natural light. Flooring is no gym with movable wall.	ew. Connected	l to
2	Unsatisfactory - Too small, poor condition, only one								ew. Connectec	l to
	, , , , , , , , , , , , , , , , , , , ,								ew. Connectec	I to
	Unsatisfactory - Too small, poor condition, only one								ew. Connected	I to
2	Unsatisfactory - Too small, poor condition, only one option for eating space provided, inadequate circulation								ew. Connected	Ito
2	Unsatisfactory - Too small, poor condition, only one option for eating space provided, inadequate circulation Average - Adequate size and condition, needs updates								ew. Connected	Ito
2	Unsatisfactory - Too small, poor condition, only one option for eating space provided, inadequate circulation Average - Adequate size and condition, needs updates or renovations to function well Satisfactory - Good size and condition, good circulation, multiple options for eating space (ex: connection to								ew. Connected	I to
2 3 4	Unsatisfactory - Too small, poor condition, only one option for eating space provided, inadequate circulation Average - Adequate size and condition, needs updates or renovations to function well Satisfactory - Good size and condition, good circulation, multiple options for eating space (ex: connection to outdoor eating space)								ew. Connected	I to
2	Unsatisfactory - Too small, poor condition, only one option for eating space provided, inadequate circulation Average - Adequate size and condition, needs updates or renovations to function well Satisfactory - Good size and condition, good circulation, multiple options for eating space (ex: connection to outdoor eating space) Very Satisfactory - Generous size, excellent condition								ew. Connected	I to
2 3 4	Unsatisfactory - Too small, poor condition, only one option for eating space provided, inadequate circulation Average - Adequate size and condition, needs updates or renovations to function well Satisfactory - Good size and condition, good circulation, multiple options for eating space (ex: connection to outdoor eating space) Very Satisfactory - Generous size, excellent condition and circulation, multiple options for eating space (ex:								ew. Connected	Ito
2 3 4 5	Unsatisfactory - Too small, poor condition, only one option for eating space provided, inadequate circulation Average - Adequate size and condition, needs updates or renovations to function well Satisfactory - Good size and condition, good circulation, multiple options for eating space (ex: connection to outdoor eating space) Very Satisfactory - Generous size, excellent condition and circulation, multiple options for eating space (ex: connection to outdoor eating space)								ew. Connected	Ito
2 3 4 5 N/A	Unsatisfactory - Too small, poor condition, only one option for eating space provided, inadequate circulation Average - Adequate size and condition, needs updates or renovations to function well Satisfactory - Good size and condition, good circulation, multiple options for eating space (ex: connection to outdoor eating space) Very Satisfactory - Generous size, excellent condition and circulation, multiple options for eating space (ex: connection to outdoor eating space) Does not apply								ew. Connected	I to
2 3 4 5 N/A	Unsatisfactory - Too small, poor condition, only one option for eating space provided, inadequate circulation Average - Adequate size and condition, needs updates or renovations to function well Satisfactory - Good size and condition, good circulation, multiple options for eating space (ex: connection to outdoor eating space) Very Satisfactory - Generous size, excellent condition and circulation, multiple options for eating space (ex: connection to outdoor eating space) Does not apply ad Services support spaces appropriately configured per			3						
2 3 4 5 N/A	Unsatisfactory - Too small, poor condition, only one option for eating space provided, inadequate circulation Average - Adequate size and condition, needs updates or renovations to function well Satisfactory - Good size and condition, good circulation, multiple options for eating space (ex: connection to outdoor eating space) Very Satisfactory - Generous size, excellent condition and circulation, multiple options for eating space (ex: connection to outdoor eating space) Does not apply ad Services support spaces appropriately configured per c?			3				gym with movable wall. Comments	ew. Connected	3.00
3 4 5 N/A 11.2 Are the Foot the ed special	Unsatisfactory - Too small, poor condition, only one option for eating space provided, inadequate circulation Average - Adequate size and condition, needs updates or renovations to function well Satisfactory - Good size and condition, good circulation, multiple options for eating space (ex: connection to outdoor eating space) Very Satisfactory - Generous size, excellent condition and circulation, multiple options for eating space (ex: connection to outdoor eating space) Does not apply ad Services support spaces appropriately configured per control of the space of th			3				gym with movable wall.		
3 4 5 N/A 11.2 Are the Foot the ed speci	Unsatisfactory - Too small, poor condition, only one option for eating space provided, inadequate circulation Average - Adequate size and condition, needs updates or renovations to function well Satisfactory - Good size and condition, good circulation, multiple options for eating space (ex: connection to outdoor eating space) Very Satisfactory - Generous size, excellent condition and circulation, multiple options for eating space (ex: connection to outdoor eating space) Does not apply ad Services support spaces appropriately configured per c?			3				gym with movable wall. Comments		
3 4 5 N/A 11.2 Are the Foot the ed special	Unsatisfactory - Too small, poor condition, only one option for eating space provided, inadequate circulation Average - Adequate size and condition, needs updates or renovations to function well Satisfactory - Good size and condition, good circulation, multiple options for eating space (ex: connection to outdoor eating space) Very Satisfactory - Generous size, excellent condition and circulation, multiple options for eating space (ex: connection to outdoor eating space) Does not apply ad Services support spaces appropriately configured per control of the space of th			3				gym with movable wall. Comments		
2 3 4 5 N/A 11.2 Are the Foot the ed spece 1 2	Unsatisfactory - Too small, poor condition, only one option for eating space provided, inadequate circulation Average - Adequate size and condition, needs updates or renovations to function well Satisfactory - Good size and condition, good circulation, multiple options for eating space (ex: connection to outdoor eating space) Very Satisfactory - Generous size, excellent condition and circulation, multiple options for eating space (ex: connection to outdoor eating space) Does not apply ad Services support spaces appropriately configured per control of the space of th			3				gym with movable wall. Comments		
2 3 4 5 N/A 11.2 Are the Foot the ed spece 1 2	Unsatisfactory - Too small, poor condition, only one option for eating space provided, inadequate circulation Average - Adequate size and condition, needs updates or renovations to function well Satisfactory - Good size and condition, good circulation, multiple options for eating space (ex: connection to outdoor eating space) Very Satisfactory - Generous size, excellent condition and circulation, multiple options for eating space (ex: connection to outdoor eating space) Does not apply od Services support spaces appropriately configured per control of the space of th			3				gym with movable wall. Comments		
2 3 4 5 N/A 11.2 Are the Foot the ed spect 1 2 3	Unsatisfactory - Too small, poor condition, only one option for eating space provided, inadequate circulation Average - Adequate size and condition, needs updates or renovations to function well Satisfactory - Good size and condition, good circulation, multiple options for eating space (ex: connection to outdoor eating space) Very Satisfactory - Generous size, excellent condition and circulation, multiple options for eating space (ex: connection to outdoor eating space) Does not apply ad Services support spaces appropriately configured per control of the space of th			3				gym with movable wall. Comments		
2 3 4 5 N/A 11.2 Are the Foot the ed spect 1 2 3 4	Unsatisfactory - Too small, poor condition, only one option for eating space provided, inadequate circulation Average - Adequate size and condition, needs updates or renovations to function well Satisfactory - Good size and condition, good circulation, multiple options for eating space (ex: connection to outdoor eating space) Very Satisfactory - Generous size, excellent condition and circulation, multiple options for eating space (ex: connection to outdoor eating space) Does not apply ad Services support spaces appropriately configured percty Very unsatisfactory - None provided Unsatisfactory - Too small, disconnected, poor condition Neutral - Adequate size, average condition, needs updates or renovations to function well Satisfactory - Good size, connected, good condition			3				gym with movable wall. Comments		

12 - Media Res	ources	1	2	3	4	5	N/A	1	30.00	57%
121	ry/Media Center easily accessible for the occupants and			3				Comments		
visitors to tl	he school?			0				Comments	1.00	3.00
1	Very unsatisfactory - Not accessible							Somewhat near to main entrance but lacks adequate	e signage for	
2	Unsatisfactory - Limited access, difficult to find, no							wayfinding. Some transparency but signage is poor.		
	transparency									
3	Average - Adequate accessibility, needs updates or									
	renovations to function well									
4	Satisfactory - Accessible, easy to find, good									
_	transparency, good condition									
5	Very Satisfactory - Accessible, easy to find, excellent									
N1/A	transparency, excellent condition									
N/A	Does not apply	ı	ı		Ι	1	ı			
12.2 How well d	oes the Library/Media Center support quiet study?		2					Comments	1.00	2.00
1	Very unsatisfactory - No quiet study spaces							One large area and no breakout spaces. No acoustic	privacy.	
2	Unsatisfactory - One area in poor condition, poor									
	acoustic privacy									
3	Average - One or more areas provided, needing									
	updates or renovations to function well									
4	Satisfactory - Clusters or small rooms adjacent to media									
-	center, good condition, good acoustic privacy									
5	Very Satisfactory - Multiple clusters or small rooms									
	adjacent to media center, excellent condition, excellent									
N/A	acoustic privacy Does not apply									
	· · ·	l					I			
12.3 How well d	oes the Library/Media Center support social interaction?				4			Comments	1.00	4.00
1	Very unsatisfactory - No space							Some informal seating in multiple areas.		
2	Unsatisfactory - Too small, poor condition, layout and									
	furnishings do not support informal interaction well									
3	Average - Adequate size and condition, needs updates									
	or renovations to function well.									
4	Satisfactory - Good size, good condition, layout and									
	furnishings support informal interactions									
5	Very Satisfactory - Generous size, excellent condition,									
	layout and furnishings support informal interactions									
N/A	Does not apply	1			1	1		T		
12/1	oes the Library/Media Center support collaborative work		2					Comments	1.00	
in small gro	pups (4-8 students)?	<u> </u>	<u> </u>	L	<u> </u>	<u> </u>	<u> </u>		1.00	2.00
1	Very unsatisfactory - No breakout rooms, no flexible							Only one area provided. No acoustic separation. No	breakout spac	es.
0	furniture, no support									
2	Unsatisfactory - Too small, one area, poor condition									
3	Average - Adequate size, multiple areas provided,									
4	needing updates or renovations to function well									
4	Satisfactory - Clusters or small rooms adjacent to media									
5	center, flexible furniture, good condition Very Satisfactory - Multiple clusters or small rooms									
5	adjacent to media center, flexible furniture, excellent									
	condition									
N/A	Does not apply									

12 - Media Res	ources - Continued	1	2	3	4	5	N/A			
17.5	oes the Library/Media Center support collaborative work oups (10-25)?			3				Comments	1.00	3.00
1 2 3 4 5	Very unsatisfactory - No gathering areas Unsatisfactory - Too small, one common space, limited seating, poor condition Average - Adequate size, one common space, needs updates or renovations to function well Satisfactory - Good size, multiple common spaces with seating, good condition Very Satisfactory - Generous size, multiple commons spaces with seating, excellent condition							Could host large groups, but the furniture is bulky and	difficult to mo	ove.
N/A 12.6 How well d	Does not apply loes the Library/Media Center support technology?			3				Comments	1.00	3.00
1 2 3 4 5 N/A	Very unsatisfactory - No vis comm tools Unsatisfactory - Outdated, poorly functioning, or insufficient Good - Mix of old and new whiteboards/projectors/etc. Satisfactory - Projectors, marker boards, smart boards in most spaces - good condition Very Satisfactory - Projectors, marker boards, smart boards in most spaces - new condition Does not apply		l					Multiple TVs on mobile carts and two different projecto	ors.	
13 - Technolog		1	2	3	4	5	N/A		20.00	45%
*	quipped are the facilities with instructional technology?			3				Comments	1.00	3.00
1 2 3 4 5	Very unsatisfactory - Limited to no technology present in instructional spaces Unsatisfactory - One type of technology present Average - Multiple types of technology, smart boards, poor condition, limited to only certain areas of school Satisfactory - Multiple types of technology, smart boards, good condition. Very Satisfactory - Multiple types of technology, smart boards, excellent condition							Flat screens on mobile carts and digital projectors.		
N/A Is there an	Does not apply adequate number of power and data outlets in learning		2					Comments		
spaces? 1 2 3 4	Very unsatisfactory - Outlet configuration does not support digital devices throughout school (1 per wall) Unsatisfactory - Outlet configuration support digital devices only in certain areas of school (2 per wall) Average - Outlet configuration support digital devices but not enough capacity throughout school (3 per wall) Satisfactory - Outlet configuration support digital devices with adequate coverage and capacity throughout school (>3 per wall) Very Satisfactory - Excellent outlet configuration to support digital devices throughout school (>3 per wall)							Two per wall. Power strips used for more power distrib	1.00 ution.	2.00
N/A	Does not apply							1		

13 - Technolog	gy (cont.)	1	2	3	4	5	N/	'A		
13.3 Are there of	adequate charging locations for devices?		2					Comments	1.00	2.0
1	Very unsatisfactory - No centralized charging location			•				Charging carts seen in school but few in studios.		
2	Unsatisfactory - Centralized charging location, but inadequate in size for number of devices									
3	Average - Charging cart or tower but not adequately sized for number of devices									
4	Satisfactory - Charging cart or tower not centralized									
5	Very Satisfactory - Charging cart or tower located centralized location. Excellent condition									
N/A	Does not apply									
ls there ad	dequate AV for presentations spaces – cafeteria and gym?		2					Comments	1.00	2.0
1	Very unsatisfactory - AV not present in one or more							Roll in a TV on mobile cart. There is a sound system pre	esent.	
	space									
2	Unsatisfactory - AV undersized for room, poor condition									
3	Average - Adequately sized / poor condition OR AV									
	undersized / adequate condition									
4	Satisfactory - Good size, good condition									
5	Very Satisfactory - Generous sized, excellent condition									
N/A	Does not apply				1					
13.5 Is there dig	gital media signage at the reception area?	1						Comments	0.00	0.0
1	Very unsatisfactory - No digital media present in reception area									
2	Unsatisfactory - Undersized, poor condition									
3	Average - Adequately sized / poor condition OR									
	undersized / adequate condition									
4	Satisfactory - Media signage present, good sized, good condition									
5	Very Satisfactory - Generously sized, excellent condition									
N/A	Does not apply							1		

14 - Administr	ation Spaces	1	2	3	4	5	N/A		20.00	50%
ls there a r 14.1 visitors?	eception area that functions as a security checkpoint for all							Comments	1.00	
1	Very unsatisfactory - No security checkpoint		1			ļ				
2	Unsatisfactory - Checkpoint is too small, poor condition									
3	Average - Needs updates or renovations to function well									
4	Satisfactory - Good size, good condition									
5	Very Satisfactory - Generous size, excellent condition									
N/A	Does not apply									
Does the a	dministration area feel welcoming?			0				6 .		
14.2				3				Comments	1.00	3.00
1	Very unsatisfactory - No welcome space							Good size, but needs updates to feel less dated.		
2	Unsatisfactory - Too small, poor lighting and									
	transparency, limited informal seating, poor condition									
3	Average - Adequate size and layout, needs updates or									
	renovations to feel welcoming									
4	Satisfactory - Good size and layout, good lighting and									
	transparency, informal seating provided									
5	Very Satisfactory - Generous size and layout, plenty of									
	light and transparency, informal seating provided,									
	excellent condition									
N/A	Does not apply				,	,		1		
	spaces that require it, does the administration area have			3				Comments		
adequate	acoustic privacy?							33	1.00	3.00
1	Very unsatisfactory - No acoustic separations									
2	Unsatisfactory - Acoustic separations do not perform									
	well									
3	Average - Some acoustic separations function okay, but									
	portions need updates or renovations									
4	Satisfactory - Good acoustic separations									
5	Very Satisfactory - Excellent acoustic separations									
N/A	Does not apply		ı							
Are conference	ence rooms easily accessed for public / parent use?			3				Comments		
				Ŭ				Comments	1.00	3.00
1	Very unsatisfactory - Not accessible for public/parent							One conference room across the hall from main office	Э.	
	use									
2	Unsatisfactory - Limited access, no transparency, poor									
	condition, difficult to find									
3	Average - Adequate accessibility, needs updates or									
	renovations to function well									
4	Satisfactory - Good accessibility, good transparency,									
	good size and condition									
5	Very Satisfactory - Excellent accessibility, excellent									
	transparency, generous size, excellent condition									
N/A	Does not apply									